

TERRATEC S.I. Ltd

**SITE INVESTIGATION.
GEO-ENVIRONMENTAL TESTING.
01273 517020**

Unit E, Newhaven Workshops, Beach Close, Newhaven, East Sussex. BN9 0BY
Reg. No. 8047143 terratecsiltltd@live.co.uk Vat No 945 6866 69

Mr P Meredith,
55,57 The High Street,
Arundel,
West Sussex

20th July 2015

Dear Sir,

RE: SITE AT REAR OF ARUNDEL HIGH STREET, WEST SUSSEX.

*As instructed we visited the above site and conducted a BRE 365 Soakage test to aid the design of soakaways for the proposed development.

*We report our findings below:

*The soakage test was carried out in a hand dug pit measuring Length 800mm Width 400mm and depth of 1.2m

*We encountered the Chalk at 900mm depth.

*The half empty time was 35minutes.

*This gave a Porosity Value of 5.27×10^{-5} m/second at 1.2m depth.

*This value indicates that soakaways will work very well for the proposed development and we would recommend a storm crate type system be used.

*If you have any further questions, please contact us.

Yours faithfully,



Dave J Thorpe.
Terratec S.I.ltd