

Schedule of Materials

WALLS Bricks: Soft Red, imperial size 228 x 108 x 68 mm, by Imperial Bricks Ltd



Mortar: 1:1:6 OPC; hydraulic lime; building sand

ROOF and WEATHER TILING Slates: Matalade natural slate, blue/grey
250 x 500 x 5 mm



RAINWATER GOODS 112 MM Cascade Roundstyle Cast Iron Style in black



Statement of Detail

Windows to be factory manufactured Conservation Sliding Sash system timber by Mumford and Wood. Colour white. See detail on Drwg no 13577/107A

Front door to be timber panelled door, decorated white to match windows above.

Window external reveals to be 50mm with extended timber sills 60mm and capillary groove.

Ground Floor windows to have Soldier course

Note: The window and door design are as consented in AB/5/18PL

Brickwork to be Soft Reds by Imperial Bricks Ltd, laid in Flemish Bond, alternate headers and stretchers used in each course. Mortar to be 1:1:6 OPC: hydrated lime: sand with flush finish.

Rainwater Goods to be from the Cascade 112mm range in Black, fitted strictly in accordance with manufacturers' instructions on rafter feet brackets discharging into existing downpipe to the North elevation.

 ANDREW FULLER ASSOCIATES		
<i>Chartered Surveyors</i>		
Norton Studio, School Lane Arundel, West Sussex BN18 9DR tel: 01903 885444 email: info@a-fuller.co.uk www.andrewfuller.co.uk		
 Job Title Norton Studio, School Lane, Arundel Proposed new dwelling		
Client Mr A Fuller		
Drawing Name Schedule of Materials		
Drawing Status Construction		
Drawn by AF Date 10/19		
Checked by Date		
Drawing Scale		
Drawing No 13577/106 Status Revision A		