

AB/125/15/L
DOE

1. 5401 TARRANT STREET (South Side) ----- 5.6.69. Nos 43 to 47 (odd) - No 49 TQ 0107 1/57

II GV

2. Late C18. Terraced houses. Stuccoed Front, remainder nodular flint with brick dressings. Slate roof. 3 storeys. Brick modillion eaves cornice. Stringcourses above ground and first floors. 7 ranges of double-hung sash winnows with glazing bars on 1st and 2nd floors, except that central window on 2nd floor of No 45 is blocked, and No 47 has no glazing bars. No 43 has a segmental bay with 3 double-hung sash windows with glazing bars on the ground floor, and door with 6 fielded panels and blind fanlight with panelled reveals in doorcase with Tuscan columns taking dentilled pediment. No 45 has a canted bay window with 3 double-hung sash windows with glazing bars, and a 6-panelled door (partly glazed) with panelled reveals in a moulded frame with pediment. No 47 has a shop front consisting of a partly glazed door with marginal glazing bars and oblong fanlight in moulded surround with pediment over, and 1 oblong bay window with glazing bars and cornice. No 49 has an order of Tuscan pilasters on ground floor, supporting an entablature which frames a fascia board, and breaks upward in middle in semi-circular arch. The pilasters are irregularly disposed in 3 pairs, framing 2 doors with 2 moulded panels each and partly glazed, in deep reveals and up 2 ashlar steps. 1 door is flanked by a plate glass shop window with rounded shoulders, over a plinth with a recessed and moulded panel.

Nos 43 to 47 (odd) and wall between Nos 49 and 51 form a group.

National Grid Reference: TQ 01700 07013