



Malttravers St

Bakers Arms Hill

21

19

17

IC1

drain to be relayed at 1:60

Existing drain from IC1 to IC2 falls at 1:12
IC1 Invert to be lowered by 170mm to allow relayed drain to fall at 1:60
IC1 to have new dbl seal cover + frame.

Existing cover to IC2 to be replaced with new metd wt cover + frame

IL of IC2 to remain as existing.

All this existing drainage and ICs to remain as existing.



3712	
Proposed Works at 17 Malttravers St. ARUNDEL BN18 9AP	
Drainage Plan Extng + Proposed 1:200 Feb'21	17