

No.31 Maltravers Street - Door Schedule

JOB NR.	DRAWING NR.	ISSUE	REV	PREPARED BY:	ISSUE DATE
4120	GA 901	PL	3	PC	02.06.20

Tankerton Works
12 Argyle Walk
London WC1H 8HA



GENERAL NOTES

1	To be read in conjunction with plan layouts GA 303, GA 304, GA 305 & GA 306 and door elevation drawings DA 401 - DA 404.
2	All new frames to be in hardwood.
3	Structural opening is measured to back of frame.
4	To be read in conjunction with Ironmongery Schedule
5	
6	

REV	DATE	NOTES
1	03/2020	First Issue
2	04/2020	Dimensions updated. Types M & N added.
3	05/2020	Updated in accordance with Client changes.

DOOR NR.	ROOM SERVED	ROOM NR.	INTERNAL/EXTERNAL	TYPE	LEAF	STRUCTURAL OPENING		LEAF SIZE			LEAF 2 (mm)	DOOR OPERATION	LINING DEPTH (mm)	ACOUSTIC RATING	FIRE RATING	SELF-CLOSING	SPECIFICATION						Drawing References			IRONMONGERY SET	NOTES
						WIDTH	HEIGHT	WIDTH (mm)	HEIGHT (mm)	THICKNESS (mm)							DOOR FACE PROFILE - SIDE 1	DOOR FACE PROFILE - SIDE 2	DOOR FACE FINISH - SIDE 1	DOOR FACE FINISH - SIDE 2	DOOR FRAME	DOOR GLAZING	ELEVATION	HEAD	JAMB		
DB.	01	Annex Kitchen/ Living	RB.01	External	B	1	1585	2000	840	1928	44mm	-	Single swing	EXISTING	-	-	-	Hardwood French Door with Side-Hung Side panel	See SIDE 1	Painted off-white	Painted off-white	Hardwood	YES	DA 401			Doorset with glazed sidelight to be installed in enlarged, existing window opening. Toughened glass. 50mm restrictor to be fitted to side panel.
DB.	02	Annex Storage	RB.02	Internal	H	1	810	2000	726	1918	44mm	-	Single swing	EXISTING	-	-	-	Solid hardwood door, tongue and groove boarding in frame	See SIDE 1	Painted off-white	Painted off-white	Hardwood	-	DA 403			Doorset to be installed in enlarged, existing opening.
DB.	03	Annex Shower Room	RB.04	Internal	H	1	810	2000	726	1958	44mm	-	Single swing	100	-	-	-	Flush, routed out MDF on solid core	Flush, routed out MDF on solid core	Painted off-white	Painted off-white	Hardwood	-	DA 403			
DB.	04	Workshop	RB.05	Internal	H	1	810	2000	726	1558	44mm	-	Single swing	100	-	-	-	Flush, routed out MDF on solid core	Flush, routed out MDF on solid core	Painted off-white	Painted off-white	Hardwood	-	DA 403			Rub down woodwork, make necessary repairs and redecorate.
DB.	05	Workshop Store	RB.06	Internal	H	1	810	2000	726	1958	44mm	-	Single swing	100	-	FD30	-	Flush, routed out MDF on solid core	Flush, routed out MDF on solid core	Painted off-white	Painted off-white	Hardwood	-	DA 403			
DB.	06	Larder	RB.08	Internal	H	1	810	2000	726	1958	44mm	-	Single swing	100	-	FD30	-	Flush, routed out MDF on solid core	Flush, routed out MDF on solid core	Painted off-white	Painted off-white	Hardwood	-	DA 403			
DB.	07	Stair to Kitchen	RB.07	Internal	H	1	810	2000	726	1958	44mm	-	Single swing	100	-	FD30	YES	Flush, routed out MDF on solid core	Flush, routed out MDF on solid core	Painted off-white	Painted off-white	Hardwood	-	DA 403			
DB.	08	Games Room	RB.09	External	C	2	1810	2000	863	1928	44mm	863	Single swing	EXISTING	-	-	-	Glazed, hardwood	See SIDE 1	Painted off-white	Painted off-white	Hardwood	YES	DA 401			New doorset to be accommodated in existing opening. Toughened glass.
DB.	09	Home office	RB.10	External	D	1	EXISTING	EXISTING	Site dim	Site dim	44mm	-	Single swing, Stable	EXISTING	-	-	-	Stable-style solid hardwood door. Tongue and groove boarding in frame. Glazed top leaf.	See SIDE 1	Painted off-white	Painted off-white	Hardwood	YES	DA 402			Toughened glass.
DB.	10	Shed	RB.11	External	A	1	910	2000	826	1958	44mm	-	Single swing	215mm	-	-	-	Solid oak door, Tongue and groove boarding in frame	See SIDE 1	Untreated	Untreated	Hardwood	-	DA 401			
DB.	11	Annex Entrance	RB.12	External	A	1	810	2000	726	1958	44mm	-	Single swing	Site dim	-	-	-	Tongue and groove	See SIDE 1	Untreated	Untreated	Hardwood	-	DA 401			
DB.	12	Garden Storage	RB.12	External	A	1	EXISTING	EXISTING	Site dim	Site dim	Site dim	-	Single swing	Site dim	-	-	-	Tongue and groove	See SIDE 1	Untreated	Untreated	Hardwood	-	DA 401			
DB.	13	Garden	-	External (Gate)	N	1	910	-	826	1840	44	-	Single swing	-	-	-	-	Ledged and braced oak gate.	Ledged and braced oak gate.	Untreated	Untreated	Hardwood	-	DA 405/ DA 406			Bracing to garden side.
DB.	14	Garden	-	External (Gate)	EXISTING	1	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	-	Single swing	EXISTING	-	-	-	-	-	-	-	-	-	-	-	-	
DB.	15	Games Room	RB.09	Internal	G	1	EXISTING	EXISTING	Site dim	Site dim	Site dim	-	Single swing	EXISTING	-	FD30	-	Glazed, softwood	Glazed, softwood	Painted off-white	Painted off-white	Hardwood	YES	DA 403			Toughened glass.
DG.	01	Entrance Hall	RQ.01	External	EXISTING	1	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	-	Single swing	EXISTING	-	-	-	-	-	Painted to match existing	Painted to match existing	EXISTING	-	-			Existing door retained to be re-hung on left. Rub down woodwork, make necessary repairs and redecorate.
DG.	02	Family Room	RQ.02	Internal	H	1	EXISTING	EXISTING	EXISTING	EXISTING	44mm	-	Single swing	Site dim	-	FD30	-	Flush, routed out MDF on solid core	Flush, routed out MDF on solid core	Painted off-white	Painted off-white	Hardwood	-	DA 403			New doorset to be accommodated in existing opening.
DG.	03	Family Room Cupboard	RQ.02	Internal	H	1	810	2100	726	2058	44mm	-	Single swing	100	-	-	-	Flush, routed out MDF on solid core	Flush MDF on solid core - rear face	Painted off-white	Painted off-white	Hardwood	-	DA 403			
DG.	04	Dining Area	RQ.05	External	E	2	3610	2135	by manufacturer	by manufacturer	See door style	1000	Single swing in glazed screen	EXISTING	-	-	-	Crittall-style, painted galvanised steel	Crittall-style, painted galvanised steel	Crittall-style, painted galvanised steel	Crittall-style, painted galvanised steel	Crittall-style, painted galvanised steel	YES	DA 402			Powder-coated galvanised steel double-glazed screen. Toughened glass.

No.31 Maltravers Street - Door Schedule

JOB NR.	DRAWING NR.	ISSUE	REV	PREPARED BY:	ISSUE DATE
4120	GA 901	PL	3	PC	02.06.20

GENERAL NOTES

1	To be read in conjunction with plan layouts GA 303, GA 304, GA 305 & GA 306 and door elevation drawings DA 401 - DA 404.
2	All new frames to be in hardwood.
3	Structural opening is measured to back of frame.
4	To be read in conjunction with Ironmongery Schedule
5	
6	

REV	DATE	NOTES
1	03/2020	First Issue
2	04/2020	Dimensions updated. Types M & N added.
3	05/2020	Updated in accordance with Client changes.

DOOR NR.	ROOM SERVED	ROOM NR.	INTERNAL/EXTERNAL	TYPE	LEAF	STRUCTURAL OPENING		LEAF SIZE			LEAF 2 (mm)	DOOR OPERATION	LINING DEPTH (mm)	ACOUSTIC RATING	FIRE RATING	SELF-CLOSING	SPECIFICATION						Drawing References			IRONMONGERY SET	NOTES
						WIDTH	HEIGHT	WIDTH (mm)	HEIGHT (mm)	THICKNESS (mm)							DOOR FACE PROFILE - SIDE 1	DOOR FACE PROFILE - SIDE 2	DOOR FACE FINISH - SIDE 1	DOOR FACE FINISH - SIDE 2	DOOR FRAME	DOOR GLAZING	ELEVATION	HEAD	JAMB		
DG.	05	Living Area	RQ.06	Internal	J	2	1545	2100	by manufacturer	by manufacturer	44mm	by manufacturer	Single swing	100	-	FD30	-	Crittall-style, painted galvanised steel	Crittall-style, painted galvanised steel	Crittall-style, painted galvanised steel	Crittall-style, painted galvanised steel	Crittall-style, painted galvanised steel	YES	DA 403			Powder-coated galvanised steel single-glazed screen. Toughened glass.
DG.	06	Living Room Cupboard	RQ.06	Internal	H	1	460	2100	376	2058	44mm	-	Single swing	100	-	-	-	Flush, routed out MDF on solid core	Flush MDF on solid core - rear face	Painted off-white	Painted off-white	Hardwood	-	DA 403			
DG.	07	Under-stair cupboard	RQ.01	Internal	H	1	750	1400	726	1358	44mm	-	Single swing	100	-	FD30	-	Flush, routed out MDF on solid core	Flush MDF on solid core - rear face	Painted off-white	Painted off-white	Hardwood	-	DA 403			
DG.	08	WC	RQ.08	Internal	H	1	810	2100	726	2058	44mm	-	Single swing	100	-	-	-	Flush, routed out MDF on solid core	Flush out MDF on solid core	Painted off-white	Painted off-white	Hardwood	-	DA 403			
DG.	09	Cloaks	RQ.07	Internal	H	1	810	2100	726	2058	44mm	-	Single swing	100	-	FD30	-	Flush, routed out MDF on solid core	Flush, routed out MDF on solid core	Painted off-white	Painted off-white	Hardwood	-	DA 403			
D1.	01	Home Office	R1.07	Internal	K	1	1250	2100	by manufacturer to suit opening	by manufacturer to suit opening	44mm	-	Single pocket door	100	-	FD30	-	Flush, routed out MDF on solid core	Flush, routed out MDF on solid core	Painted off-white	Painted off-white	-	YES	DA 404			Concealed Frame Pocket Door by Selo
D1.	02	Bedroom 2 En-suite Shower Room	R1.03	Internal	H	1	810	2100	726	2058	44mm	-	Single swing	100	-	-	-	Flush, routed out MDF on solid core	Flush, routed out MDF on solid core	Painted off-white	Painted off-white	Hardwood	-	DA 403			
D1.	03	Bedroom 2	R1.02	Internal	H	1	810	2100	726	2058	44mm	-	Single swing	100	-	FD30	-	Flush, routed out MDF on solid core	Flush, routed out MDF on solid core	Painted off-white	Painted off-white	Hardwood	-	DA 403			
D1.	04	Master Bedroom	R1.04	Internal	H	1	810	2100	726	2058	44mm	-	Single swing	100	-	FD30	-	Flush, routed out MDF on solid core	Flush, routed out MDF on solid core	Painted off-white	Painted off-white	Hardwood	-	DA 403			
D1.	05	Master Bedroom Dressing Room	R1.05	Internal	L	1	750	2100	by manufacturer to suit opening	by manufacturer to suit opening	44mm	-	Single pocket door	100	-	-	-	Flush, routed out MDF on solid core	Flush, routed out MDF on solid core	Painted off-white	Painted off-white	-		DA 404			Concealed Frame Pocket Door by Selo
D1.	06	Master Bedroom En-suite Bathroom	R1.06	Internal	H	1	810	2100	726	2065	44mm	-	Single swing	100	-	-	-	Flush, routed out MDF on solid core	Flush, routed out MDF on solid core	Painted off-white	Painted off-white	Hardwood	-	DA 403			
D1.	07	Master Bedroom En-suite Bathroom	R1.06	External	F	1	EXISTING	EXISTING	Site dim	Site dim	44mm	-	Single swing	EXISTING	-	-	-	Glazed, hardwood	Glazed, hardwood	Painted off-white	Painted off-white	Hardwood	-	DA 403			New doorset to be accommodated in existing opening. Opening fanlight over.
D1.	08	Master Bedroom	R1.04	External	F	1	EXISTING	EXISTING	850mm	Site dim	44mm	-	Single Swing	EXISTING	-	-	-	Glazed, hardwood	Glazed, hardwood	Painted off-white	Painted off-white	Hardwood	-	DA 403			New doorset to be accommodated in existing opening. Opening fanlight over.
D1.	09	Landing	R1.01	Internal	-	1	710	1500	626	1458	44mm	-	Removable panel	100	-	FD30	-	Flush, routed out MDF on solid core	Flush MDF on solid core - rear face	Painted off-white	Painted off-white	Hardwood	-	-			
D1.	10	Master Bedroom	R1.04	Internal	-	-	810	2100	-	-	-	-	Framed opening	100	-	-	-	-	-	-	-	Hardwood	-	-			Framed opening with architrave.
D1.	11	Master Bedroom	R1.05	Internal	-	-	810	2100	-	-	-	-	Framed opening	100	-	-	-	-	-	-	-	Hardwood	-	-			Framed opening with architrave.
D1.	12	Bedroom 2	R1.02	Internal	-	-	810	2100	-	-	-	-	Framed opening	100	-	-	-	-	-	-	-	Hardwood	-	-			Framed opening with architrave.
D1.	13	Master Bedroom En-suite Bathroom	R1.06	Internal	M	1	EXISTING	EXISTING	Site dim	Site dim	25mm	Equal leaves	Single swing	-	-	-	-	-	-	-	-	Hardwood	-	DA 404			
D2.	01	Store/ Boiler	R2.02	Internal	H	1	710	1700	626	1668	44mm	-	Single Swing	100	-	FD30	-	Flush, routed out MDF on solid core	Flush MDF on solid core - rear face	Painted off-white	Painted off-white	Hardwood	-	DA 403			
D2.	02	Bedroom 4	R2.03	Internal	H	1	810	2000	726	2058	44mm	-	Single Swing	100	-	FD30	-	Flush, routed out MDF on solid core	Flush, routed out MDF on solid core	Painted off-white	Painted off-white	Hardwood	-	DA 403			
D2.	03	Bedroom 3	R2.04	Internal	H	1	810	2000	726	2058	44mm	-	Single Swing	100	-	FD30	-	Flush, routed out MDF on solid core	Flush, routed out MDF on solid core	Painted off-white	Painted off-white	Hardwood	-	DA 403			
D2.	04	Family Bathroom	R2.06	Internal	H	1	810	2000	726	2058	44mm	-	Single Swing	100	-	FD30	-	Flush, routed out MDF on solid core	Flush, routed out MDF on solid core	Painted off-white	Painted off-white	Hardwood	-	DA 403			
D2.	05	Under Eaves Storage	R2.05	Internal	N	2	716	850	By manufacturer	By manufacturer	25mm	by manufacturer	Pocket Bi-Parting	100	-	-	-	Flush, routed out MDF on solid core	Flush MDF on solid core - rear face	Painted off-white	Painted off-white	Hardwood	-	DA 404			

Tankerton Works
12 Argyle Walk
London WC1H 8HA

