

[REDACTED]

From: Max Thoms [REDACTED]
Sent: 23 March 2021 11:18
To: Planning.Responses [REDACTED]
Cc: Chris Hawkins [REDACTED]; Billy Hawkins [REDACTED]
Subject: RE: Planning Decision on AB/125/20/L : 19 Maltravers Street FAO: Zac Denton

Dear Mr Denton,

Further to the recent listed building consent granted for works at 19 Maltravers St, Arundel ref: AB/125/20/L, please see discharge of conditions below:

3. The roof will have a grey GRP coating and the upstands will be detailed with Code 5 lead flashing laid in accordance with the LSA guidelines. Where possible, the lead will extend underneath the timber cladding and the lead will be chased into the render/brickwork a minimum 25mm to the rear elevation.

4. The application shows a brickwork finish. My clients wish to amend this to a rendered finish to the small areas either side of the rear elevation door. The render mix will be 1:3 (lime: sand) and painted in a colour to match the original rear elevation. The rear elevation of the property is rendered and render would be more in keeping with the appearance of the property. The brickwork sections to the lower ground floor of the rear are red stock bricks and are not of significant heritage importance in my opinion. Please advise if you need anything further with regards to this amendment.

5. The existing external door providing access from the kitchen to the garden will be carefully removed and re-instated. IMG 9457 shows the timber slim line double glazed door.

6. Details of materials to be used are below:

- Skylight – 1000 x 2000mm aluminium double glazed skylight. See attached link <https://toughenedglasssystems.co.uk/product/skylights-rooflights-1000-1000/>
- Roof – grey GRP roof covering Tak-shield or Re-tek or similar. No slate shingles will be installed owing to the 5 degree pitch of the flat roof.
- Skylight – details above
- Guttering – to the rear only – black uPVC to match rear.
- Door – original timber door to be removed and re-instated.
- Fascia – Timber painted.

If there is anything further you require, then please can you set this out and I can provide you with the info you need.

7. The existing door providing access into the kitchen will be blocked up and a new 1000 x 800mm joinery quality timber four panelled window will be installed. The glass will be laminated. Please see section AA attached showing the location and height of the window etc. Again, if you need anything further, please let me know.

I trust the above is clear but if you have any queries, please let me know. My mobile is 07581784651 if you wish to discuss further.

Kind Regards,

Max

Max Thoms BSc (Hons) MRICS
Chartered Building Surveyor

Stuart Radley Associates
Unit 5, Tungsten Building
George Street
Portslade
BN41 1RA

01323 818888 / 07581 784651

This email, and any files transmitted with it, is confidential and is intended solely for the use of the individual or entity to which it is addressed.

If you receive this in error please notify info@stuartradleyassociates.co.uk immediately and do not copy, forward or disclose its contents to any other party.

This email has been swept for the presence of computer viruses but, nevertheless, any attachment to this email may contain a virus that our software has failed to identify. You are advised to carry out your own antivirus checks before opening any attachment. Stuart Radley Associates accepts no liability in respect of any loss, cost, damage or expense suffered as a result of accessing this message or any of its attachments.