

27/4/20

Good afternoon Diane

In relation to the property of 23 Fitzalan road Arundel

I carried out the work in question with the previous owners instruction.

It was done around the summer of 2014. I do not have any relative paperwork going back that far to give to you, sorry for that.

The hard standing was created on a compacted sub base of 250mm of type 1/mot

Then 50mm of coarse sand compacted and screeded .

The finish layer of concrete blocks are Marshalls driveway blocks 50mm.

All drainage is run to the raised flower borders created specifically for that purpose.

The tarmac and dropped kerb created on the threshold was something I wasn't part of.

This was done by another contractor employed by the previous owners and completed after the hard standing.

I did not have the relevant qualifications of insurances to complete this part

I hope this is satisfactory and assists in you in your current situation.

Kind regards

Fred Taylor

Taylormade Groundworks