

Schedule of Materials for Byass House, 59 Maltravers street, Arundel, BN18 9BQ - Planning Application Reference: AB/121/16/L

This schedule of materials is to contribute to the satisfaction of Condition 3 detailed on the consent referred to by the above application number.

Walls

The brick walls to the extension use an Ibstock Swanage Imperial Red Stock 68mm brick to match the main house, have been laid in Flemish bond with a weather struck lime mortar joint.

Photograph of sample panel of brickwork agreed on site with Dr Ian Wightman on the 18th May 2017.



The coping stone used is a Haddonstone T720 as agreed with Dr Wightman during a site visit on 18th May 2017.

Roof

The new flat roof is covered with glass reinforced plaster (GRP) as annotated in the Materials Schedule on approved drawing no. 15837/04A.

Internal doors

The new doors to the cupboards, en-suite toilets and second floor as shown on approved drawings 15837/04A, 15837/05A and superseding drawing

15837/08A under consented application reference AB/81/17/L, are Georgian Style softwood 6 panel doors, that have been hand painted.



ABOUT US | HOW TO BUY | TRADE CUSTOMERS

Contact your local depot

Request a brochure

Home

Advice & Inspiration

Kitchens

Appliances

Doors & Joinery

Hardware

Flooring

Bathroom cabinets

Home > Doors and joinery collection > Internal doors > Softwood doors > 6 Panel Clear Pine door



6 Panel Clear Pine door

Paint to suit any colour scheme or stain to keep the natural grain visible for an authentic feel.

- Constructed using engineered pine stiles and rails
- Ready for finishing with varnish, stain, paint or Osmo Oil

H1981mm x W610mm (6' 6" x 2' 0")	DIS1330
F Standard	
H1981mm x W686mm (6' 6" x 2' 3")	DIS1340
F Standard	
H1981mm x W762mm (6' 6" x 2' 6")	DIS1360
F Standard	
H1981mm x W838mm (6' 6" x 2' 9")	DIS1370
F M Standard	
H2040mm x W626mm	DIS1730 ↑
F Standard	
H2040mm x W726mm	DIS1740 ↑
F Standard	
H2040mm x W826mm	DIS1780 ↑
F M Standard	

F = FSC®
↑ = Subject to availability

Save



Download Technical Specification

[379.40K]

All existing doors have been repaired and decorated and rehung.

ARUN DISTRICT COUNCIL AB/45/18/DOC