

REASONS FOR PROPOSED TREE WORK

T1 Cherry Plum along rear fence line:

- Shorten apical and lateral growth by a maximum of 1m
 - Current height 7m
 - Finished height 6m
 - Average crown spread 3m
 - Average reduced crown spread 2m
- Crown thin by 15% leaving a maximum wound of 25mm diameter

The tree is beginning to get big for its location with branches extending over a number of properties; the tree work specification is intended to retain the tree whilst reducing its overall crown size and density