

Garden on north side flanked by walls of beach flint with red brick dressings and Pulborough stone coping. 2 Pulborough stone piers at north ends with stringcourses 3/4 way up, coved cornices, and recessed square panels with plain shields in low relief.

1.
5401

TQ 0107 1/56

II

TARRANT STREET
(South Side)

No 33

ARUN DISTRICT COUNCIL

No.	AB	58	10	L
RECEIVED				

2.
Late C18. Red brick. East elevation nodular flint with red brick dressings. Hipped tile roof.

3 storeys. Brick modillion eaves cornice. Ground floor has canted bay with 3 double-hung sash windows, and cornice over, and 1 6-panelled door in moulded frame with pediment supported by consoles, and elaborate mid-C19 knocker. Wooden beam flush with brickwork above all ground floor openings suggest that they might be later, as does a double-hung sash cellar window very deeply recessed under the canted bay. 2 flush-framed double-hung sash windows with glazing bars on 1st and 2nd floors.

1.
5401

TQ 0107 1/57

II

5.6.69.

TARRANT STREET
(South Side)

Nos 43 to 47 (odd)
No 49

GV

2.
Late C18. Terraced houses. Stuccoed front, remainder nodular flint with brick dressings. Slate roof.

3 storeys. Brick modillion eaves cornice. Stringcourses above ground and first floors. 7 ranges of double-hung sash windows with glazing bars on 1st and 2nd floors, except that central window on 2nd floor of No 45 is blocked, and No 47 has no glazing bars.

No 43 has a segmental bay with 3 double-hung sash windows with glazing bars on the ground floor, and door with 6 fielded panels and blind fanlight with panelled reveals in doorcase with Tuscan columns taking dentilled pediment.

No 45 has a canted bay window with 3 double-hung sash windows with glazing bars, and a 6-panelled door (partly glazed) with panelled reveals in a moulded frame with pediment.

No 47 has a shop front consisting of a partly glazed door with marginal glazing bars and oblong fanlight in moulded surround with pediment over, and 1 oblong bay window with glazing bars and cornice.

No 49 has an order of Tuscan pilasters on ground floor, supporting an entablature which frames a fascia board, and breaks upward in middle in semi-circular arch. The pilasters are irregularly disposed in 3 pairs, framing 2 doors with 2 moulded panels each and partly glazed, in deep reveals and up 2 ashlar steps. 1 door is flanked by a plate glass shop window with rounded shoulders, over a plinth with a recessed and moulded panel.

Nos 43 to 47 (odd) and wall between Nos 49 and 51 form a group.