

OFFERING GREATER CHOICE, THE CAST IRON STYLE DOMESTIC RAINWATER RANGE IS AVAILABLE IN 3 DESIGN OPTIONS TO ADD A TOUCH OF HERITAGE TO BOTH PERIOD AND CONTEMPORARY PROPERTIES.

The range includes: 106mm Prostyle, which is based on the Ogee design, 112mm Roundstyle and, for larger or steeper roofs, a 115mm Deepstyle profile, all utilising the 68mm downpipes, fittings and six hoppers moulded to traditional Ogee, Bath and Gothic designs.

106mm PROSTYLE

The sleek lines and modern styling result in a contemporary finish with a quality cast iron look and feel.

112mm ROUNDSTYLE

Blends perfectly with traditionally styled buildings, being virtually indistinguishable from more expensive cast iron materials.


115mm DEEPSTYLE

A higher capacity semi elliptical rainwater system, providing greater drainage efficiency on larger roof areas.




68mm DOWNPIPE


The traditionally styled 68mm downpipe system, with 1.8m round pipe, connectors and shoes, are fixed to the gutter with a range of offsets and hoppers.



106mm Prostyle



112mm Roundstyle



115mm Deepstyle

- Authentic detailing and finish on downpipe, guttering, hoppers and fittings
- Fully compatible with Cast Iron Soil System and traditional cast iron
- Available in 3 design options
- Incorporates 68mm Downpipe
- Choice of six hoppers
- 10 year guarantee

Cast Iron Style Gutter Capacities

		Gutter Flow Capacity Litres per second		Maximum Roof Area m ²	
		Level	1:600	Level	1:600
106mm Prostyle	Outlet at one end	2.05	2.55	97	121
	Outlet at centre	4.1	5.1	195	242
112mm Roundstyle	Outlet at one end	1.00	1.30	48	62
	Outlet at centre	1.82	2.43	87	116
115mm Deepstyle	Outlet at one end	1.88	2.30	90	110
	Outlet at centre	3.75	4.58	180	220

BRETT MARTIN