

1.
5401

TQ 0107 1/16

II*

26.3.49.

GV

HIGH STREET
(West Side)

No 61
Railings to No 61

2.
C18. Town house. Red brick with rubbed brick voussoirs. Hipped tile roof. Mid C19 red brick chimneys. 3 storeys. Eaves cornice with closely-spaced wooden consoles. 5 ranges of double-hung sash windows with glazing bars. Doorway with unfluted Roman Doric columns, dentilled pediment, semi-circular fanlight and 6-panelled door. 3 ashlar steps up to door. Iron railings to south and north of doorway with 2 urn finials and 4 thicker posts with Doric capitals.

Nos 51 to 67 (odd) form a group.

1.
5401

TQ 0107 1/17

II

26.3.49.

GV

HIGH STREET
(West Side)

No 63

2.
Early C18. Stuccoed. Pitched tile roof with projecting eaves rendered over, cat-slide behind. 2 storeys with attics. 2 ranges of double-hung sash windows with glazing bars, all late C18, except for north window on 1st floor, which is early C18. Late C18 projecting shop window with glazing bars, to north of door. Doorway up 4 ashlar steps, dentilled pediment taken on consoles, frieze with Chinoiserie basketwork motif. 6-panelled door, partly glazed. 1 planked door, and 1 window to basement.

Nos 51 to 67 (odd) form a group.

1.
5401

TQ 0107 1/18

II

5.6.69.

GV

HIGH STREET
(West Side)

No 65

2.
Early C19. Stuccoed. Hipped slate roof. 3 storeys and attic. Cornice and blocking course. 2 ranges of windows with moulded surrounds, those on 1st floor French with rectangular fanlights, marginal glazing bars, and a moulded cornice, those on 2nd floor double-hung sashes with glazing