

1.
5401

MALTRAVERS STREET
(North Side)

Retaining wall to garden
on South and East sides
of No 60

TQ 0107 1/163

II

GV

2.
Early C19. Red brick: Pulborough stone coping. In King Street it becomes nodular flint with Pulborough stone coping.

Nos 46 to 62 (even) and retaining wall at No 60 form a group with Nos 45 to 63 (odd) and 77 to 83 (odd) and pavements and railings.

1.
5401

MALTRAVERS STREET
(North Side)

No 72 (Rock Cottage)

TQ 0107 1/97

II

GV

2.
Mid C19. Cottage. South elevation galleted nodular flint, with yellow brick dressings. Hipped slate roof. North elevation beach flint, with red brick dressings. Red brick chimney with yellowbrick cornicing.
2 storeys. Yellow brick modillion eaves cornice. 2 ranges of double-hung sash windows with glazing bars to south. 1 4-panelled door with semi-circular fanlight, and blocked window above.
2 storey wing to north.

Nos 64 to 84 (even) form a group together with the wall opposite on the south side.

1.
5401

MALTRAVERS STREET
(North Side)

Nos 74 to 84 (even)

TQ 0107 1/53

II

GV

2.
Early C19. Terraced cottages. South elevation stuccoed: remainder nodular flint with red brick dressings. Slate roofs (Nos 74-8 hipped: Nos 80-4 pitched, and steeper). Late C19 red brick chimneys with much cornicing. South elevation has 2 storeys and basement. Stucco stringcourse above ground floor, and stucco cornice to eaves with parapet. Pilasters between each house and at ends. 1 window range each, all double-hung sash windows with glazing bars in moulded stucco surrounds,