

1.
5401

TARRANT STREET
(North Side)

No 52

TQ 0107 1/293

II

GV

2.

Mid C19. Red brick with grey brick headers in recessed panels. Pitched slate roof. Red brick chimneys.

3 storeys and semi-basement. 2 brick modillion eaves cornices, 1 above other, at eaves level. 2 double-hung sash windows with glazing bars on 2nd floor. 1 tripartite double-hung sash window with glazing bars on 1st floor, flanked by semi-circular panels of grey brick headers. 1 double-hung sash window with glazing bars on ground floor. One 2-panelled door with moulding and semi-circular fanlight over, in plain reveal and surrounded by concentric brick relieving arch. 1 double-hung sash window with glazing bars to semi-basement. 5 ashlar steps to door flanked by brick walls with ashlar coping, and iron railings with spear finials which also enclose area.

Nos 52 to 54 (even) and Nos 70 to 74 (even) form a group with Nos 83, 85 and 91 to 101 (odd).

1.
5401

TARRANT STREET
(North Side)

No 54
(South View)

TQ 0107 1/69

II

GV

2.

Early C19. Red brick with grey headers (Flemish bond). North and west elevations nodular flint with red brick dressings. Hipped slate roof. Red brick chimneys. 3 storeys. Brick modillion eaves cornice. 2 double-hung sash windows with glazing bars on 2nd floor, 1 on 1st floor. Canted bay to ground floor and 1st floor with cellar door below ground floor window, and planked wooden section between ground and 1st floor windows, 3 windows on each floor, all double-hung sashes with glazing bars; cornice above with scalloped bargeboard. Door with 4 moulded panels and oblong fanlight in plain reveals framed by pilasters with elongated, fluted capitals and cornice above. 1-storey extension to west with lean-to roof; red brick front and west elevation of nodular flint with red brick dressings. Ramping parapet with ashlar coping on south elevation. Brick modillion eaves cornice on west elevation. South elevation has 6-panelled door in plain reveals surrounded by moulded frame, with cornice over and 2 wooden steps up. This and door in main block are connected by a balcony with brick retaining wall, ashlar coping and iron railings with 3 ball finials, approached by a curving flight of 6 limestone steps.

Nos 56 to 64 (even) and Nos 70 to 74 (even) form a group with Nos 83, 85 and 91 to 101 (odd).