

NEW SURFACE WATER DRAINS
VIA SHALLOW ACCESS CHAMBERS
TO BE CONNECTED TO NEW
SOAKAWAY, MINIMUM 5m FROM
ANY STRUCTURE AND PUBLIC
SEWER, ALL TO THE COMPLETE
SATISFACTION OF THE LOCAL
AUTHORITY BUILDING CONTROL.
EXACT LOCATION TO BE AGREED.

- ① EXISTING DOOR TO BE REMOVED AND OPENING BUILT UP IN 100mm BLOCKWORK AND FINISHED WITH 12.5mm PLASTER EITHER SIDE TO MATCH AND MARRY TO THE EXISTING
- ② EXISTING WINDOW TO BE REMOVED AND OPENING BUILT UP IN 100mm BLOCKWORK AND FINISHED WITH 12.5mm PLASTER EITHER SIDE TO MATCH AND MARRY TO THE EXISTING
- ③ FORM OPENING IN THE EXISTING WALL TO SUIT NEW 1050x500mm WINDOW. MAKE GOOD TO ALL SURFACES AS REQUIRED

NEW 230mm DIAMETER SHALLOW ACCESS CHAMBER
CONTRACTOR TO CHECK THE INVERT LEVELS OF DRAINS AND ALSO THE DIRECTION OF FLOW PRIOR TO COMMENCEMENT OF WORK. ANY CONFLICT WITH THE DRAWINGS TO BE REPORTED TO THE ARCHITECT PRIOR TO THE COMMENCEMENT OF WORK. EXACT LOCATION TO BE AGREED ON SITE.

DATE	SCALE	DRAWN BY
Jan 2020	1:50@A1	jb
		CHECKED BY
		MF
JOB NO.	DRAWING NO.	REVISION
19018	4.01	C