




SPECIFICATION
All works generally, to comply with the written Soft Landscape Specification.

NOTE: DO NOT SCALE FROM DRAWING

Legend

- Existing trees to be retained and protected during construction
- Proposed tree planting within soft landscape. See detail on sheet 1
- Proposed specimen shrub planting to receive short angular staking on half standards with expandable tree ties. Irrigation tubing to root system of specimens as required
- Proposed climbing plants to be trained up adjacent wall/ fence/pergola with galvanised wires and hook set 250mm apart with support canes removed prior to planting
- Proposed hedge planting to be planted in a double staggered row 300mm apart and at 500mm centres in each row. To be maintained at 1m height
- Proposed mixed native hedge planting to be planted in a double staggered row 300mm apart and at 500mm centres in each row. To be maintained at 1m height and 1.8m height adjacent to site boundaries
- Proposed shrub planting to receive 75mm bark mulch after planting operations
- Proposed grass areas to receive good quality amenity grass turfs laid in line with good horticultural practices
- Proposed Species Rich Lawn Turf (WFT-Species-Rich-28) as supplied by Wildflower Turf or similar and approved
- Proposed Wildflower Landscape Turf (WFT-Landscape-34) as supplied by Wildflower Turf or similar and approved
- Proposed SUDS Wildflower Turf (WFT-SUD-37) as supplied by Wildflower Turf or similar and approved
- Proposed marginal/wetland planting
- Cut lines
- Proposed 1.2m high post and rail fence

12.04.17 Additional planting to central pond AE
11.04.17 Easement added to Eastern boundary JD
07.04.17 Replacement Oak JD
08.03.17 Layout change AE
20.02.17 Revisions due to revised drainage AE
29.11.16 Sub Station Layout Change JD
08.06.16 Comments JD
Rev Date Details Drawn

ACD ENVIRONMENTAL

HEAD OFFICE
Rodbourne Rail Business Centre, Grange Lane,
Malmesbury, SN16 0ES
Tel: 01665 825546

Courtyard House, Mill Lane, Godalming, GU7 1EY
Tel: 01483 425714

Suite 6, Crescent House, Yonge Close, Eastleigh, SO50 9SX
Tel: 02382 026300

9 Brownlow Road, Cambridge, CB4 3NG
Tel: 07825 868654

email: mail@acdenv.co.uk
www.acdenvironmental.co.uk

DAVID WILSON HOMES

scheme: Hook Lane, Westergate
client: Barretts David Wilson Homes
drawing: Landscape Proposals
date: May 2016
scale: 1:200@A1
drawing no: BDWS20440 11G sheet3
drawn: DC checked: AE

Copyright of ACD Environmental Ltd. All rights described in Chapter IV of the Copyright, Designs and Patents Act 1988 have been generally asserted. 2011. Copyright of this plan remains with ACD until all fees have been paid in full.