

Replacement
Oak for
TPO/AL/1/14:T1

Cherry
Trees

The
Hame

Tara

Springfield

Little Acres

SPECIFICATION
All works generally, to comply with the written Soft
Landscape Specification.

NOTE: DO NOT SCALE FROM DRAWING

Legend

- Existing trees to be retained and protected during construction
- Proposed tree planting within soft landscape. See detail on sheet 1
- Proposed specimen shrub planting to receive short angular staking on half standards with expandable tree ties. Irrigation tubing to root system of specimens as required
- Proposed climbing plants to be trained up adjacent wall/ fence/pergola with galvanised wires and hook set 250mm apart with support canes removed prior to planting
- Proposed hedge planting to be planted in a double staggered row 300mm apart and at 500mm centres in each row. To be maintained at 1m height
- Proposed mixed native hedge planting to be planted in a double staggered row 300mm apart and at 500mm centres in each row. To be maintained at 1m height and 1.8m height adjacent to site boundaries
- Proposed shrub planting to receive 75mm bark mulch after planting operations
- Proposed grass areas to receive good quality amenity grass turves laid in line with good horticultural practices
- Proposed Species Rich Lawn Turf (WFT-Species-Rich-26) as supplied by Wildflower Turf or similar and approved
- Proposed Wildflower Landscape Turf (WFT-Landscape-34) as supplied by Wildflower Turf or similar and approved
- Proposed SUDS Wildflower Turf (WFT-SUD-37) as supplied by Wildflower Turf or similar and approved
- Proposed marginal/wetland planting
- Cut lines
- Proposed 1.2m high post and rail fence

Planting Schedule

Trees						
Species Name	Girth	Height	Density	Specification		No
Tilia cordata	12-14cm	350-425cm	Counted	Heavy Standard	Clear Stem min. 200	RB5No
Betula nigra	12-14cm	350-425cm	Counted	Heavy Standard	Clear Stem min. 200	RB2No
Betula pendula	12-14cm	350-425cm	Counted	Heavy Standard	Clear Stem min. 200	RB5No
Carpinus betulus	14-16cm	350-425cm	Counted	Heavy Standard	Clear Stem min. 200	RB2No
Prunus padus	12-14cm	350-425cm	Counted	Heavy Standard	Clear Stem min. 200	RB2No
Acer campestre	12-14cm	350-425cm	Counted	Heavy Standard	Clear Stem min. 200	RB13No
Acer campestre 'Streetwise'	14-16cm	350-425cm	Counted	Heavy Standard	Clear Stem min. 200	RB3No
Prunus 'Pandora'	12-14cm	350-425cm	Counted	Heavy Standard	Clear Stem min. 200	RB8No
Pyrus calleryana 'Chanticleer'	12-14cm	350-425cm	Counted	Heavy Standard	Clear Stem min. 200	RB8No
Amelanchier arb. 'Robin Hill'	12-14cm	350-425cm	Counted	Heavy Standard	Clear Stem min. 200	RB2No
Sorbus aucuparia	12-14cm	350-425cm	Counted	Heavy Standard	Clear Stem min. 200	RB4No
Quercus robur	20-25cm	450-625cm	Counted	Semi-Mature	Clear Stem min. 200	RB1No

Shrubs						
Species Name	Height	Pot Size	Specification	Density		No
Abelia grandiflora 'Kaleidoscope'	30-40cm	3L	Bushy	4/m²		146No
Amelanchier lamarckii	80-100cm	10L	Branched	Counted		2No
Aucuba japonica 'Rozannie'	30-40cm	3L	Bushy	4/m²		142No
Ceanothus thyrsiflorus repens	30-40cm	3L	Bushy	4/m²		105No
Chaenomeles speciosa 'Moerlosii'	60-80cm	10L	Branched 2 brks	Counted		1No
Cornus alba 'Sibirica'	40-60cm	5L	Bushy	4/m²		11No
Cornus sanguinea	80-100cm	BR	Bushy	1/m²		26No
Cornus sanguinea	30-40cm	3L	Bushy	1/m²		14No
Corylus avellana	80-100cm	BR	Bushy	1/m²		26No
Corylus avellana	80-100cm	BR	Bushy	1/m²		14No
Crataegus monogyna	80-100cm	BR	Bushy	1/m²		39No
Crataegus monogyna	80-100cm	BR	Bushy	1/m²		22No
Daphne odora 'Aureomarginata'	30-40cm	3L	Bushy	4/m²		154No
Daphne pontica	30-40cm	3L	Bushy	4/m²		218No
Escallonia 'Apple Blossom'	60-80cm	5L	Bushy	0.5Ctr Double Staggered at 0.3m offset		518No
Escallonia 'Apple Blossom'	40-60cm	3L	Bushy	3/m²		6No
Euonymus fortunei 'Emerald Gaiety'	20-30cm	3L	Bushy	4/m²		495No
Hebe 'Nicola's Blush'	30-40cm	3L	Bushy	4/m²		166No
Hebe 'Red Edge'	20-30cm	3L	Bushy	4/m²		80No
Hydrangea macrophylla 'Zebra'	30-40cm	3L	Bushy	4/m²		198No
Ilex crenata	30-40cm	3L	Bushy	0.5Ctr Double Staggered at 0.3m offset		31No
Ilex crenata	30-40cm	3L	Bushy	4/m²		15No
Lavandula angustifolia 'Munstead'	20-30cm	3L	Bushy	4/m²		21No
Ligustrum ovalifolium	40-60cm	5L	Bushy	0.5Ctr Double Staggered at 0.3m offset		1014No
Lonicera nitida 'Lemon Beauty'	30-40cm	3L	Bushy	4/m²		24No
Lonicera nitida 'Lemon Beauty'	40-60cm	5L	Bushy	3/m²		28No
Mahonia wagneri 'Pinnacle'	20-30cm	3L	Bushy	4/m²		119No
Phormium 'Apricot Queen'	60-80cm	10L	Counted			1No
Phormium 'Maori Queen'	60-80cm	10L	Counted			1No
Photinia fraseri 'Red Robin'	40-60cm	5L	Bushy	0.5Ctr Double Staggered at 0.3m offset		469No
Photinia fraseri 'Red Robin'	30-40cm	3L	Branched	4/m²		54No
Pieris japonica 'Little Heath'	30-40cm	3L	Bushy	3/m²		94No
Pittosporum tenuifolium 'Tom Thumb'	30-40cm	3L	Bushy	4/m²		155No
Prunus spinosa	80-100cm	BR	Bushy	1/m²		26No
Prunus spinosa	80-100cm	BR	Bushy	1/m²		14No
Rosmarinus off. 'Miss Jessop's Upright'	30-40cm	3L	Branched	4/m²		74No
Salix caprea 'Kilmock'	125-150cm	RB	Counted			12No
Salix purpurea	125-150cm	RB	Counted			11No
Salvia officinalis 'Icterina'	20-30cm	3L	Bushy	4/m²		101No
Sambucus nigra	80-100cm	BR	Bushy	1/m²		3No
Sambucus nigra	80-100cm	BR	Bushy	1/m²		7No
Sarcococca humilis	20-30cm	3L	Bushy	4/m²		278No
Skimmia japonica 'Fragrans'	30-40cm	3L	Bushy	4/m²		192No
Skimmia japonica 'Rubella'	30-40cm	3L	Bushy	4/m²		85No
Viburnum davidii	20-30cm	3L	Bushy	4/m²		100No
Weigela 'Praecox Variegata'	60-80cm	10L	Bushy	Counted		1No

Climbers						
Species Name	Height	Pot Size	Specification	Density	No	
Hydrangea petiolaris	100-150cm	10L	Framed	Counted	2No	

Herbaceous						
Species Name	Height	Pot Size	Specification	Density	No	
Hebeborus x hybridus 'Harvington Red'		3L		4/m²	122No	

Bulbs						
Species Name	Specification	Density	No			
Narcissus 'Tete a Tete'		15/m²	1287No			

Marginal / Aquatics						
Species Name	Pot Size	Specification	Density	No		
Cardamine pratensis	1L	Well Rooted	2/m²	26No		
Iris pseudacorus	1L	Well Rooted	2/m²	36No		
Juncus effusus	1L	Well Rooted	2/m²	26No		

ACD ENVIRONMENTAL

HEAD OFFICE
Rodbournes Rail Business Centre, Grange Lane,
Malmesbury, SN16 0ES
Tel: 01666 825646

Courtyard House, Mill Lane, Codrington, GU7 1EY
Tel: 01483 425714

Suite 6, Crescent House, Yonge Close, Eastleigh, SO50 9SX
Tel: 02382 026300

9 Brownlow Road, Cambridge, CB4 3NG
Tel: 07825 868654

email: mail@acdenv.co.uk
www.acdenvironmental.co.uk

scheme: Hook Lane, Westergate
client: David Wilson Homes

drawing: Landscape Proposals
date: May 2016
scale: 1:200@A1
drawing no: BDWS20440 11G sheet4
drawn: DC checked: AE

Copyright of ACD Environmental Ltd. All rights described in Chapter IV of the Copyright, Designs and Patents Act 1988 have been generally asserted. 2011. Copyright of this plan remains with ACD until all fees have been paid in full.