

SGN 1

Monitoring tree protection

Always:

- have a pre-commencement meeting with the tree consultant before development starts
- use the tree consultant to regularly check that protection remains fit for purpose
- use the tree consultant to supervise work in RPAs
- keep a written record of supervision

SGN 2

Fencing protected trees

Always:

- install protection before development starts
- make sure protection is fit for purpose, i.e. it prevents damage to trees and soil
- keep protection in place until there is no risk to trees
- get written permission to move or remove any protection

SGN 3

Pollution control

Always:

- keep toxic products away from RPAs

SGN 4

Site cranes & piling rigs

Always:

- use the tree consultant to supervise work with cranes and piling rigs in RPAs

SGN 5

Height restrictions

Always:

- prevent the access of vehicles into controlled areas taller than the critical height

SGN 6

Excavating in RPAs

Always:

- use the tree consultant to supervise work in RPAs
- use hand tools to dig in RPAs
- protect exposed roots from sunlight and drying out

SGN 7

Installing/upgrading surfacing in RPAs

Always:

- use the tree consultant to supervise work in RPAs
- minimise damage to roots and disturbance to soil in RPAs
- minimise excavation when installing or upgrading surfacing in RPAs

SGN 8

Installing structures in RPAs

Always:

- use the tree consultant to supervise work in RPAs
- hand-dig pile, pad, or post locations down to at least 60cm
- protect RPAs from contamination from poured wet concrete

SGN 9

Installing services in RPAs

Always:

- use the tree consultant to supervise work in RPAs
- select the least damaging option when installing services, so prioritise trenchless, over broken trench over continuous trench
- hand-dig trenches if trenchless is not feasible

SGN 10

Landscaping in RPAs

Always:

- use the tree consultant to supervise work in RPAs
- avoid raising ground levels within 1m of the trunks of retained trees

SGN 11

How to use plan

More detailed guidance on each Site Guidance Note (SGN) can be found in a printed hard copy compilation of all the SGNs, Manual for Managing Trees On Development Sites version 3.0, issued to the Site Manager at the pre-commencement site meeting. (Note: This should be retained on site throughout the duration of works). Additionally, an electronic pdf compilation of all the SGNs, was submitted with this drawing to the local planning authority and the client. Alternatively, a pdf of each SGN can be downloaded by:

- clicking the image links in the electronic pdf version of this plan;
- holding a mobile phone QR (Quick Response) code reader over the QR code in the paper version of this plan; or
- visiting our website at <https://www.barrelltreecare.co.uk/resources/technical-guidance>

Tree No	Species	Category	RPA Radius	Tree Works
All retained trees & hedges				Carry out safety check and lift over site to 3-4 m as necessary.
G1	Sycamore	C	3.6	
G2	Scots pine	B	7.2	
G3	Ash, sycamore	B	6	
G4	Hawthorn, elm, blackthorn	C	3	
T5	Ash	B	3	
T6	Elm	C	3	Fell
T7	Elm	C	3	Fell
G8	Elm	C	3	Fell
T9	Elm	U	5.1	Fell
T10	Holly	C	3.9	
G11	Hawthorn, hazel	C	2.4	
T12	Oak	A	15	
G13	Leyland cypress	C	5.7	
T14	Oak	A	14.4	
T15	Oak	A	10.8	
G16	Hawthorn	C	3.6	
T17	Oak	A	13.2	
T18	Gum	C	4.2	
T19	Holly	C	5.4	
H20	Hawthorn, blackthorn	C	2.4	
VT21	Field maple	A	14.4	
T22	Oak	B	11.4	
T23	Oak	B	9.6	
VT24	Field maple	A	15	
G25	Hawthorn, elm, blackthorn	C	3.6	
T26	Goat willow	C	7.2	
G27	Hawthorn, elder, elm, goat willow, ash	C	2.4	
T28	Oak	B	9.6	
T29	Oak	C	6.6	
T30	Oak	B	11.4	
T31	Oak	B	12.6	
T32	Hazel	C	12	
T33	Oak	A	6.6	
G34	Hazel, hawthorn	C	9	
T35	Oak	U	9.6	
G36	Hazel	C	6	
G37	Elm, hawthorn, blackthorn, elder	C	3	
G38	Hawthorn, blackthorn, hazel	C	3	
T39	Field maple	A	10.2	
H40	Hawthorn, blackthorn, elm, field maple	C	2.4	Fell part
T41	Field maple	A	13.8	
T42	Field maple	B	10.2	
VT43	Field maple	A	11.1	
T44	Hawthorn	C	3.6	
G45	Elm, hawthorn, holly	C	3	Fell
T46	Oak	B	10.2	
T47	Hawthorn	C	4.8	
T48	Hawthorn	C	6	
T49	Willow	B	12	
G50	Hawthorn, elm	C	2.4	Fell part
T51	Oak	C	8.7	
G52	Hawthorn	C	2.4	
G53	Hawthorn, field maple, hazel, blackthorn	C	3	Fell part
T54	Ash	C	4.8	
T55	Oak	A	10.8	
T56	Field maple	C	4.8	
T57	Hawthorn	C	3	
T58	Field maple	C	5.4	
G59	Hawthorn, blackthorn, goat willow	C	4.2	
G60	Ash, oak	B	7.2	
T61	Ash	U	10.2	Advise tree owner
T62	Ash	U	8.1	Fell for management
T63	Ash	U	8.1	Fell for management
G64	Field maple	C	7.2	Fell
G65	Hazel, elm, plum, field maple	C	4.2	Fell, dead and poor trees, and cut back rest to boundary line to reform as a hedge
T66	Oak	U	3.6	Fell for management
T67	Oak	B	14.7	
G68	Ash	U	7.8	Fell for management
G69	Willow, plum, field maple, hazel	C	5.4	Fell part
T70	Oak	B	6	
G71	Hawthorn, ash, willow	C	4.2	Fell part
G72	Oak, cypress, willow, ash	B	6.6	
G73	Ash, field maple, oak	C	5.4	
T74	Oak	B	12	
G75	Ash	C	6.6	
G76	Oak	B	6	
G77	Oak	C	2.4	Fell
G78	Elm	C	1.8	Fell
G79	Field maple	B	5.4	Fell one southern tree
T80	Ash	B	9	
T81	Ash	C	4.8	Fell
G82	Field maple	C	5.4	Fell
T83	Oak	A	10.2	
T84	Oak	C	6	
G85	Ash, field maple	B	6	Fell 2 northern trees
G86	Willow, elm, hawthorn, hazel, plum	C	2.4	Fell
T87	Oak	C	6.9	Fell
T88	Horse chestnut	B	9.6	Fell
T89	Sycamore	C	10.2	Fell
T90	Oak	B	11.4	Fell
T91	Oak	A	15	
T92	Oak	A	13.5	
H93	Hawthorn, field maple, elm, blackthorn, hazel	C	2.4	Fell
T94	Sycamore	C	10.8	Fell
T95	Oak	C	6	Fell
T96	Oak	A	9	
T97	Oak	B	10.8	
T98	Oak	C	7.2	

www.barrelltreecare.co.uk