



NOT FOR CONSTRUCTION




S.H.E (Safety, Health & Environmental) Information in accordance to OSHA regulations 2015. The following notes refer to Hazards/Risks considered in addition to those normally associated with this type of work.


Numbered references correspond to the list below:

 Existing Services

The chamber is located within an area occupied by existing services.

 Ground Conditions & Deep Excavation

The works require excavations in Excess of 2.5m deep within the site road. The design intent is for a sheet piled cofferdam to be used. The design of the Cofferdam, or any alternative solution, is the responsibility of a suitably qualified temporary works engineer working on behalf of the contractor.

 Ground Conditions & Temporary Works

Historical BGS information suggests that ground conditions in this area are predominantly clays which will require temporary support during construction.

P01	13.09.24	Primary Issue	UW
Rev	Date	Revision Description	Issued by
Drawing Status: S0 - Review in Progress			
<p><b>GODSELL • ARNOLD</b></p> <p><b>PARTNERSHIP LTD</b></p> <p><b>Consulting Civil and Structural Engineers</b></p> <p>7 Arrowsmith Court, Station Approach Broadstone, Dorset. BH18 8AX Telephone: 01202 600 900 Website: www.gapltd.net</p>			
Client: STC CONTRACTS			
Project: WESTERGATE WTW			
Drawing Title: CLA VAL INSTALLATION KIOSK SITE PLAN			
Scale: 1 : 25 @ A1		Drawn: GAP	Checked: UW
Project-Originator-Zone-Level-Type-Role		Drawing No.:	Revision:
24201-GAP-XX-XX-DR-C		9002	P01

PLANNING AND BUILDING  
 COUNCIL ALU/12/25/PL