

Tree Number	Common Species Name	Trunk Diameter (mm)	Height (m)	Crown Spread (m)				First Significant Branch (m)	Crown Clearance (m)	Life Stage	Physiological Condition	Structural Condition	Comments	BS5837 Category	RPA Radius (m)
				N	E	S	W								
1	Ash	330 180 200 #	11	5	5.75	5	4.5	0.5	1.5	Early Mature	Average	Poor	Stems inaccessible due to dense Bramble, unable to thoroughly inspect Multi stemmed from ground level, unions obscured Dominant stem kinks to east from ground level, corrects at c.1.75m Pruning to eastern aspect of crown to clear from overhead utilities Unremarkable example of species	C1	5.1
2	English Oak	300#	11	5#	5.5	5.5	5.25	4.25	2	Semi Mature	Below Average	Indifferent	Clad and obscured by ivy, unable to thoroughly inspect Stem inaccessible due to dense Bramble Suppressed by neighbouring companions Unremarkable example of species	C12	3.6
3	Sitka Spruce	250#	13.5			4	2	1.75	Semi Mature	Average	Indifferent	Inaccessible, offsite within neighbouring residential land, unable to thoroughly inspect Radial crown measurement based on southern spread due to restricted access Structure appears typical for species within current context Unremarkable example of species	C12	3	
4	English Oak	450#	16.5	8#	5.5#	6.5	7.75	4.5#	3.5	Early Mature	Average	Poor	Inaccessible, offsite within neighbouring residential land, unable to thoroughly inspect Leans north west from ground level Crown biased to west Elongated form Suppressed by T3 Previous unsympathetic limb removals to crown lift	B2	9.4
5	English Oak	780	16	10#	9.5	5.75	5.5	2	5.75	Early Mature	Average	Indifferent	Inaccessible, offsite within neighbouring residential land, unable to thoroughly inspect Previous unsympathetic pruning to southern aspect of lower crown Balanced radial crown and scaffold structure Moderate example of species	B12	9.3
6	Lawson Cypress	350#	12			4	4	4	Early Mature	Average	Indifferent	Inaccessible, offsite within neighbouring residential land, unable to thoroughly inspect Radial crown measurement based on southern spread Mutually suppressed and cohesive with companion shelter Unremarkable example of species	C12	4.2	

Tree Number	Common Species Name	Trunk Diameter (mm)	Height (m)	Crown Spread (m)				First Significant Branch (m)	Crown Clearance (m)	Life Stage	Physiological Condition	Structural Condition	Comments	BS5837 Category	RPA Radius (m)	
				N	E	S	W									
7	Lawson Cypress	300 200 #	12					3.5	2.25#	4	Early Mature	Average	Indifferent	Inaccessible, offsite within neighbouring residential land, unable to thoroughly inspect Radial crown measurement based on southern spread Mutually suppressed and cohesive with companion shelter Unremarkable example of species	C12	4.2
8	English Oak	450#	15.5	94	6	6.75	4.5		5#	7	Early Mature	Average	Indifferent	Inaccessible, offsite within neighbouring residential land, unable to thoroughly inspect Structure appears typical for species within current context Minor internal deadwood Unsympathetic pruning to southern aspect of lower crown Moderate example of species	B12	5.4
9	Lawson Cypress	110 140 130 90 #	10					2.5	1.75	2	Semi Mature	Average	Indifferent	Inaccessible, offsite within neighbouring residential land, unable to thoroughly inspect Radial crown measurement based on southern spread Mutually suppressed and cohesive with companion shelter Unremarkable example of species	C12	3
10	Lawson Cypress	3*200#	11.5					2.5	3#	3	Semi Mature	Average	Indifferent	Inaccessible, offsite within neighbouring residential land, unable to thoroughly inspect Radial crown measurement based on southern spread Mutually suppressed and cohesive with companion shelter Unremarkable example of species	C12	4.2
11	Coast Redwood	650#	11	5#	6.25	5.75	5		2#	3.25	Early Mature	Average	Indifferent	Inaccessible, offsite within neighbouring residential land, unable to thoroughly inspect Suspected stem failure at c. 10m Suppressed by T12 Low arboricultural quality	C1	7.8
12	Coast Redwood	750#	18	7.5	6.75	6.25	7#		2#	1.5	Early Mature	Average	Indifferent	Inaccessible, offsite within neighbouring residential land, unable to thoroughly inspect Structure appears typical for species within current context Prominent boundary feature Good example of species	A12	9
13	English Oak	650#	15					10.25	5#	2.75	Early Mature	Average	Indifferent	Inaccessible, offsite within neighbouring residential land, unable to thoroughly inspect Well balanced crown and scaffold structure Structure appears typical for species within current context Prominent boundary feature Moderate example of species	B12	7.8

Tree Number	Common Species Name	Trunk Diameter (mm)	Crown Spread (m)					First Significant Branch (m)	Crown Clearance (m)	Life Stage	Physiological Condition	Structural Condition	Comments	BS5837 Category	RPA Radius (m)	
			N	E	S	W	Radial									
14	Ash	3*220 2*200 #	12	7#	8.25	6	6.25	2	1.75	Early Mature	Below Average	Poor	Stem inaccessible due to dense understorey. Likely to have been historically managed as part of hedgerow, now lapsed. Multi stemmed from c.0.5m, unions obscured by dense understorey. Above average internal deadwood. Above average epicormic growth. Dieback throughout crown. Considered to be entering a state of terminal decline, unlikely to offer a long term future contribution.	U	N/A	
15	Ash	320 380 3*270 #	14.5	6#	8	7	6.25	1.75	4	Early Mature	Below Average	Poor	Stem inaccessible due to dense understorey. Likely to have been historically managed as part of hedgerow, now lapsed. Multi stemmed from c.0.5m, unions obscured by dense Bramble. Above average small diameter deadwood. Multiple tear out wounds throughout scaffold structure. Pruned away from overhead utilities to west. Individually of low significance, conferred moderate value as component of wider collective.	B2	8.1	
16	Ash	120 150 220 2*100 #	14	5#	7	4	9.5	1.5	7.75	Early Mature	Below Average	Hazardous	Stems inaccessible due to dense understorey. Likely to have been historically managed as part of hedgerow, now lapsed. Bole appears hollow. Majority of stems have extensive decay to c.1m. Hazardous structural condition, unsuitable for retention.	U	N/A	
17	English Oak	750#	14	7	6.5#	5.25	7.75	6.25	4.75	Early Mature	Average	Indifferent	Situated on site boundary. Clad and obscured by ivy, unable to thoroughly inspect. Stem inaccessible due to dense basal growth. Slight lean to east from ground level. Extensive burling at base. Moderate example of species. Prominent boundary feature.	B12	9	
18	English Oak	650#	14	5.5	7.5#	7	5	5#	3	Early Mature	Average	Indifferent	Inaccessible, offsite within neighbouring residential land, unable to thoroughly inspect. Stem kinks south from ground level, corrects at c.2m. Moderate example of species. Prominent boundary feature.	B12	7.8	
19	Field Maple	2*250 130 #	7					4#	1#	3.5	Semi Mature	Below Average	Indifferent	Previous unsympathetic pruning to entire crown. Large cavity on western aspect of base. Unremarkable example of species.	C12	4.5

Tree Number	Common Species Name	Trunk Diameter (mm)	Height (m)	Crown Spread (m)				First Significant Branch (m)	Crown Clearance (m)	Life Stage	Physiological Condition	Structural Condition	Comments	BS5837 Category	RPA Radius (m)
				N	E	S	W								
23	Hawthorn	340#	6	3#	2.5#	4	4	3.75	1.5	Early Mature	Average	Hazardous	Multiple cavities on all aspects of trunk Stem kinks west from ground level Hazardous structural condition, anticipate future failure	I	N/A
22	English Oak	630#	7.5			3	2.75	2.75		Early Mature	Below Average	Poor	Previously unsympathetically reduced to monolith Limited regrowth at time of survey Large wound on western aspect of base from ground level to c.1.25m Reduced future potential	C1	7.5
23	English Oak	450#	13#	2#	4#	8.5	5#	4#	5#	Early Mature	Average	Poor	Inaccessible, offsite within neighbouring residential land, unable to thoroughly inspect Surveyed from a distance Unsympathetic pruning to entire crown Occasional decay pockets within old pruning points Unremarkable example of species	C1	5.4
24	Beech	550#	13			5#	3#	3#		Early Mature	Average	Indifferent	Inaccessible, offsite within neighbouring residential land, unable to thoroughly inspect Surveyed from a distance Recent crown reduction Moderate example of species	B1	6.6
25	English Oak	800#	16#			9#	5#	7#		Mature	Average	Indifferent	Inaccessible, offsite within neighbouring residential land, unable to thoroughly inspect Surveyed from a distance Previous unsympathetic reduction to entire crown Bifurcates at c.4m Moderate example of species Prominent within views from adjacent dwellings	B12	9.6
G1	Lonicera														
	English Oak	2*170													
	Contorted Hazel	max													
	Lawson Cypress		7												
	Holly														
	Ash	90	max												
	Laburnum	av													
G2	Lawson Cypress														
	Lonicera														
	Cherry Laurel														
	Holly	250#		9											
	Hazel	max	max												
	Portugal Laurel														
	Hawthorn														

Tree Number	Common Species Name	Trunk Diameter (mm)	Height (m)	Crown Spread (m)				First Significant Branch (m)	Crown Clearance (m)	Life Stage	Physiological Condition	Structural Condition	Comments	BS5837 Category	RPA Radius (m)
				N	E	S	W								
G3	Cherry Plum														
	Hazel														
	Hawthorn		12					5							
	Lawson Cypress	2*190#	max					max							
	Blackthorn	av							1.5 av						
	Elaeagnus		9						2.5						
	Pyracantha		av						av						
G4	Portugal Laurel														
	English Oak														
	Apple														
	Hawthorn	2*120													
	Blackthorn	av	6 av					4 av	1.5 av						
	Elder								2.5 av						
G5	Ash	350													
	Hawthorn	3*120#													
	Blackthorn	max	14.5												
	Sumac														
	Field Maple														
	Purple Plum														
G6	Holly														
	Leyland Cypress	170#	1.5												
	Hawthorn	max	to 7.5												
	Blackthorn														
	Hazel														
	Silver Birch														
	Japanese Maple														
G7	Beech	300# max	4 av					1.75 av	0.5 av						
									0.5 av						
G8	Hawthorn														
	Elder	3* 100 av	7 av												
	Holly														
G9	Cordyline														
	Euonymus	200# max	4 av												
	Myrtle														

Tree Number	Common Species Name	Trunk Diameter (mm)	Height (m)	Crown Spread (m)				First Significant Branch (m)	Crown Clearance (m)	Life Stage	Physiological Condition	Structural Condition	Comments	BS5837 Category	RPA Radius (m)						
				N	E	S	W														
G10	Viburnum	75 av	4 max		1.5 av	0.25 av	0.25 av	Young to Semi Mature	Average	Indifferent	Intermittent collection of domestic ornamental plantings				C12	0.9					
	Aucuba Japonica										Unremarkable collection										
	Lawson Cypress																				
	Berberis																				
H1	Hawthorn	75 av	2 av		1 av	0.25 av	0.25 av	Semi Mature	Average	Indifferent	Maintained field boundary hedgerow				C12	0.9					
	Blackthorn																				
	Ash																				
	Field Maple																				
H2	Hawthorn	75 av	3.5 av		1.5 av	0.25 av	0.25 av	Semi Mature	Average	Indifferent	Maintained field boundary hedgerow				C12	0.9					
	Blackthorn																				
	Dogwood																				
	Elder																				
	Cherry Plum																				
	Ash																				
	Privet																				