



Tree Planting Specification

Tree Location On Plan	Tree Species	Tree Size	Girth	Overall Height	Bare Root Or Container Grown
A	Pedunculate Oak Quercus robur	Selected Standard Tree	10-12cm	2.5m to 3.0m	Either depending on time of year planted and availability

- All trees/shrubs to be planted in pits excavated to the exact depth of the root-ball and a width equivalent to a 50% larger radius hole.
- Holes to be backfilled with a mix of 80% clean topsoil and 20% approved green compost to PAS100 and 100gms granular fertilizer.
- Incorporate a proprietary brand of watering/feeding tube system around the rootball.
- Water-in heavily after planting and surface mulch to 75mm depth.
- All trees to be short staked at 45 degrees to the stem and attached to same with a rubber securing block and tie.
- Any necessary tree pruning and tidying works are to be carried out with a 'Silky' hand saw or secateurs to BS3998 standards.

RJCA Chartered Architects

The White House, 2 Lavant Road
Chichester, West Sussex PO19 5RQ

Tel: 01243 779600

Mobile: 07973435493

Email: rjcatkinson@btinternet.com

Drawing: Site layout and block plan

Drawing Number: 2020/10/11

Rev. K

project	Lidsey Lodge Farm Sack Lane Lidsey
client	Melanie Jenkins Farming Ltd.
title	Tree Protection Plan (Incl Retentions & Removals)
dwg	BJH 03/04
scale	1:500 (@ A3)
date	Feb 2022
job	1229
drawn by	bjh
The Granary - White Chimney Row - Westbourne PO10 8RS 07875 520881 bernieharverson@gmail.com	