



Local Policing Support Team

Your Ref: AL/20/21/PL

Our Ref: LM/ARU/21/04A

Date 18th February 2021

Contact Name: Lee Melbourne

Dear Mr Davis,

RE: Land At Wings Nursery Lidsey Road Woodgate PO20 3SU

Thank you for your correspondence of the 18th of February 2021, advising me of a planning application for Demolition of Wings House & erection of 71 No. replacement dwellings (70 net new dwellings), access arrangements, sustainable drainage measures, public open space, landscaping & all other associated works (resubmission following AL/46/20/PL). This application is a Departure from the Development Plan at the above location, for which you seek advice from a crime prevention viewpoint.

The National Planning Policy Framework demonstrates the government's aim to achieve healthy, inclusive and safe places which are safe and accessible, so that crime and disorder, and the fear of crime, do not undermine the quality of life or community cohesion. With the level of crime and anti-social behaviour in the Arun District being average when compared with the rest of Sussex, I have no major concerns with the proposals, however, additional measures to mitigate against any identified local crime trends and site specific requirements should always be considered.

I refer the applicant to previous correspondence from this office pertaining to this site:

Your Ref: AL/32/19/OUT dated the 2nd April 2019 and Our Ref: NW/ARU/19/10A dated the 3rd May 2019. Additionally Your Ref: AL/46/20/PL dated the 22nd June 2020 and Our Ref: LM/ARU/20/16A dated the 23rd June 2020 to which all comments remain extant.

Mr Davis
Planning Officer
Planning Control
Arun District Council

Sussex Police Headquarters
Malling House, Malling, Lewes, East Sussex, BN7 2DZ

I note that that this latest planning application is a resubmission following the withdrawal of planning application AL/46/20/PL.

I have had the opportunity to examine the detail within the application and in an attempt to reduce the opportunity for crime and the fear of crime I offer the following comments from a Secured by Design (SBD) perspective. SBD is owned by the UK Police service and supported by the Home Office and Building Control Departments in England (Part Q Security – Dwellings), that recommends a minimum standard of security using proven, tested and accredited products. Further details can be found at www.securedbydesign.com

I direct the applicant or their agent to our website at www.securedbydesign.com where the SBD Homes 2019 Version 2 document can be found. The Secured by Design scheme is a Police initiative to guide and encourage those engaged within the specification, design and build of new homes, and those undertaking major or minor property refurbishment, to adopt crime prevention measures. The advice given in this guide has been proven to reduce the opportunity for crime and the fear of crime, creating safer, more secure and sustainable environments.

The development in the main has outward facing dwellings with back to back gardens which has created good active frontage with the streets and the public areas being overlooked, this design has all but eliminated the need for vulnerable rear garden pathways. Parking in the main has been provided in-curtilage, with parking courts and a number of parking bays which should leave the street layout free and unobstructed.

Where communal parking occurs it is important that they must be within view of an active room within the property. An active room is where there is direct and visual connection between the room and the street or the car parking area. Such visual connections can be expected from rooms such as kitchens and living rooms, but not from bedrooms and bathrooms. Gable ended windows can assist in providing observation over an otherwise unobserved area.

From a crime prevention perspective with regards to the flats (plots 24-27) it will be imperative that access control is implemented into the design and layout to ensure control of entry is for authorised persons only. For additional information I refer the applicant to chapter 27 SBD Homes Version 2 2019.

Additionally, I recommend the postal arrangements for the flats is through the wall or externally mounted secure post boxes. I strongly urge the applicant not to consider letter apertures within the flats' front doors. The absence of the letter aperture removes the opportunity for lock manipulation, fishing and arson attack and has the potential to reduce unnecessary access to the block.

I also note that there will be shared bin and cycle storage to the flats. I refer the applicant to SBD Homes Version 2 2019 Chapter 56 56.3 External, open communal bicycle stores with individual stands or multiple storage racks for securing bicycles will be as close to the building as possible, but in any event within 50 metres of the primary entrance to a block of flats and located in view of active rooms (Note 56.3) of dwellings. The store must be lit at night using vandal resistant, light fittings and energy efficient LED lights.

NB: Vertical cycle racks can be difficult for some sections of the community to use. Note 56.3: The word 'active' in this sense means rooms in building elevations from which there is direct and regular visual connection between the room and the street or parking court. Such visual connection can be expected from rooms such as kitchens and living rooms, but not from more private rooms, such as bedrooms and bathrooms.

Pertaining to doorsets within the development as a whole I refer the applicant to chapter 21 Paragraph 21.1 through to 21:22 of SBD Homes Version 2 2019.

Again with regards to windows and glazing within the development as a whole I refer the applicant to Chapter 22 Paragraph 22.1 through to 22.16.of SBD Homes Version 2 2019.

Sussex Police Headquarters
Malling House, Malling, Lewes, East Sussex,
BN7 2DZ



With regards to the LAP and LEAP - areas of play should be situated in an environment that is stimulating and safe for all children, be overlooked with good natural surveillance to ensure the safety of users and the protection of equipment, which can be vulnerable to misuse. They should be designed to allow natural surveillance from nearby dwellings with safe and accessible routes for users to come and go. Boundaries between public and private space should be clearly defined and open spaces must have features which prevent unauthorised vehicular access. I would ask that both of these areas of play are surrounded with railings and self-closing gates to provide a dog free environment.

Regards landscaping I recommend that ground planting should not be higher than 1 metre with tree canopies no lower than 2 metres. This arrangement provides a window of observation throughout the area.

Finally, lighting throughout the development will be an important consideration and where it is implemented it should conform to the recommendations within BS 5489-1:2013.

I would also ask you to note that Sussex Police is now exploring the impact of growth on the provision of policing infrastructure over the coming years and further comment on this application may be made by our Joint Commercial Planning Manager.

Thank you for giving me an opportunity to comment.

The Crime & Disorder Act 1998 heightens the importance of taking crime prevention into account when planning decisions are made. Section 17 of the Act places a clear duty on both police and local authorities to exercise their various functions with due regard to the likely effect on the prevention of crime and disorder. You are asked to accord due weight to the advice offered in this letter which would demonstrate your authority's commitment to work in partnership and comply with the spirit of The Crime & Disorder Act.

Yours sincerely

Miss Lee A Melbourne
Designing Out Crime Officer
Sussex Police Headquarters

Sussex Police Headquarters
Malling House, Malling, Lewes, East Sussex,
BN7 2DZ

