

Land at Oldlands Farm Phase 2
Steyning Way Bognor Regis, West Sussex
Planning Ref: AL/58/OUT

DESIGN CODE
On Behalf of Hanbury PM Limited

DAVIESLANDSCAPE
A R C H I T E C T S

Report Ref: DLA.1859.PDCODE.RPT.01.

Date: Feb 2018

NOTICE

This document has been produced on behalf of Hambury Properties Ltd by Davies Landscape Architects (DLA) for the sole purpose of planning for the project below:

Document Title: Reserved Matters Design Code at Oxlands Farm Phase 2

Document Reference: DLA.1859.DCode.RPT.01.Draft

This document may not be used by any person for the purpose other than which it is intended without the express written permission of Hambury PM Ltd. Any liability arising out of use by a third party for a purpose not wholly connected with the above shall be of that party who shall indemnify DLA against all claims, costs, damages and losses arising out of such use.

Document History

Rev.	Purpose	Author	Checked	Reviewed	Authorised	Date
	Draft	MD				26/02/2018

Revision Description Of Changes

Revision	Description Of Changes

1:10,000 Plans copyright - Ordnance Survey, (c) Crown Copyright 2015. All rights reserved. Licence number 100022032

DAVIESLANDSCAPE ARCHITECTS

DLA, Suite F1 & F2, Stroud House, Russell Street, Stroud.

Gloucestershire, GL5 3AN,



- 1 INTRODUCTION
- 2 SITE CONTEXT
- 3 CONSTRAINTS AND OPPORTUNITIES
- 4 DESIGN
- 5 BUILDING FORM
- 6 MATERIALS AND COLOURS
- 7 ACCESS
- 8 STREET FURNITURE
- 9 LANDSCAPE
- 10 SUSTAINABILITY



Fig 02- Outline Approved Scheme

no more than 13,506m² B8 floorspace (in accordance with B2/B8 Illustrative Masterplan DLA.1643.L003.03).

1.3 How to use the Design Code

The Design Code has been prepared to allow for flexibility. Its purpose is to establish clear design instruction and guidance. It does not fix the 'design' of development but rather presents parameters within which development must be delivered.

The Design Code proposes the form and layout of the development that is acceptable but does not fix architectural style or detailing.

In addition to establishing the design parameters The Design Code contains suggested material palettes, indicative images providing examples of development form, and landscaping considered relevant and appropriate for Oldlands Farm. Developers of future plots will be expected to include specific information on how their design solutions have been developed in response to the Code.

1.4 The Vision For Oldlands Farm Phase 2

Oldlands Farm must be an enjoyable place to work and a place where high quality design is provided. It will aim to follow best practice in sustainable design to create an exemplary business environment that encourages investment and delivers high quality employment opportunities.

1.5 The Design Team

The application has been produced in conjunction with a an experienced multidisciplinary project team, who have all worked on other phases at Oldlands Farm and have a good understanding of the site and its context.




Fig 03 - Landscape Parameters Plan

2 THE SITE CONTEXT

Oldlands Farm Phase 1 has provided a new 30,000sq.m logistics facility on behalf of Rolls Royce.

The scale and mass of the building has successfully been diminished by the use of changes in texture and colour to the external cladding with profiled and flat feature cladding to highlight the ancillary offices.

A Section 73 application to change the use of the buildings on Phase 1A has been granted to allow the sale of convenience goods. A full application is to be made shortly on this land. This will be in line with the design code for that phase and will be in harmony with this design code.

This set out the use of darker sections of cladding to add both contrast and texture and shadow to the facades which can be seen in The Range visuals. Elements of glazing are included on both buildings to provide visual interest and relief while allowing glimpses into the interior of the buildings. The appearance will be softened by the planting of trees in the zone between building and road and presents a positive elevation to the BNRR.



Rolls Royce - Oldlands Farm Phase 1



Street scene elevation from the BNRR



Aerial view



The Range entrance detail



Aerial view




Fig 04- Key Constraints

3 CONSTRAINTS AND OPPORTUNITIES

The principal constraints to future development were clearly established at the Outline stage.

Flood Risk

The site lies in Flood Zone 2 and levels will need to be raised to 2.5m AOD across the site. A flood compensation area is to be provided to the north of the BNRR as compensation for the loss of floodplain within the whole of the Oldlands Farm site. This will require care in the setting out the footprint of buildings to ensure that adequate land is left to allow slopes or retaining walls to meet the existing ground levels.

Ditches

Oldlands Farm Ditch is an established and strategic watercourse that requires access for maintenance within a minimum corridor of 8m. The ditch running parallel with the railway track is identified as a green corridor within a 15m corridor.

Public Footpath PF152

This was temporarily closed during the construction of the BNRR but should be reinstated on its current alignment, albeit it will be raised to 2.5m AOD where it crosses the site to the north.

4 DESIGN

General Design Principles

The layout plan at Figure 5 identifies an extension of Oldlands Farm Phase 1 to serve two sub-phases of development (2a and 2b).

Site Parameters and Phasing

The indicative parameters provides the limitations and extent of each phase including the proposed building zones and minimum depths/areas of retained green infrastructure, which should remain free of development.

Scale

The parameters heights plan established at the outline stage will provide the maximum heights across each phase. The least sensitive area in phase 2b will be up to 13.5m tall and the parcels adjacent to the BNRR reduced to 10.5m floor to ridge height




Fig 05- General Access and Layout Plan




Fig 06 - Heights Parameters Plan






Fig 07 - Landscape and Development Framework Plan


REC'D 02-02-0003 03-06-02 REC'D 02-06-0003




Profiled cladding




Flat panel cladding




Glazing to add interest and relief



Canopies




Profiled cladding



Flat panel cladding



Openings to reduce mass and create rhythm



Vertical cladding



Brick plinth to add interest and solidity



Horizontal banding on smaller units

The materials, in combination with glazed elements and opening patterns, will be used to work with the building's form and internal layout in order to break up the large built structures and add rhythm and emphasis to the facades.

The considerate and consistent treatment of external details such as framing of openings, eaves, canopies or solar shading will help establish a common, crisp and contemporary design language across the development and contribute to a high quality environment.

Adequate space will be provided in the elevations treatment to include signage for future occupiers.

7 ACCESS, CYCLEWAY AND FOOTPATHS

The principal access road will contain a 2m footpath and 3m cycleway as an extension of the existing spine road serving Phase 1 using bitu-macadam.

Adequate cycle shelters shall be provided for the occupants of each unit to WSCC standards.

8 STREET FURNITURE AND LIGHTING

Each plot must be provided with an adequate level of illumination in line with safety and security of all areas, at the same time as being used creatively for focal points and features. Lighting should be low level where possible directed downwards to avoid night sky pollution.

Street furniture should generally be a consistent palette across the whole of phase 2

9 LANDSCAPE

All the existing sensitive landscape features identified through the outline planning permission will be retained and link with new landscape, built form and access arrangements.

The landscape corridors will provide the major structuring element of landscape including drainage infrastructure (sustainable drainage system) and provide a biodiversity feature as well as improving visual amenity.

A balance must be reached between managed landscape around the units and the natural environment within green corridors so that a coherent and attractive environment is created within the development.


The access spine road will provide the common thread that knits together the development with phase 1 and 1a. A coordinated palette of materials and structural landscaping will contribute to the creation of an identifiable sense of place, high quality public realm and wayfinding. The aim

is to provide an accessible workplace with legible, safe and obvious routes to its users, with workplaces that are easily accessible. The principles of sustainability development must be an overarching driver across the development.

The landscape within the green infrastructure zones, which lie around the perimeters of each phase will be enhanced through native planting in the form of native trees, native hedges and scrub. The ditches will be managed to enhance biodiversity and encourage wildlife.

The spine road will be defined by avenue tree planting using trees with good form, structure and drought tolerance to include Lime and Maple species with occasional clusters of pine trees to mark entrances and feature planting areas. More ornamental shrub and tree planting will be permissible along the spine road; within amenity areas and around buildings and carparks.

Feature planting schemes should mark entrances to units draw attention to signs and afford year round interest including at least 30% evergreen species.



Structured landscape



Attractive public realm



Solar Power

10 SUSTAINABILITY AND RENEWABLE ENERGY

The aim across the whole of phase 2 is to reduce CO2 emissions through the combination of fabric efficiency measures and the integration of renewable energy measures including photo voltaic solar arrays mounted on roofs or decks.

The development is proposed to incorporate best practice energy efficiency and sustainability measures which is demonstrated through the commitment in achieving BREEAM 'Very Good' standards.

Passive Design & Layout

Building orientation plays an important role in energy conservation and maximising solar gain. Consideration will also been given to minimising excessive solar gain and subsequent building overheating, thus avoiding excessive use of mechanical cooling systems in the summer months.

Water Conservation


Buildings will incorporate measures to minimise water usage such as dual flush toilets and low flush capacity; taps will have flow restrictions and/ or dosage control or sensor control, as will urinals;

Low water consumption appliances will be specified in office kitchen areas where appliances are installed (such as dishwashers).


Flood and SUDS

An integrated Sustainable Urban Drainage Systems (SUDS) will be formed for the whole of the phase 2 development as required by Planning Condition 21/22 and will ensure that the development is designed to limit runoff to the equivalent, or less, of the runoff from the existing undeveloped site.

Measures will primarily include using oversized drainage pipes in roads; permeable paving in plot carparks and storing water in underground crates. Smaller areas of landscape can also be utilised for swales and small retention ponds.



SUDS FEATURES



Solar Sha



DAVIESLANDSCAPE
A R C H I T E C T S