



DOC SUMMARY 12.01.21

TYRONE HOUSE, NORTON LANE, NORTON, ALDINGBOURNE, PO20 3NH

TYRONE HOUSE, NORTON LANE, NORTON, ALDINGBOURNE, PO20 3NH

AL/51/20/PL DEMOLITION OF EXISTING HOUSE AND OUTBUILDINGS AND ERECTION OF 1 No DWELLING AND GARAGE


CONDITIONS 3, 5, 7 & 14

3. SCHEDULE OF MATERIALS:

External Walls: Through colour monocouche render by Weberpral M - colour 'Chalk'



Roof: Cembrit Westerland Slate







5. SUSTAINABILITY:

A 47.8% reduction in CO₂ over current building regulations is proposed, achieved by improvements to the fabric of the building and the use of BioLPG Calor Gas (a renewable and sustainable gas made from waste). Please refer to the SAP calculations at the end of this statement.

7. Car Parking Spaces

Please refer to Figure 1 below.




- Ⓐ 2 No 2.4 x 4.8 parking spaces
- Ⓑ 2 No spaces within garage

FIGURE 1 - PROPOSED PARKING


14. External lighting

Please refer to Figure 2 below.



- Ⓐ Floodlight
- Ⓑ Wall light

FIGURE 2 - PROPOSED EXTERNAL LIGHTING



Luxon®

Slim Floodlight LED 50W 5000K 4000Lm IP65 Body - Black

Part Code: **LXSFL50WB**

£33.45 Excl. VAT

Stock Availability

Choose a branch to view stock levels

1788 available for delivery


Product Description

Part Code: **LXSFL50WB**

- Black die cast aluminium housing, toughened glass cover
- Corrosion resistant fixing bolts and cable gland
- Pre-fitted cable: 600mm
- Beam spread: 110°
- Life hours: 20,000

A. FLOODLIGHT – SWITCHED BY PIR MOTION SENSOR WITH MANUAL OVERRIDE SWITCH

Ravel 2 Light LED Wall Light - Black Resin



Dimensions:
Height: 160mm,
Projection: 90mm,
Width: 80mm.

**Ravel 2 Light LED Wall Light
Black Resin**

Resin wall light.

Ideal for use in coastal areas or areas where corrosion may be a concern.

Twin lights output which may be mounted in any desired direction.

15 years anti-corrosion guarantee.

- IP44 rated.
- Supplied with 2 x 4w LED GU10 lamp. (Max 7w)
- Total: 308 lumens.
- Colour: 3000K

Product Code	Description	Price (ex VAT)	Quantity
FL 4904BK	Ravel 2 Light LED Wall Light - Black Resin	EACH £19.85	1 <input type="button" value="Add"/>

B. WALL LIGHT – MANUAL SWITCH

Client : Kieran Naphine
C/o Smith Simmons & Partners

Calculation : Thermal Check in Accordance with
Approved Document L1A (2013)

Calculation Ref : SAP/2020/022/01



Dwelling Address or House Type :

New Dwelling at Tyrone House, Norton Lane, Norton, Chichester, PO20 3NH


Building Regulation L1(a)(i) Compliance

Target Emissions Rate (CO₂)	14.50
Dwelling Emissions Rate (CO₂)	7.57
Dwelling Emissions ≤ Target Emissions, therefore :	PASS
Percentage Reduction of CO₂ from insulation and biogas fuel	47.8%

Target Fabric Energy Efficiency	59.30
Actual Fabric Energy Efficiency	53.20
Actual ≤ Target, therefore :	PASS

SAP Energy Rating	73
--------------------------	-----------

The risk of solar over heating has been assessed as : and therefore complies with ADL1A, paragraph 2.40	Slight
--	---------------



Calculation By : Ian Sheppard (QUID207615)

Thermal Solutions

21 Lincoln Avenue, Rose Green, Bognor Regis, West Sussex, PO21 3EJ



Dwelling Address/House Type : New Dwelling at Tyrone House, Norton Lane, Norton, Chichester, PO20 3NH

Calculation Reference : SAP/2020/022/01

CONSTRUCTION & INSULATION	U-Value
<u>External wall 1</u> External render, 100mm Hemelite Standard block, 51mm clear cavity, 9mm OSB, 140 x 38mm timber stud with 125mm Actis Hybris insulation between, 25mm battens over studs, 12.5mm plasterboard - U value from supplier Parnell Homes Heat capacity = $0.0125 \times 700 = 8.75$	0.22
<u>External wall 2 - stud closing off loft voids</u> Tiles, battens, felt, rafters, vented void, nominal 100 x 50mm timber studs with 150mm Celotex XR4000 between, 15mm plasterboard finish - U value includes $R_u = 0.50 \text{ m}^2 \text{ K/W}$ - Heat Capacity = $0.015 \times 700 = 10.50$	0.22
<u>Stud Partitions</u> Timber studs with 9mm OSB and 15mm plasterboard both sides Heat Capacity = $(0.015 \times 700) + (0.009 \times 500 \times 1.6) = 17.70$	0.00
<u>Roof 1 - vaulted ceiling over first floor</u> Tiles, battens, felt, nominal 200 x 50mm rafters at 400mm centres with 150mm Celotex XR4000 between rafters, 52.5mm Celotex PL4000 (40mm insulation + 12.5mm plasterboard) to sloping soffit - Heat Capacity = $0.0125 \times 700 = 8.75$	0.16
<u>Roof 2</u> Tiles, battens, felt, rafters, vented loft void, nominal 200 x 50mm timber joists with 100mm Knauf Loft Roll 40 between and 2 x 150mm Loft Roll 40 cross laid over joists, 15mm plasterboard - Heat capacity = 10.50	0.10
<u>Roof 3 - flat roof</u> Waterproofing, 18mm OSB, 150mm Celotex XR4000, 18mm OSB, firrings on 170 x 47mm timber joists, 15mm plasterboard Heat Capacity = 10.50	0.14
<u>Ground Floor</u> 75mm screed, 150mm Celotex XR4000 over beam and block floor with dense concrete infill blocks Heat capacity = $0.075 \times 1200 = 90$	0.12
<u>First Floor</u> 22mm floorboards on suspended composit joists with insulation between, with 15mm plasterboard to soffit Heat Capacities: as ceiling = 10.50 as floor = $0.022 \times 1.6 \times 500 = 17.6$	0.00
<u>Windows</u> Timber frame, double glazed with low "E" glass etc.... To achieve average U value as shown	1.40
<u>French Doors</u> Timber frame, double glazed with low "E" glass etc.... To achieve average U value as shown	1.20
<u>Patio Doors</u> Aluminium frame, double glazed with low "E" glass etc.... To achieve average U value as shown	1.80
<u>Entrance Door</u> Solid door and frame to achieve U value as shown	0.90
<u>Single Side Door</u> Solid door and frame to achieve U value as shown	1.20
<u>Roof Lights</u> Keylite Hi-Therm WCP05HT double glazed units	1.30
<u>Lantern</u> Timber or UPVc frame, double glazed with low "E" glass etc.... To achieve average U value as shown	1.20
The above notes may not include all elements, such as membranes or vapour barriers	

Dwelling Address/House Type : New Dwelling at Tyrone House, Norton Lane, Norton, Chichester, PO20 3NH

Calculation Reference : SAP/2020/022/01

<u>Heating, Orientation & Ventilation</u>	
<u>Space Heating</u> Condensing boiler with automatic ignition using Biogas fuel, serving underfloor heating on ground floor, radiators at first floor and domestic hot water - Minimum boiler SEDBUK rating as shown (2009 definition)	<u>SEDBUK</u> 89%
<u>Heating Controls :</u> Full time and temperature zone controls & boiler interlock device	
<u>Domestic Hot Water</u> By the above boiler, utilising 2 x 250 litre Megaflco Eco indirect storage cylinders with separate timer, thermostat and fully insulated primary pipework - Cylinders have factory fitted foam insulation each with 1.61 kW.h/day storage losses	
<u>Secondary Heater</u> Closed wood burning stove - HETAS approved appliance	
<u>Low Energy Internal Lighting</u> 100% of fixed light fittings include Low Energy Lamps	
<u>Orientation and Shading :</u> Front elevation faces North West with zero sides sheltered with average overshadowing.	
<u>Air Permeability & Ventilation</u> Air permeability taken as 5.0 m ³ /hr/m ² . Decentralised continuous mechanical ventilation using iCONstant by Airflow Ltd to kitchen and wet rooms - and one chimney	

Dwelling Address/House Type : New Dwelling at Tyrone House, Norton Lane, Norton, Chichester, PO20 3NH

Calculation Reference : SAP/2020/022/01

Thermal Bridging

Thermal bridging at openings and junctions of external walls with roofs & floors etc, are assumed to comply with details below. An appropriate system will be set in place by the builder to monitor and confirm their implementation - this system to be agreed with Building Control

The application of the details must also be co-ordinated by a responsible person

Thermal bridging at the following junctions will comply with current Accredited Construction Details (2006)

<u>Item</u>	<u>Junction in or with external wall</u>	<u>ψ value</u>
E2	lintels - details TFW - WD - 01	0.300
E3	Cills - Detail TFW - WD - 02	0.040
E4	Reveal - Detail TFW - WD - 03	0.050
E5	Ground floor - detail TFW - GF - 02	0.160
E6	First floor - detail TFW - IF - 01	0.070
E10	Eaves - ins at joist level - detail TFW - RE - 01	0.060
E11	Eaves - insulated at rafter level - detail TFW - RE - 06	0.040
E13	Gable - insulation at rafter level - detail TFW - RG - 03	0.040
E16	External corners - detail TFW - EW - 01	0.09

The Accredited Details may be found on the link below

<http://www.planningportal.gov.uk/buildingregulations/approveddocuments/partl/bcassociateddocuments9/acd>

The following junctions have no accredited details or those available have been deemed unpractical, and so a default heat loss will be used, in accordance with Table K

<u>Item</u>	<u>Junctions</u>	<u>ψ value</u>
E1	lintels over patio doors	1.000
E14	Wall and flat roof	0.080
E16	Corner between patio doors	0.180
E17	Internal corners	0.000

Where no details are available, the principles of sealing and minimising thermal bridging should be adhered to

Dwelling Address/House Type : New Dwelling at Tyrone House, Norton Lane, Norton, Chichester, PO20 3NH

Calculation Reference : SAP/2020/022/01

ACTUAL ELEMENT AREAS

GROUND FLOOR	$(19.49 \times 11.74) - (3.58 \times 1.46)$	= 223.59 m ²
U PERIMETRE	$19.49 + 13.20 + 32.69$	= 65.38 m
GROUND FLOOR AVH	$\frac{((6.41 \times 3.16) + (217.18 \times 2.55))}{223.59}$	= 2.57 m
FIRST FLOOR	$(11.82 \times 4.70) + (19.51 \times 5.56) + (8.90 \times 1.46)$	= 177.02 m ²
FIRST FLOOR AVH	$\frac{((3.31 \times 3.37) + (21.11 \times 3.98) + (152.60 \times 2.72))}{177.02}$	= 2.88 m
ROOFS	<p>Roof 1 - vaulted</p> $\left(\frac{(1.56 \times 1.18) + (1.00 \times 21.11)}{\cos 44} \right) - 1.84$ <p>Roof 2 - loft void</p> $223.59 - 21.11 - (1.56 \times 2.12)$ <p>Roof 3 - flat</p> $(7.68 \times 4.70) + (7.04 \times 1.46) - 6.41$	= 30.07 m ² = 199.17 m ² = 39.96 m ²
WINDOWS	<p>In GF wall 1</p> $(4.80 \times 1.73) + (8.04 \times 1.53) + (1.60 \times 1.49) + (1.60 \times 1.30) = 25.07$ <p>In FF wall 1 - including bullseye windows</p> $(17.60 \times 1.32) + (2.00 \times 0.43) = 24.09$ <p>Total</p> $= 49.16$ <p>Facing front</p> $(8.04 \times 1.53) + (8.00 \times 1.32) + (2.00 \times 0.43) = 23.72$ <p>Facing rear</p> $(4.80 \times 1.73) + (6.40 \times 1.32) = 16.75$ <p>Facing left</p> $(1.60 \times 1.49) + (2.40 \times 1.32) = 5.55$ <p>Facing right</p> $(1.60 \times 1.30) + (0.80 \times 1.32) = 3.14$ <p>Total</p> $= 49.16$	= 25.07 m ² = 24.09 m ² = 49.16 m ² = 23.72 m ² = 16.75 m ² = 5.55 m ² = 3.14 m ² = 49.16 m ²
PATIO DOORS	<p>Facing rear in GF wall 1</p> $4.99 \times 2.30 = 11.48$ <p>Facing left in GF wall 1</p> $4.34 \times 2.30 = 9.98$	= 11.48 m ² = 9.98 m ²
FRENCH DOORS	<p>Facing rear in GF wall 1</p> $1.60 \times 2.30 = 3.68$ <p>Facing rear in FF wall 1</p> $1.60 \times 2.00 = 3.20$ <p>Total facing rear</p> $= 6.88$ <p>Facing left in FF wall 1</p> $1.61 \times 2.00 = 3.22$	= 3.68 m ² = 3.20 m ² = 6.88 m ² = 3.22 m ²

Calculation Reference : SAP/2020/022/01

Entrance

$$2.10 \times 2.26 = 4.75 \text{ m}^2$$

Single side doors - facing right

$$1.01 \times 2.26 = 2.28 \text{ m}^2$$

Velux facing front

$$(0.78 \times 1.18) + (0.78 \times 1.18) = 1.84 \text{ m}^2$$

Lantern

$$2.34 \times 2.74 = 6.41 \text{ m}^2$$

GF wall 1

$$(65.38 \times 2.55) - 25.07 - 11.48 - 9.98 - 3.68 - 4.75 - 2.28 = 109.48 \text{ m}^2$$

FF wall 1

$$\begin{aligned} & (65.38 \times 2.72) + (4.45 \times 2.16) + (14.74 \times 0.18) - 24.09 - 3.20 \\ & - 3.22 = 156.94 \text{ m}^2 \end{aligned}$$

Total wall 1 = 266.42 m²

FF wall 2

$$\begin{aligned} & (4.45 \times 2.16) + (1.72 \times 0.30) + (3.44 \times 0.47) + (1.72 \times 0.38) + \\ & (2.51 \times 1.56) + (2.12 \times 1.27) + (2.12 \times 1.27) = 21.70 \text{ m}^2 \end{aligned}$$

GF stud

$$55.85 \times 2.00 \times 2.55 = 284.84 \text{ m}^2$$

FF Stud wall

$$64.58 \times 2.00 \times 2.43 = 313.86 \text{ m}^2$$

ZONE 1

$$(12.86 \times 4.51) + (2.00 \times 0.18) + (7.51 \times 7.05) + (0.26 \times 1.28) = 111.64 \text{ m}^2$$

THERMAL BRIDGING - COMPLIANT JUNCTIONS WITH EXTERNAL WALL

timber lintels	1.60	+	1.60	+	1.60	+	1.60	+	1.01	+	1.60	+	1.60	+	1.60	
	0.82	+	2.10	+	0.82	+	1.60	+	1.60	+	3.20	+	16.00	+	4.80	= 43.15

Cills	43.15	-	1.60	-	1.01	-	2.10	-	1.60	-	1.60	-	1.60	=	33.64	E3
-------	-------	---	------	---	------	---	------	---	------	---	------	---	------	---	-------	----

$$\text{Jambs} (4.00 \times 2.30) + (4.00 \times 2.26) + (4.00 \times 2.00) + (6.00 \times 1.73)$$

$$(12.00 \times 1.53) + (2.00 \times 1.30) + (24.00 \times 1.32) = 89.26 \text{ E4}$$

Ground floor = 65.38 E5

First floor = 65.38 E6

Eaves - ins at joist level 65.38 - 5.84 - 4.45 - 4.45 = 50.64 E10

Eaves - ins at rafter level 1.46 x 4.00 = 5.84 E11

Gable - ins at rafter level 8.90 x 1.390 = 12.37 E13

$$\text{Corners (external)} (5.00 \times 2.55) + (10.00 \times 2.72) = 39.95 \text{ E16}$$

THERMAL BRIDGING - DEFAULT JUNCTIONS

lintels over patio doors 4.99 + 4.34 = 9.33 E1

$$\text{Flat roof} \quad 3.85 \quad + \quad 4.70 \quad + \quad 3.85 \quad + \quad 4.70 \quad + \quad 3.52 \quad + \quad 1.46 \quad + \quad 3.52 \quad + \quad 1.46 \quad = \quad 27.06 \quad \text{E14}$$

Corner tween patio doors	1.00	x	2.55	=	2.55	E16
--------------------------	------	---	------	---	------	-----

$$\text{Corners (internal)} \quad (2.00 \quad \times \quad 2.55 \quad) + (6.00 \quad \times \quad 2.72 \quad) \quad = \quad 21.42 \quad \text{E17}$$



Project Information

Building type	Detached house		
Reference	SAP/2020/022/01		
Date	18 December 2020		
Client	Kieran Napthine	Project	Tyrone House
	C/o Smith Simmons & Partners		Norton Lane
			Norton
			Chichester
			PO20 3NH

REGULATION COMPLIANCE REPORT - Approved Document L1A, 2012 Edition, England

assessed by program JPA Designer version 6.05.046, printed on 22/12/2020 at 19:50:20

New dwelling as designed

1 TER and DER

Fuel for main heating system: biogas (including anaerobic digestion) (fuel factor = 1.06)		
Target Carbon Dioxide Emission Rate	TER = 14.50	
Dwelling Carbon Dioxide Emission Rate	DER = 7.57	OK

1b TFEE and DFEE

Target Fabric Energy Efficiency (TFEE)	TFEE = 59.3	
Dwelling Fabric Energy Efficiency (DFEE)	DFEE = 53.2	OK

2a Thermal bridging

Thermal bridging calculated from linear thermal transmittances for each junction

2b Fabric U-values

Element	Average	Highest	
Wall	0.22 (max. 0.30)	0.22 (max. 0.70)	OK
Floor	0.12 (max. 0.25)	0.12 (max. 0.70)	OK
Roof	0.11 (max. 0.20)	0.16 (max. 0.35)	OK
Openings	1.42 (max. 2.00)	1.80 (max. 3.30)	OK

3 Air permeability

Air permeability at 50 pascals:	5.00	OK
Maximum :	10.00	

4 Heating efficiency

Main heating system:

Source of efficiency: Boiler and underfloor heating, biogas
from manufacturer

Efficiency: 89.0% SEDBUK2009
Minimum: 88.0%

OK

Main heating system 2:

Source of efficiency: Boiler and radiators, biogas
from manufacturer

Efficiency: 89.0% SEDBUK2009
Minimum: 88.0%

OK

Secondary heating system:

Room heater systems - Solid fuel
Closed room heater

Efficiency: 65.00%
Minimum: 65.00%

OK

5 Cylinder insulation

Hot water storage

Manufacturer's declared cylinder loss factor (kWh/day) 3.22
Permitted by DBSCG 3.92

Primary pipework insulated

Yes

OK

OK

6 Controls

(Also refer to "Domestic Building Services Compliance Guide" by the DCLG)

Space heating controls

Time and temperature zone control
Cylinderstat - Yes
Independent timer for DHW - Yes
Yes

OK

OK

OK

OK

Boiler Interlock

7 Low energy lights

Percentage of fixed lights with low-energy fittings: 100.0%
Minimum: 75.0%

OK

8 Mechanical ventilation

Worst case specific fan power : 0.19
Maximum : 0.7W/(litre/sec) for each fan

OK

9 Summertime temperature

Overheating risk (South East England):

Slight

OK

OK

Based on:

Thermal mass parameter : 102.54
Overshading : Average or unknown (20-60 % sky blocked)
Orientation : NorthWest
Ventilation rate : 4.00
Blinds/curtains :
None with blinds/shutters closed 0.00% of daylight hours

10 Key features

Ground floors U-value 0.12 W/m²K
Pitched roofs insulated between joists U-value 0.10 W/m²K
Solid door U-value 0.90 W/m²K
Low-carbon or renewable for secondary heating fuel.
Wood logs
