

GSE UltraFlex Smooth Geomembrane

GSE UltraFlex is a smooth Linear Low density polyethylene(LLDPE) Geomembrane manufactured with the highest quality resin specifically formulated for flexible geomembranes. this product is used in applications that require increased flexibility and elongation properties where differential or localized subgrade settlements may occur such as in a landfill closure application.

Product Specifications

TESTED PROPERTY	TEST METHOD	FREQUENCY	VALUES ^(*)
Thickness ⁽¹⁾ , mm	ASTM D 5199	Every roll	0.75
Density, g/cm ³ (Max)	ASTM D 792	90,000 Kg	0.939
Tensile Properties(each direction) Strength at Break, N/mm Elongation at Break, (%)	ASTM D 6693, Type IV Dumbbell, 2 imp G.L. 50 mm	9,000 Kg	19 750
Tear Resistance, N	ASTM D 1004	20,000 Kg	67
Puncture Resistance, N	ASTM D 4833	20,000 Kg	181
Carbon Black Content, % (Range)	ASTM D 4218	9,000 Kg	2.0 - 3.0
Carbon Black Dispersion	ASTM D 5596	20,000 Kg	Note ⁽²⁾
Oxidative Induction Time (OIT) min	ASTM D 3895(200 °C, O ₂ , 1atm)	90,000 Kg	> 100
TYPICAL ROLL DIMENSIONS			
Roll Length ⁽³⁾ , (m)		280	280
Roll Width ⁽³⁾ , (m)		5.8	7.0
Roll Area ⁽³⁾ , (m ²)		1624	1960
Standard Container, Roll		15	15

Revision Date: November, 2014

NOTES:

- ^(*) All values-unless otherwise noted are Minimum average values.
- ⁽¹⁾ Minimum Average Thickness: Nominal -5%.
- ⁽²⁾ Dispersion only applied to near spherical agglomerates 9 of 10 views shall be Category 1 or 2. No more than 1view from Category 3.
- ⁽³⁾ Roll lengths and widths have a tolerance of $\pm 1\%$
- GSE HD is available in rolls weighting approximately (1200 kg)
- All HD geomembranes have dimensional stability of $\pm 2\%$ when tested according to ASTM D 1204 and LTB of $> -77^{\circ}\text{C}$ when tested according to ASTM D 746.

GSE UltraFlex is produced at GSE Lining Technology-Egypt.

This information is provided for reference purposes only and is not intended as a warranty or guarantee. GSE assumes no liability in connection with the use of this information. Please check with GSE for current, standard minimum quality assurance procedures and specifications. GSE and other markets used in this document are trademarks and service marks of GSE Lining Technology, Inc.; certain of which are registered in the U.S.A. and other countries.

Middle East Headquarters
GSE Lining Technology-Egypt
 St. # 28, the 4th industrial zone
 The 6th of October City,
 Giza, Egypt

Corporate Headquarters
GSE Lining Technology, Inc.
 19103 Gundle Road
 Houston, Texas 77073
 USA

Other production Facilities & Sales Offices
 Germany
 United kingdom
 Thailand
 Australia
 Russia
 Spain
 Turkey

