

**Conversion of existing barn
At
Sack Lane, Lidsey**

Schedule of external materials

Existing building

Walls:

Existing brick and flint walls to be retained.
Repairs and detailing around new openings formed with
Red/brown stock brick work to match existing.

Stained feather edge boarding to gable to be replaced with matching boarding

Roof:

Existing slate roof covering to be retained.

Doors and windows:

All doors and windows to be stained timber.

Proposed Extension

Walls :

Walls constructed in a red/brown stock brick to match existing

Roof :

New roof to be clad with natural slates to match existing.
Re-using slates stripped from existing roof where new roof abuts.

Doors and windows:

All doors and windows to be stained timber.

New Window Openings

Existing door opening on east elevation to be adapted to form new window. Existing brick arch to be carefully taken down whilst supporting wall and roof over. New matching brick arch formed at a higher level with pre-cast concrete lintels supporting masonry behind.

Opening in-filled up to cill level with matching brick work, brick bonded into existing brick reveals.

New door and window openings formed on south elevation with brick arches over and brick work to reveals matching existing.

On north elevation existing stable doors to be carefully removed, taking care not to damage existing brick reveals. Wall and roof over opening to be temporarily supported and existing concrete lintels to be carefully removed. New brick arches formed over openings in brick work to match existing. New thresholds formed at new floor level in matching brick work.

Below windows to living room and bedroom opening partially in-filled with timber framing clad externally with feather edge boarding.

New doors and windows to be purpose made stained timber.

External Cladding

All existing stained feather edge boarding to be replaced with new matching stained timber.

Extension

New extension to be constructed in accordance with drawings 07/87/03 revision A and 07/87/04.