

H J Concepts Ltd
Suite A 2nd Floor Trinity Court
2-4 West Street Fareham

Land to South of Sundown

Revision

Job No:

17-1197

Page:

SW-

Section:

Main Soakaway House & Garage (FOS 2.0 on 'f')

Prepared By:

PH

Date:

17/03/2022

ALTERNATIVE SOAKAWAY SIZES

	trench soakaways		
width of trench [mm]:	2000	2500	3000
required trench length [m]:	10.78	9.00	7.69
	ring soakaways		
diameter of ring [mm]:	1050	1350	1500
required pit diameter [m]:	2.99	2.99	2.99

* Based on effective depth and number of pits as in Soakaway Data table

SUMMARY OF CALCULATIONS

critical design rainfall duration t_{crit}	=	240	min
required storage volume V_{req}	=	21.37	m ³
provided storage volume V_{prov}	=	24.23	m ³
utilisation factor	=	0.88	.OK
required time to discharge 50% t_{50}	=	6.10	hours
utilisation factor	=	0.25	.OK

GENERAL DATA

site location:	England and Wales
soakaway type:	geocellular units
impermeable area drained to soakaway 'A' [m ²]	355
60 min rainfall depth of 5 year return period 'R' [mm]	20
M5-60 to M5-2d rainfall ratio 'r'	0.35
allowance for climate change:	40%

SOAKAWAY DATA

soakaway width 'W' [m]	=	3.00
soakaway length 'L' [m]	=	2.50
total depth from ground level 'D _b ' [m]	=	1.50
depth to drain invert level 'D _d ' [m]	=	0.50
soakaway effective depth 'D _{eff} ' [m]	=	1.00
free volume in infill aggregate [%]	=	95

SOIL INFILTRATION DATA

allowance for infiltration through soakaway base:	No
available on-site infiltration test results:	☐ Yes ☒ No
soil infiltration rate 'f' [m/s]	4.80E-05

REQUIRED STORAGE CAPACITY PER RAINFALL DURATION

rainfall duration [min]	rainfall factor Z1	M5-D rainfalls [mm]	M10-D			M100-D			ignore			outflow from soakaway [m ³]	required storage [m ³]
			Z2	rainfalls [mm]	inflow [m ³]	Z2	rainfalls [mm]	inflow [m ³]	Z2	rainfalls [mm]	inflow [m ³]		
5	0.36	7.13	1.20	12.01	4.26	1.84	18.39	6.53				0.17	6.36
10	0.51	10.13	1.22	17.32	6.15	1.91	27.13	9.63				0.33	9.30
15	0.62	12.33	1.23	21.23	7.54	1.95	33.62	11.94				0.50	11.44
30	0.79	15.73	1.24	27.31	9.70	2.00	43.96	15.61				0.99	14.61
60	1.00	20.00	1.24	34.72	12.33	2.03	56.84	20.18				1.99	18.19
120	1.22	24.47	1.24	42.47	15.08	2.01	68.92	24.47				3.97	20.49
240	1.50	29.93	1.22	51.14	18.15	1.97	82.58	29.32				7.95	21.37
360	1.69	33.80	1.21	57.19	20.30	1.94	91.78	32.58				11.92	20.66
600	1.95	38.93	1.19	65.04	23.09	1.90	103.48	36.74				19.87	16.86
1440	2.48	49.60	1.17	81.30	28.86	1.81	125.91	44.70				47.69	0.00

* Z2 is growth factor from M5 rainfalls