



Opus International Consultants (UK) Ltd
 Modulus House
 Salterns Lane
 Fareham
 Hampshire
 PO16 0QS

Project No.: 8849 Date: 30.06.2011 TSA 1
 Project Title: The Homestead Ph. 2 30% Rev 0

Reject/Rubble Filled Soakaway Assessment to BRE Digest 365

Site Location: Westergate, W Sussex

$r = 0.37$ (range 0.12 to 0.45)

Drained Area = 344 m²

Pit Length $L_x = 2.5$ m

Pit Length $L_y = 8$ m

Soakaway Invert = 9.5 m

Entry Pipe Invert = 10.3 m

% Void in fill = 95 %

TOTAL STORAGE AVAILABLE 15.2 m³

Effective soakage area a_{50} 8.4 m²

Soil Filtration Rate = 6.96E-06 m/s

M5-60 Rainfall = 20 mm

Storm Duration	5 min	10 min	15 min	30 min	1 hr	2 hr	4 hr	6 hr	10 hr	24 hr
(secs)	300	600	900	1800	3600	7200	14400	21600	36000	86400
Value Z1	0.363	0.513	0.623	0.793	1	1.216	1.473	1.653	1.873	2.373
Rainfall M5 (mm)	7.26	10.26	12.46	15.86	20	24.32	29.46	33.06	37.46	47.46
Value Z2	1.203	1.221	1.229	1.24	1.24	1.24	1.222	1.21	1.197	1.175
Rainfall M10 (mm)	8.73	12.52	15.31	19.66	24.8	30.15	36	40	44.83	55.76
RUNOFF (m³)	3.003	4.306	5.266	6.763	8.531	10.371	12.384	13.76	15.421	19.181
SOAKAGE (m³)	0.02	0.04	0.05	0.11	0.21	0.42	0.84	1.26	2.10	5.05
eq'd STORAGE (m³)	2.986	4.270922	5.2134	6.6578	8.3205	9.9501	11.542	12.497	13.316	14.13
	<i>pass</i>	<i>pass</i>	<i>pass</i>	<i>pass</i>	<i>pass</i>	<i>pass</i>	<i>pass</i>	<i>pass</i>	<i>pass</i>	<i>pass</i>