

Classification of sample: TP47-0.15-26/08/2025

 **Non Hazardous Waste**
Classified as **17 05 04**
in the List of Waste

Sample details

Sample name:	LoW Code:
TP47-0.15-26/08/2025	Chapter:
Sample Depth:	17: Construction and Demolition Wastes (including excavated soil from contaminated sites)
0.15 m	Entry:
Moisture content:	17 05 04 (Soil and stones other than those mentioned in 17 05 03)
9.9%	
(no correction)	

Hazard properties

None identified

Determinands

Moisture content: 9.9% No Moisture Correction applied (MC)

#	Determinand			CLP Note	User entered data	Conv. Factor	Compound conc.		Classification value	MC Applied	Conc. Not Used
	EU CLP index number	EC Number	CAS Number								
1	pH		PH		5.7 pH		5.7 pH		5.7 pH		
2	arsenic { arsenic trioxide }				8 mg/kg	1.32	10.563 mg/kg		0.00106 %		
	033-003-00-0	215-481-4	1327-53-3								
3	boron { diboron trioxide }				<1 mg/kg	3.22	<3.22 mg/kg		<0.000322 %		<LOD
	005-008-00-8	215-125-8	1303-86-2								
4	cadmium { cadmium oxide }				<0.2 mg/kg	1.142	<0.228 mg/kg		<0.0000228 %		<LOD
	048-002-00-0	215-146-2	1306-19-0								
5	chromium in Cr(III) compounds { chromium(III) oxide (worst case) }				21 mg/kg	1.462	30.693 mg/kg		0.00307 %		
		215-160-9	1308-38-9								
6	chromium in Cr(VI) compounds { chromium (VI) compounds, with the exception of barium chromate and of compounds specified elsewhere in this Annex }				<2 mg/kg	2.27	<4.54 mg/kg		<0.000454 %		<LOD
	024-017-00-8										
7	copper { dicopper oxide; copper (I) oxide }				14 mg/kg	1.126	15.762 mg/kg		0.00158 %		
	029-002-00-X	215-270-7	1317-39-1								
8	lead { lead chromate }			1	45 mg/kg	1.56	70.192 mg/kg		0.0045 %		
	082-004-00-2	231-846-0	7758-97-6								
9	mercury { mercury dichloride }				<1 mg/kg	1.353	<1.353 mg/kg		<0.000135 %		<LOD
	080-010-00-X	231-299-8	7487-94-7								
10	nickel { nickel chromate }				13 mg/kg	2.976	38.691 mg/kg		0.00387 %		
	028-035-00-7	238-766-5	14721-18-7								
11	selenium { nickel selenate }				<2 mg/kg	2.554	<5.108 mg/kg		<0.000511 %		<LOD
	028-031-00-5	239-125-2	15060-62-5								
12	zinc { zinc sulphate }				62 mg/kg	2.469	153.096 mg/kg		0.0153 %		
	030-006-00-9	231-793-3 [1] 231-793-3 [2]	7446-19-7 [1] 7733-02-0 [2]								
13	TPH (C6 to C40) petroleum group		TPH		24 mg/kg		24 mg/kg		0.0024 %		
14	naphthalene				<0.1 mg/kg		<0.1 mg/kg		<0.00001 %		<LOD
	601-052-00-2	202-049-5	91-20-3								
15	acenaphthylene				<0.1 mg/kg		<0.1 mg/kg		<0.00001 %		<LOD
		205-917-1	208-96-8								

#	Determinand			CLP Note	User entered data	Conv. Factor	Compound conc.	Classification value	MC Applied	Conc. Not Used
	EU CLP index number	EC Number	CAS Number							
16	acenaphthene	201-469-6	83-32-9		<0.1 mg/kg		<0.1 mg/kg	<0.00001 %		<LOD
17	fluorene	201-695-5	86-73-7		<0.1 mg/kg		<0.1 mg/kg	<0.00001 %		<LOD
18	phenanthrene	201-581-5	85-01-8		<0.1 mg/kg		<0.1 mg/kg	<0.00001 %		<LOD
19	anthracene	204-371-1	120-12-7		<0.1 mg/kg		<0.1 mg/kg	<0.00001 %		<LOD
20	fluoranthene	205-912-4	206-44-0		0.2 mg/kg		0.2 mg/kg	0.00002 %		
21	pyrene	204-927-3	129-00-0		0.19 mg/kg		0.19 mg/kg	0.000019 %		
22	benzo[a]anthracene	601-033-00-9	200-280-6		<0.1 mg/kg		<0.1 mg/kg	<0.00001 %		<LOD
23	chrysene	601-048-00-0	205-923-4		0.13 mg/kg		0.13 mg/kg	0.000013 %		
24	benzo[b]fluoranthene	601-034-00-4	205-911-9		0.13 mg/kg		0.13 mg/kg	0.000013 %		
25	benzo[k]fluoranthene	601-036-00-5	205-916-6		<0.1 mg/kg		<0.1 mg/kg	<0.00001 %		<LOD
26	benzo[a]pyrene; benzo[def]chrysene	601-032-00-3	200-028-5		0.13 mg/kg		0.13 mg/kg	0.000013 %		
27	indeno[123-cd]pyrene	205-893-2	193-39-5		<0.1 mg/kg		<0.1 mg/kg	<0.00001 %		<LOD
28	dibenz[a,h]anthracene	601-041-00-2	200-181-8		<0.1 mg/kg		<0.1 mg/kg	<0.00001 %		<LOD
29	benzo[ghi]perylene	205-883-8	191-24-2		<0.1 mg/kg		<0.1 mg/kg	<0.00001 %		<LOD
Total:								0.0319 %		

Key

	User supplied data
	Determinand values ignored for classification, see column 'Conc. Not Used' for reason
	Determinand defined or amended by HazWasteOnline (see Appendix A)
	Speciated Determinand - Unless the Determinand is Note 1, the Conversion Factor is used to calculate the compound concentration
<LOD	Below limit of detection
CLP: Note 1	Only the metal concentration has been used for classification

Supplementary Hazardous Property Information

HP 3(i): Flammable "flammable liquid waste: liquid waste having a flash point below 60°C or waste gas oil, diesel and light heating oils having a flash point > 55°C and ≤ 75°C"

Force this Hazardous Property to non-hazardous for cumulative determinand results below the threshold of: 1000 mg/kg (0.1%) because: No free product encountered at any exploratory hole position, therefore TPH unlikely to be flammable at concentrations < 1000 mg/kg

Hazard Statements hit:

Flam. Liq. 3; H226 "Flammable liquid and vapour."

Because of determinand:

TPH (C6 to C40) petroleum group (conc.: 0.0024%)

WAC results for sample: TP47-0.15-26/08/2025

WAC Settings: samples in this Job do not constitute a single population.

WAC limits used to evaluate this sample: "UK"

The WAC used in this report are the WAC defined for the inert, stable non-reactive hazardous and hazardous classes of landfill in the UK. You should check the actual acceptance criteria when the disposal site is identified as they may differ from the generic WAC used in this report.

The sample cannot be evaluated against the Inert (Inert waste landfill) criteria because of missing determinand values.

The sample cannot be evaluated against the SNRHW (Stable non-reactive hazardous waste in non-hazardous landfill) criteria because of missing determinand values.

WAC Determinands

Solid Waste Analysis			Landfill Waste Acceptance Criteria Limits		
#	Determinand	User entered data	Inert waste landfill	Stable non-reactive hazardous waste in non-hazardous landfill	Hazardous waste landfill
1	TOC (total organic carbon)	%	3	5	6
2	LOI (loss on ignition)	%	-	-	10
3	BTEX (benzene, toluene, ethylbenzene and xylenes)	mg/kg	6	-	-
4	PCBs (polychlorinated biphenyls, 7 congeners)	mg/kg	1	-	-
5	Mineral oil (C10 to C40)	mg/kg	500	-	-
6	PAHs (polycyclic aromatic hydrocarbons)	mg/kg	100	-	-
7	pH	pH	-	>6	-
8	ANC (acid neutralisation capacity)	mol/kg	-	-	-
Eluate Analysis 10:1					
9	arsenic	mg/kg	0.5	2	25
10	barium	mg/kg	20	100	300
11	cadmium	mg/kg	0.04	1	5
12	chromium	mg/kg	0.5	10	70
13	copper	mg/kg	2	50	100
14	mercury	mg/kg	0.01	0.2	2
15	molybdenum	mg/kg	0.5	10	30
16	nickel	mg/kg	0.4	10	40
17	lead	mg/kg	0.5	10	50
18	antimony	mg/kg	0.06	0.7	5
19	selenium	mg/kg	0.1	0.5	7
20	zinc	mg/kg	4	50	200
21	chloride	mg/kg	800	15,000	25,000
22	fluoride	mg/kg	10	150	500
23	sulphate	mg/kg	1,000	20,000	50,000
24	phenol index	mg/kg	1	-	-
25	DOC (dissolved organic carbon)	mg/kg	500	800	1,000
26	TDS (total dissolved solids)	mg/kg	4,000	60,000	100,000

Key

	User supplied data
	Not applicable
	Missing WAC determinand value
	SNRHW WAC criteria fail

Appendix A: Classifier defined and non GB MCL determinands

■ pH (CAS Number: PH)

Description/Comments: Appendix C4
Data source: WM3 1st Edition 2015
Data source date: 25 May 2015
Hazard Statements: None.

■ chromium(III) oxide (worst case) (EC Number: 215-160-9, CAS Number: 1308-38-9)

Description/Comments: Data from C&L Inventory Database
Data source: <https://echa.europa.eu/information-on-chemicals/cl-inventory-database/-/discli/details/33806>
Data source date: 17 Jul 2015
Hazard Statements: Acute Tox. 4; H332, Acute Tox. 4; H302, Eye Irrit. 2; H319, STOT SE 3; H335, Skin Irrit. 2; H315, Resp. Sens. 1; H334, Skin Sens. 1; H317, Repr. 1B; H360FD, Aquatic Acute 1; H400, Aquatic Chronic 1; H410

■ TPH (C6 to C40) petroleum group (CAS Number: TPH)

Description/Comments: Unknown Oil

Hazard statements taken from WM3 1st Edition 2015
Data source: WM3 1st Edition 2015
Data source date: 25 May 2015
Hazard Statements: Flam. Liq. 3; H226, Asp. Tox. 1; H304, STOT RE 2; H373, Muta. 1B; H340, Carc. 1B; H350, Repr. 2; H361d, Aquatic Chronic 2; H411

■ acenaphthylene (EC Number: 205-917-1, CAS Number: 208-96-8)

Description/Comments: Data from C&L Inventory Database
Data source: <http://echa.europa.eu/web/guest/information-on-chemicals/cl-inventory-database>
Data source date: 17 Jul 2015
Hazard Statements: Acute Tox. 4; H302, Acute Tox. 1; H330, Acute Tox. 1; H310, Eye Irrit. 2; H319, STOT SE 3; H335, Skin Irrit. 2; H315

■ acenaphthene (EC Number: 201-469-6, CAS Number: 83-32-9)

Description/Comments: Data from C&L Inventory Database
Data source: <http://echa.europa.eu/web/guest/information-on-chemicals/cl-inventory-database>
Data source date: 17 Jul 2015
Hazard Statements: Eye Irrit. 2; H319, STOT SE 3; H335, Skin Irrit. 2; H315, Aquatic Acute 1; H400, Aquatic Chronic 1; H410, Aquatic Chronic 2; H411

■ fluorene (EC Number: 201-695-5, CAS Number: 86-73-7)

Description/Comments: Data from C&L Inventory Database
Data source: <http://echa.europa.eu/web/guest/information-on-chemicals/cl-inventory-database>
Data source date: 06 Aug 2015
Hazard Statements: Aquatic Acute 1; H400, Aquatic Chronic 1; H410

■ phenanthrene (EC Number: 201-581-5, CAS Number: 85-01-8)

Description/Comments: Data from C&L Inventory Database
Data source: <http://echa.europa.eu/web/guest/information-on-chemicals/cl-inventory-database>
Data source date: 06 Aug 2015
Hazard Statements: Acute Tox. 4; H302, Eye Irrit. 2; H319, STOT SE 3; H335, Carc. 2; H351, Skin Sens. 1; H317, Aquatic Acute 1; H400, Aquatic Chronic 1; H410, Skin Irrit. 2; H315

■ anthracene (EC Number: 204-371-1, CAS Number: 120-12-7)

Description/Comments: Data from C&L Inventory Database
Data source: <http://echa.europa.eu/web/guest/information-on-chemicals/cl-inventory-database>
Data source date: 17 Jul 2015
Hazard Statements: Eye Irrit. 2; H319, STOT SE 3; H335, Skin Irrit. 2; H315, Skin Sens. 1; H317, Aquatic Acute 1; H400, Aquatic Chronic 1; H410

■ fluoranthene (EC Number: 205-912-4, CAS Number: 206-44-0)

Description/Comments: Data from C&L Inventory Database
Data source: <http://echa.europa.eu/web/guest/information-on-chemicals/cl-inventory-database>
Data source date: 21 Aug 2015
Hazard Statements: Acute Tox. 4; H302, Aquatic Acute 1; H400, Aquatic Chronic 1; H410

■ pyrene (EC Number: 204-927-3, CAS Number: 129-00-0)

Description/Comments: Data from C&L Inventory Database; SDS Sigma Aldrich 2014
Data source: <http://echa.europa.eu/web/guest/information-on-chemicals/cl-inventory-database>
Data source date: 21 Aug 2015
Hazard Statements: Skin Irrit. 2; H315, Eye Irrit. 2; H319, STOT SE 3; H335, Aquatic Acute 1; H400, Aquatic Chronic 1; H410

■ **indeno[123-cd]pyrene** (EC Number: 205-893-2, CAS Number: 193-39-5)

Description/Comments: Data from C&L Inventory Database
Data source: <http://echa.europa.eu/web/guest/information-on-chemicals/cl-inventory-database>
Data source date: 06 Aug 2015
Hazard Statements: Carc. 2; H351

■ **benzo[ghi]perylene** (EC Number: 205-883-8, CAS Number: 191-24-2)

Description/Comments: Data from C&L Inventory Database; SDS Sigma Aldrich 28/02/2015
Data source: <http://echa.europa.eu/web/guest/information-on-chemicals/cl-inventory-database>
Data source date: 23 Jul 2015
Hazard Statements: Aquatic Acute 1; H400 , Aquatic Chronic 1; H410

Appendix B: Rationale for selection of metal species

arsenic {arsenic trioxide}

Reasonable case CLP species based on hazard statements/molecular weight and most common (stable) oxide of arsenic. Industrial sources include: smelting; main precursor to other arsenic compounds

boron {diboron trioxide}

Reasonable case CLP species based on hazard statements/ molecular weight, physical form and low solubility. Industrial sources include: fluxing agent for glass/enamels; additive for fibre optics, borosilicate glass

cadmium {cadmium oxide}

Reasonable case CLP species based on hazard statements/molecular weight, very low solubility in water. Industrial sources include: electroplating baths, electrodes for storage batteries, catalysts, ceramic glazes, phosphors, pigments and nematocides. Worst case compounds in CLP: cadmium sulphate, chloride, fluoride & iodide not expected as either very soluble and/or compound's industrial usage not related to site history

chromium in Cr(III) compounds {chromium(III) oxide (worst case)}

Reasonable case species based on hazard statements/molecular weight. Industrial sources include: tanning, pigment in paint, inks and glass

chromium in Cr(VI) compounds {chromium (VI) compounds, with the exception of barium chromate and of compounds specified elsewhere in this Annex}

Worst case species based on hazard statements/molecular weight

copper {dicopper oxide; copper (I) oxide}

Reasonable case CLP species based on hazard statements/molecular weight and insolubility in water. Industrial sources include: oxidised copper metal, brake pads, pigments, antifouling paints, fungicide. Worse case copper sulphate is very soluble and likely to have been leached away if ever present and/or not enough soluble sulphate detected.

lead {lead chromate}

Worst case CLP species based on hazard statements/molecular weight

mercury {mercury dichloride}

Worst case CLP species based on hazard statements/molecular weight

nickel {nickel chromate}

Worst case CLP species based on hazard statements/molecular weight

selenium {nickel selenate}

Worst case CLP species based on hazard statements/molecular weight

zinc {zinc sulphate}

Worst case CLP species based on hazard statements/molecular weight is zinc chromate. But no detectable Cr (VI) is present to form zinc chromate. Therefore next realistic worst CLP species based on hazard statements/molecular weight has been selected, which is zinc sulphate.

Appendix C: Version

HazWasteOnline Classification Engine: WM3 1st Edition v1.2.GB - Oct 2021
HazWasteOnline Classification Engine Version: 2025.318.6867.12415 (15 Nov 2025)
HazWasteOnline Database: 2025.318.6867.12415 (15 Nov 2025)

This classification utilises the following guidance and legislation:

WM3 v1.2.GB - Waste Classification - 1st Edition v1.2.GB - Oct 2021

CLP Regulation - Regulation 1272/2008/EC of 16 December 2008

1st ATP - Regulation 790/2009/EC of 10 August 2009

2nd ATP - Regulation 286/2011/EC of 10 March 2011

3rd ATP - Regulation 618/2012/EU of 10 July 2012

4th ATP - Regulation 487/2013/EU of 8 May 2013

Correction to 1st ATP - Regulation 758/2013/EU of 7 August 2013

5th ATP - Regulation 944/2013/EU of 2 October 2013

6th ATP - Regulation 605/2014/EU of 5 June 2014

WFD Annex III replacement - Regulation 1357/2014/EU of 18 December 2014

Revised List of Waste 2014 - Decision 2014/955/EU of 18 December 2014

7th ATP - Regulation 2015/1221/EU of 24 July 2015

8th ATP - Regulation (EU) 2016/918 of 19 May 2016

9th ATP - Regulation (EU) 2016/1179 of 19 July 2016

10th ATP - Regulation (EU) 2017/776 of 4 May 2017

HP14 amendment - Regulation (EU) 2017/997 of 8 June 2017

13th ATP - Regulation (EU) 2018/1480 of 4 October 2018

14th ATP - Regulation (EU) 2020/217 of 4 October 2019

15th ATP - Regulation (EU) 2020/1182 of 19 May 2020

The Chemicals (Health and Safety) and Genetically Modified Organisms (Contained Use)(Amendment etc.) (EU Exit)

Regulations 2020 - UK: 2020 No. 1567 of 16th December 2020

The Waste and Environmental Permitting etc. (Legislative Functions and Amendment etc.) (EU Exit) Regulations 2020 - UK:

2020 No. 1540 of 16th December 2020

GB MCL List - version 1.1 of 09 June 2021

GB MCL List v2.0 - version 2.0 of 20th October 2023

GB MCL List v3.0 - version 3.0 of 11th January 2024

GB MCL List v4.0 - version 4.0 of 2nd March 2024

GB MCL List v5.0 - version 5.0 of 26th June 2024

GB MCL List v6.0 - version 6.0 of 15th February 2025

GB MCL List v7.0 - version 7.0 of 23rd September 2025

APPENDIX J

Waste Disposal Ticket



L&S Waste Management Ltd
Titchfield House
Pegham Industrial Park
Laveys Lane
Fareham
PO15 6SD

Waste Transfer Note
Carrier Licence: CBDU198877
VAT Reg: 503 895 927
Permit No: EPR/DP3091EQ
Company Reg: 03475329

EXCHANGE

Account No. TRAVIS		Site Address	
TRAVIS PERKINS LIMITED ACCOUNTS PAYABLE L1572 WASTE MANAGEMENT LTD LODGE WAY HOUSE HARLESTONE ROAD NN5 7UG		C/O ASHMARDEN LTD LIDSEY ROAD NURSERY WOODGATE CHICHESTER PO20 3SU	Ticket No. 2451964
			Date 27-04-2026
			Payment Method Account
		SITE CONTACT: GARY STRUDWICK [REDACTED]	Order Number 3862006225

Transaction Details		Special Instructions	
Vehicle Reg	WU70AOX	Area	FAREHAM
Driver	Neil Cable	SIC Code	41100
Skip Size	12 Yard 9.2 m3 Mammoth Skip (Enc)		
Waste Type	Cement Bonded Asbestos		
EWC Code	17 06 05		

Warning - Under the Duty of Care Environmental Protection Act 1990, the hirer is responsible for informing the driver of the contents of the skip.

CONDITIONS OF SKIP HIRE

Any waste containing hazardous properties should **NOT** be placed into the skip i.e. anything that would cause harm to air, water, land, humans or animals. The following items are **EXCLUDED** and should not be placed into our skips - **Asbestos, Chemicals, Japanese Knotweed, Liquid Paint, Lithium Batteries, Medical / Clinical Waste, Railway Sleepers, Vehicle Batteries.**

L&S Waste Management Ltd can assist in the responsible disposal of these **EXCLUDED** items, please contact 01329 840000 for further details.

Some NON-HAZARDOUS waste items can be placed into our skips subject to an additional charge - **Arm Chairs / Bean Bag / Office Chair - Containing POP'S Persistent Organic Pollutants, Car Tyre, Fire Extinguisher, Fridge/Freezer, Tree Root, Mattress, Small Domestic Appliance (TV, Microwave Etc.)**

Should you require any assistance with your skip hire please contact our Customer Service Team on [REDACTED]
Full terms and conditions can be found on our web site. www.lswaste.co.uk/news-media/legal-and-downloads

I agree that the waste transferred is as stated above and I confirm that I have fulfilled my duty to apply the waste hierarchy by Regulation 12 of the Waste (England and Wales) Regulations 2011 and all current amendments. For and on behalf of the customer. I have read and accept the Terms and Conditions of Server / Hire which are available on our Website:

Signature: [REDACTED]

Print Name: G Strudwick

DISPOSAL INFORMATION

DISPOSAL POINT		HAULIER	
Waste Disposal Licence No:	EPR/BU812617/V018	Waste Carrier Signature:	[REDACTED]
BiffaRedhill North East Quadrant Cormongers Lane Nutfield Surrey RH1 4ER	Gross Weight: 0 Tare Weight: 0 Net Weight: 2720 Ticket No: I1111474	Print Name: Neil Cable Date: 27-April-2026	