




From: Sarah Burrow <Sarah.Burrow@arun.gov.uk>
Sent: 21 June 2022 10:51
To: Planning.Responses <Planning.Responses@arun.gov.uk>
Cc: Amber Willard <Amber.Willard@arun.gov.uk>
Subject: RE: Planning Consultation on: AL/54/22/HH

Engineers Comments Regarding Surface Water Drainage

The application is within the Lidsey Treatment Catchment, therefore surface water drainage design should be carefully considered. Infiltration must be fully investigated.

Existing and proposed trees (root protection zones) must not conflict with suds features/pipework.

PCENG D2

“Development shall not commence, other than works of site survey and investigation, until full details of the proposed surface water drainage scheme have been submitted to and approved in writing by the Local Planning Authority. The design should follow the hierarchy of preference for different types of surface water drainage disposal systems as set out in Approved Document H of the Building Regulations, and the recommendations of the SuDS Manual produced by CIRIA. Winter groundwater monitoring to establish highest annual ground water levels and winter percolation testing to BRE 365, or similar approved, will be required to support the design of any infiltration drainage. No building / No part of the extended building shall be occupied until the complete surface water drainage system serving the property has been implemented in accordance with the agreed details and the details so agreed shall be maintained in good working order in perpetuity.”

Reason: To ensure that the proposed development is satisfactorily drained in accordance with policies W SP1, W DM1, W DM2 and W DM3 of the Arun Local Plan. This is required to be a pre-commencement condition because it is necessary to implement the surface water drainage system prior to commencing any building works.

And the accompanying informative:

INFORMD

"Infiltration rates for soakage structures are to be based on percolation tests undertaken in the winter period and at the location and depth of the proposed structures. The infiltration tests must be carried out in accordance with BRE365, CIRIA R156 or a similar approved method. All design storms must include a climate change allowance, as per <https://www.gov.uk/guidance/flood-risk-assessments-climate-change-allowances>, on stored volumes or rainfall intensity. Infiltration structures must cater for the critical 1 in 10 year storm event, (plus 40%) between the invert of the entry pipe to the soakaway and the base of the structure. All surface water drainage designs must also have provision to ensure there is capacity in the system to contain the critical 1 in 100 year storm event (plus 45%).

Adequate freeboard must be provided between the base of the soakaway structure and the highest recorded annual groundwater level identified in that location. Any SuDS or soakaway design must include adequate groundwater monitoring data to determine the highest groundwater table in support of the design. The applicant is advised to discuss the extend of ground water monitoring with the council's engineers.

Supplementary guidance notes regarding surface water drainage are located at <https://www.arun.gov.uk/drainage-planning-consultations> on Arun District Council's website. A surface water drainage checklist is available on Arun District Council's website, this should be submitted with a Discharge of Conditions Application."

Kind regards

Sarah Burrow
Engineering Assistant, Engineering Services

T: 01903 737815
E: sarah.burrow@arun.gov.uk



Current working pattern: Monday-Friday, 8am - 2:30pm

Arun District Council, Civic Centre, Maltravers Rd, Littlehampton, West Sussex, BN17 5LF
www.arun.gov.uk

Sign up to our newsletter [here](#)



From: Planning.Responses <Planning.Responses@arun.gov.uk>
Sent: 04 May 2022 11:49
To: Land Drainage <Land.Drainage@arun.gov.uk>
Subject: Planning Consultation on: AL/54/22/HH

To: **Engineers (Drainage)**

NOTIFICATION FROM ARUN DISTRICT COUNCIL

Town & Country Planning Act 1990 (as amended)
Town & Country Planning (Development Management Procedure) (England) Order 2015

Planning Permission for Works or Extension to a Dwelling

Application No: AL/54/22/HH
Registered: 3rd May 2022
Site Address: Dove Cottage Nyton Road Westergate PO20 3UN
Grid Reference: 494018 105619
Description of Works: Creation of first floor with 2 x rear dormers with juliet balconies and 3 x front rooflights, erection of single storey rear extension, summer house to rear, installation of car port to front and alterations to fenestration.

The Council have received the above application.

[Click here to view the application details](#)

This application has been identified as CIL Liable. Therefore please be aware that, in accordance with Appendix 2 of the Arun CIL Charging Schedule, your consultation response should only include requests for Section 106 for onsite mitigation, Pagham Harbour Management Contributions (if applicable) or Affordable Housing. "Off" Site mitigation measures directly related to this development should be dealt with by condition if possible to ensure the scaling back of Section 106 if possible. CIL contributions will be used for "off" site infrastructure mitigation schemes. Therefore if this proposal triggers the need for "off" site mitigation, please ensure that you engage in the CIL Infrastructure List Consultation process upon receipt of a consultation letter.

Should you have any comments to make, these should be sent by replying to this email by 11th June 2022 . You can also monitor the progress of this application through the Council web site:

<https://www.arun.gov.uk/planning-application-search>

The application will be determined having regard to the development plan policies (if any are relevant) and other material considerations. The development plan can be accessed via the website

<https://www.arun.gov.uk/development-plan> as can information on what comments we can consider

<https://www.arun.gov.uk/planning-application-comments>

Please be aware that any comments you may make will be available on our website so please do not insert personal details or signatures on your reply.

Should the application go to appeal the Planning Inspectorate will publish any comments made to the Council on their website: <https://app.planninginspectorate.gov.uk/> but they will protect personal details.

When the appeal relates to a householder application there will be no opportunity to make further comments.

In the absence of a reply within the period stated, I shall assume that you have no observations to make

Yours sincerely

Amber Willard

Planning Officer- Arun District Council

Telephone: 01903 737500 x37445

Email: amber.willard@arun.gov.uk

