

Lidsey Road, Woodgate

Phase 2

LANDSCAPE MANAGEMENT PLAN

Client: Barratt Redrow Homes



Green Landscape Studio Ltd.
Lakeside Centre
Wide Lane
Eastleigh
Hampshire
SO50 5PD

T| 

CONTENTS

1. Introduction	3
2. Management responsibility	4
3. Preliminaries	5
4. General maintenance	6
5. Existing trees and vegetation	7
6. Mown grassland and lawn areas	8
7. Wildflower/long grassland areas	9
8. Tussocky grassland areas	11
9. Wetland areas and ponds	12
10. Tree planting	14
11. Hedgerow	15
12. Native scrub planting	17
13. Ornamental planting	18
14. Hard surfacing	20
15. Fencing and railing	20
16. Site furniture	20
17. Play Areas	21

Job No.	GLS_020_I70_P2_I802
Rev.	A
Date	06.03.26
Author	SK/LM
Checked by	AE
Signed off by	CLIENT
Purpose	For Planning

Copyright: The contents of this document must not be copied or reproduced in whole or in part without the written consent of Green Landscape Studio Limited.

This document is produced for planning purposes only and should not be used for construction.

1. Introduction

- 1.1 This document has been prepared by Green Landscape Studio Ltd. on behalf of Barratt Redrow Homes. The document sets out the establishment and long term landscape management and maintenance for the landscaping associated with proposed development at Lidsey Road, Woodgate Phase 2.
- 1.2 The Management plan provides information on managing the landscape elements within the site boundary to enhance the amenity and biodiversity value and connectivity to the surrounding landscape.
- 1.3 This management plan should be made available to new residents to help outline the principles of the retained habitat and encourage the future managed of these areas in perpetuity.
- 1.4 The hard and soft landscaping associated with the development consist of a variety of separate elements, including the following:
 - Plot Landscaping
 - Public Open Space
 - Play Ares
 - SuDS

Associated information

- 1.5 This document is based on the following drawings:
 - Illustrative Masterplan GLS_020_170_P2_1200
 - Landscape General Arrangement Plan GLS_020_170_P2_1300
 - Detailed Planting Plans GLS_020_170_P2_1500 to 1508
 - Detailed Play Area Proposals GLS_020_170_P2_2001 to 2002
- 1.6 This document should also be read in conjunction with the following documents:
 - Landscape Specification GLS_020_170_P2_266_1801

2. Management responsibility

- 2.1 The landscaping within individual plot boundaries will be the responsibility of the domestic owners. Where properties are not sold, the management will remain with Barratt Redrow Homes and their appointed management company.
- 2.2 Any areas of public realm and public open space within the site boundary will be the responsibility of Barratt Redrow Homes and their appointed management company until such time where a resident run and/or social housing management company is set up and the responsibility is handed over. Adopted roads and ancillary footpaths/verges will be the responsibility of the relevant highway authority and will not be detailed further in this management plan.
- 2.3 Any appointed management company or their appointed contractors will require the necessary experience and certificates of competence to undertake landscape management operations on site. Where practical, contractors with relevant experience in biodiversity management will be sought. The managing organisation is responsible in ensuring that the management complies with the guidelines set out in this plan.

3. Preliminaries

Pre-practical completion

- 3.1 Any plants found to be defective before or at Practical Completion should be rectified in the first available planting season. This includes general plant failure as well as failure as the result of malicious damage or theft, lack of vigour, poor materials or any plants not in line with the approved drawings and associated specification. Replacement planting shall be carried out by the contractor at their own expense.
- 3.2 The relevant sections of this management plan should be implemented immediately post installation of each element, to ensure healthy establishment of the proposed planting and avoid future maintenance issues upon the handover of the landscaping to the appointed management company or domestic owners.

Post practical completion (Defects period)

- 3.3 During the defects period the contractor will maintain the installed landscaping in line with this management plan until such time where it is handed over to the appointed management company or domestic owners.
- 3.4 Any plants found to be defective during the defects period should be rectified in the first available planting season. Plant failure is as defined in point 3.1. Planting shall be replaced by the contractor at their own expense.

Post defects period

- 3.5 Post the defects period the maintenance of the landscape will be the responsibility of the appointed management company, with private areas maintained by the domestic owners. The maintenance will be in perpetuity in line with the objectives set out in the management plan and the approved drawings, unless otherwise agreed by the Local Planning Authority.
- 3.6 Replacement of planting shall take place as many times as is necessary in order to maintain a complete cover of plants and to maintain the scheme as designed and within the correct planting season. This is to ensure compliance with the planning approval for the site.
- 3.7 The replacement planting shall be carried out by the appointed management company and will be at their expense.
- 3.8 Following the end of the initial five year period of this management plan programme, the management plan will be re-assessed and updated in line with guidance current at the time of review and any site surveys and inspections carried out. Any changes made/proposed should not be detrimental to the amenity and biodiversity objectives set out in the approved landscape proposals.

4. General maintenance

- 4.1 All soft landscaping areas shall be maintained in line with the details set out in this management plan and in line with the intended landscape design as shown on the approved drawings.
- 4.2 All soft landscaping areas within the management company's responsibility shall be inspected and assessed on a monthly basis in order to ensure that the site is being managed appropriately and to ensure that health and safety hazards are minimised. Inspections shall be carried out by a competent person, either a member of BALI or the LI, acting for the management company, with work carried out as required.
- 4.3 Any health and safety risks picked up outside the control of the management company's responsibility, i.e. in domestic gardens, shall be highlighted to the responsible party. The works to be carried out in relation to these areas will lie in the responsibility of said party.
- 4.4 No existing trees shall be removed or cut without written agreement from the Local Planning Authority. Existing trees are to be retained, protected and undisturbed during the contract.
- 4.5 Any rectification of plant failure should be carried out in line with the approved drawings and specification, unless otherwise agreed by the local Planning Authority.
- 4.6 The management company is responsible for litter picking and the emptying of litter bins in those areas which it manages. This shall initially be carried out every 2 weeks, with the frequency reviewed regularly to ensure the site has a neat and tidy appearance and bins don't create a health and safety risk.
- 4.7 All maintenance should be carried out to the relevant sections of BS 7370 – Grounds Maintenance.

Long term management objectives

- 4.8 The long term management objectives of this plan are:
 - To provide a high quality, well maintained and attractive landscape setting for the development and local community which will tie into the existing landscape setting
 - To establish and maintain health and safety procedures for the management and maintenance of the site
 - To establish a landscape which can be used for recreation by the new residents and local community
 - To establish and maintain habitat for wildlife to ensure the landscape complies to the biodiversity net gain requirements
 - To comply with legal obligations and constraints and demonstrate use of best practice

5. Existing trees and vegetation

Maintenance objectives

- Retain and protect existing trees and vegetation as shown on the tree protection plans and landscape proposals
- Mitigate any negative impacts on existing retained trees and vegetation, including disturbance to ecological habitat

Maintenance operations

- 5.1 Management of existing trees and vegetation will be carried out in line with the Arboriculture Impact Assessment and Method Statement.
- 5.2 Existing trees will require limited maintenance over the coming years, with pruning undertaken when required. The following specification is applicable to all arboricultural works:
 - A qualified arboriculturist should be consulted prior to any work taking place.
 - All work should be carried out to BS3998 – Tree Work Recommendations and by a recognised tree contracting company from the Arboricultural Association's list of registered contractors.
 - All work shall be carried out at an appropriate time and with the consent of the management company and local authority if necessary.
- 5.3 All trees on site should be visually checked annually and immediately after adverse weather events. These checks should be staggered so that trees are inspected at different times of the year. Any trees which display signs of stress, decline, decay or damage should have the necessary work carried out as above. A detailed trees inspection should be carried out by a competent person at least once every three years.
- 5.4 All arisings from any work carried out should be removed from site, unless otherwise specified by the ecologist. The work site should be left clean and tidy.
- 5.5 Where heavy ivy infestation is present this can be removed by cutting any ivy stems at the base of the tree during the maintenance period.
- 5.6 Long term maintenance of existing retained hedgerow and scrub planting shall be maintained in line with the relevant 'Hedgerow' and 'Scrub planting' chapter in this plan.

6. Mown grassland and lawn areas

Maintenance objectives

- Maintain a healthy vigorous sward, free from disease, fungal growth, discolouration, scorch or wilt
- Prevent compaction or waterlogging
- Repair any damaged areas
- Retain a neat appearance

Maintenance operations

- 6.1 Mown grassland areas, as shown on the landscape proposals, shall be cut during the growing season, generally between April and October, to a height of 25-40mm with arisings removed from site. Ensure all debris and litter is removed from the grass area prior to cutting. Cutting can start as soon as the newly installed grassland area exceeds 50mm.
- 6.2 Particular care should be taken near tree planting to ensure no damage occurs. Nylon filament rotary cutters or other mechanical tools and not allowed within 100mm from the stem of any tree. If operation is required closer than 100mm from the stem this should be carried out using hand tools.
- 6.3 Cutting shall be carried out as required to achieve a neat and usable space, with grass not allowed to grow above a height of 75mm, generally every 10-14 days. After cutting the grassland should be left neat and even and without surface rutting, compaction or damage.
- 6.4 Any damaged areas or bare patches should be repaired in line with the approved landscape specification, to ensure a closely knit and even grassed area.
- 6.5 Fallen leaves should be removed to avoid damage to the grass. Any arising should be taken offsite for recycling.
- 6.6 Any slight hollows shall be rectified using the top dressing method after the last cut in autumn. The topdressing shall consist of a suitable sandy loam material which will be raked or brushed into the grass. Prior to raking in the topdressing, ensure thatch and moss has been removed from the grass. The application rate is generally 2kg/m², but can be adjusted to ensure a level surface is achieved. The topdressing should be lightly rolled after raking or brushing in to ensure good contact is made with the existing soil.
- 6.7 Deeper hollows shall be rectified by neatly cutting a square of turf and building up the levels underneath using a suitable sandy loam soil until the correct level is achieved. Once the turf is replaced lightly roll it to ensure good contact between the new and existing soil. The turf shall be kept watered well until it has fully married in.
- 6.8 The grassland area should be spiked annually in October to prevent compaction and waterlogging. If there is compaction or waterlogging, this should be resolved using a suitable de-compaction method to ensure the health of the grassland and all year round usability of the landscape.
- 6.9 Grass edges to planted areas are to be trimmed annually to maintain a neat edge.

7. Wildflower/long grassland areas

Maintenance objectives

- Create and maintain a structural and botanical diversity species-rich wildflower meadow
- Create a biodiverse habitat to wildlife as well as foraging and breeding opportunities
- Create a rural character to the development, whilst creating a transition to the surrounding landscape

Maintenance operations

Establishment of wildflower/grassland areas

- 7.1 During the first growing season wildflower/grassland areas, as shown on the landscape proposals, shall be cut regularly (every 10-14 days) to a height of 40-60mm with arising removed from site, to create a healthy and strong wildflower/grassland area and suppress the flush of annual weeds likely to be present in the soil. Cutting should start as soon as seeds reach a height above 60mm, if bulbs are included within wildflower or grassland areas care should be taken to not cut flowering bulbs.
- 7.2 Particular care should be taken near tree planting to ensure no damage occurs. Nylon filament rotary cutters or other mechanical tools and not allowed within 100mm from the stem of any tree. If operation is required closer than 100mm from the stem this should be carried out using hand tools.

Long term maintenance

- 7.3 Once established cuttings should be reduced to the following:
- A spring cut to a height of 40-75mm around April, with arisings removed from site
 - A main summer hay cut in early to mid-august to a height of 40-75mm, arising should be left to dry for approx. 7 days before removing from site. The summer hay cut should be carried out when the weather is dry.
 - One to two autumn cuts before November to a height of 40-75mm, with arisings removed from site.
- 7.4 Cutting should be carried out by cutting from one side to the other or from the centre outwards to ensure any late remaining ground nesting birds and chicks have an opportunity to escape.
- 7.5 Where bulbs are included in the wildflower/grassland areas, cutting should be postponed until bulbs have stopped flowering and leaves start dying back.
- 7.6 Any damaged areas or bare patches should be repaired in line with the approved landscape specification.
- 7.7 Particular care should be taken near tree planting to ensure no damage occurs. Nylon filament rotary cutters or other mechanical tools and not allowed within 100mm from the stem of any tree. If operation is required closer than 100mm from the stem this should be carried out using hand tools.

- 7.8 If there is compaction or waterlogging, this should be resolved using a suitable de-compaction method to ensure the health of the wildflower/grassland area.
- 7.9 Noxious weeds, such as docks, thistles, nettles, ragwort and willowherb should be removed by hand pulling or spot treatment with glyphosate. It is intended to minimise the long term input of chemicals, however, the use of this treatment might be required in the first few growing seasons to suppress initial re-growth following ground disturbance.

8. Tussocky grassland areas

Maintenance objectives

- Create and maintain structurally and botanically diverse species-rich areas of tussocky grassland
- Create a biodiverse habitat to wildlife as well as foraging and breeding opportunities
- Create a rural character to the development, whilst creating a transition to the surrounding landscape

Maintenance operations

Establishment of tussocky grassland areas

- 8.1 During the first growing season, tussocky grassland areas, as shown on the landscape proposals, shall be cut regularly (every 10-14 days) to a height of 40-60mm with arising removed from site, to create a healthy and strong grassland area and suppress the flush of annual weeds likely to be present in the soil. Cutting should start as soon as seeds reach a height above 60mm.
- 8.2 Particular care should be taken near tree planting to ensure no damage occurs. Nylon filament rotary cutters or other mechanical tools and not allowed within 100mm from the stem of any tree. If operation is required closer than 100mm from the stem this should be carried out using hand tools.

Long term maintenance

- 8.3 Once established cuttings should be reduced to the following:
- Areas should be cut on rotation on a 2-3 year cycle between October and February.
 - No more than half of each area should be cut in any one year, leaving the remaining half undisturbed for wildlife.
- 8.4 Cutting should be carried out by cutting from one side to the other or from the centre outwards to ensure any late remaining ground nesting birds and chicks have an opportunity to escape.
- 8.5 Any damaged areas or bare patches should be repaired in line with the approved landscape specification.
- 8.6 Particular care should be taken near tree planting to ensure no damage occurs. Nylon filament rotary cutters or other mechanical tools and not allowed within 100mm from the stem of any tree. If operation is required closer than 100mm from the stem this should be carried out using hand tools.
- 8.7 If there is compaction or waterlogging, this should be resolved using a suitable de-compaction method to ensure the health of the grassland area.
- 8.8 Noxious weeds, such as docks, thistles, nettles, ragwort and willowherb should be removed by hand pulling or spot treatment with glyphosate. It is intended to minimise the long term input of chemicals, however, the use of this treatment might be required in the first few growing seasons to suppress initial re-growth following ground disturbance.

9. Wetland areas and ponds

Maintenance objectives

- Create and maintain a structural and botanical diversity species-rich wetland area
- Retention and management of open water areas where permanent water is present
- Waterbodies will be managed to minimise health and safety issues due to proximity of residential properties

Maintenance operations

- 9.1 Areas of wet grassland which only occasionally or seasonally flood can be managed in line with the wildflower area maintenance regime in the previous chapter.

Establishment of wetland areas

- 9.2 During the first growing season wetland areas should be cut back regularly (every 2-3 months during the growing season) to encourage the development of a good perennial ground cover and suppress weed growth.

Long term maintenance

- 9.3 Once established cutting should be reduced to every 2-3 years. Cutting should take place between September and November and should be done on a rotational basis. In ditches, cut section and/or work from one bank each year. Within the pond vegetation can be removed as a wedge each year ensuring the whole area is fully cut once every 2-3 years.
- 9.4 Dense areas of a single species (e.g. yellow iris or common reed) will require selective thinning to increase biodiversity.
- 9.5 Any arisings will be temporarily placed adjacent to the pond or ditch on a protective membrane around the pond edge and removed after 48hrs.
- 9.6 Noxious weeds should be removed by hand, no chemicals should be used.
- 9.7 No fertilisers shall be used in proximity to the pond or ditch – refer to landscape specification for further detail.
- 9.8 Areas of permanent water should be maintained to ensure at least 35-60% of the water surface is open at any time.
- 9.9 Where desilting is required as part of the drainage strategy maintenance plan, this should be carried between November and January to minimise disturbance to wildlife. Care should be taken to minimise disturbance to the vegetation surrounding the pond or ditch. The silt removed will temporarily be placed adjacent to the pond or ditch on a protective membrane to allow the invertebrate assemblage to repopulate the pond. It should be removed after 48hrs.
- 9.10 The ponds and wetland areas will be visually inspected on a monthly basis and any debris or rubbish will be removed. The water quality will be visually monitored during these inspections for any signs of pollutants (e.g. scum, excessive growth or algae and discolouration) and invasive species. Remedial

action will be taken accordingly. Advice from a qualified ecologist will be sought, where remedial actions will affect the ecology of the pond.

10. Tree planting

Maintenance objectives

- Creation and establishment of tree lines streets
- Supplementing existing tree groups to create age diversification
- Provide connectivity to the surrounding environment
- Establishment of boundary tree planting and tree planting within the development to help buffer views from the surrounding environment and soften the development

Maintenance operations

- I0.1 Where trees are staked, the stakes and ties will be checked monthly and it should be anticipated that they will need adjusting at least twice annually. Any broken or damaged stakes will be replaced and ties re-fixed at a slightly lower position, allowing for growth since planting.
- I0.2 Where trees are supported using underground guying, the stability of the trees should be checked monthly to ensure underground guying hasn't been damaged. If instability is detected this should be discussed with a qualified landscape architect or Arboricultural consultant and rectified.
- I0.3 Once established staking should be removed, generally after 5 years. Underground guying can stay in place.
- I0.4 Trees should be watered regularly during dry periods until established to full depth of the topsoil or to field capacity. Watering operations should be carried out as often as required to ensure the continued establishment and thriving of the trees.
- I0.5 To reduce excessive competition, a weed free area will be retained around any trees to a diameter of 1m with mulch topped up annually until the tree has established.
- I0.6 Newly planted trees will required re-firming as required during the first three years. If the soil around newly planted trees is heavily compacted or soil capping has occurred remedial action should be taken.
- I0.7 Young trees should be pruned formatively to maintain a desired shape as well as to maintain health and vigour, until a permanent structurally sound scaffold system of branches typical of the species and appropriate to the site is established.
- I0.8 Once matured tree planting shall be maintained in line with the 'Existing tree planting' chapter in this management plan.

11. Hedgerow

Maintenance objectives

- Create and maintain a well-balanced hedge structure
- Establishment of native hedgerows to the site boundaries to help buffer views from the surrounding environment and soften the development edge
- For mixed native hedgerow create and maintain a biodiverse habitat for wildlife
- For ornamental hedgerow create and maintain a natural boundary to demarcate individual plot boundaries and soften built form

Maintenance operations

Establishment of hedgerows

- 11.1 Hedgerow planting should be watered regularly during dry periods until established. Watering should be carried out to full depth of the topsoil or to field capacity. Watering operations should be carried out as required to ensure the continued establishment and thriving of the hedgerow planting.
- 11.2 In addition, managements operation during the establishment phases will comprise of weed control (if required) and formative pruning of the hedgerow to establish dense branch growth.
- 11.3 For mixed native hedgerows pruning will be carried out in the first 2 to 3 years after installation and will consist of 'facing up either side of the hedge. All hedge cuts must be undertaken using appropriate hand or power tools.
- 11.4 Ornamental hedgerows should be pruned to the desired height and shaped as shown on the landscape proposals as soon as sufficient growth is present, with formative pruning carried out in early spring.
- 11.5 New planting will need to be re-firmed, as required, to ensure good root establishment.

Long term maintenance

- 11.6 Once established mixed native hedgerows should be pruned every 2-3 years, on a rotational basis leaving one side uncut each year. The hedge will be cut in an 'A' shape' to maintain a wide base for bird nesting to a height of approx. 2.5m.
- 11.7 Additional hedgerow cutting might be required from a health and safety perspective (although this is unlikely in the first few years). This should be monitored along with the monthly site inspections and rectified where required. This is most likely to be required where a native hedgerow aligns a footpath, in which case the hedge should be cut on an annual basis to ensure use of the footpath is not compromised.
- 11.8 Cutting of the mixed native hedgerow should take place outside the bird nesting season, ideally during the winter (From November until early February) to allow for foraging for wildlife during late summer and autumn.

- 11.9 Ornamental hedges should be cut bi-annually to the correct height and shape as shown on the landscape proposals, leaving a neat and tidy appearance. Cutting generally takes place between spring and summer and again in the autumn, if there are any signs of bird nesting, cutting should be delayed until after the birds have fled the nest. Bird nesting season is generally considered to run from March to August.
- 11.10 Once established cutting of ornamental hedges should be limited to current growth, rather than old wood.

12. Native scrub planting

Maintenance objectives

- Create and maintain a biodiverse habitat for wildlife
- Establishment of planting to help buffer views from the surrounding environment and soften the development edge

Maintenance operations

Establishment of scrub planting

- 12.1 Scrub planting should be watered regularly during dry periods until established. Watering should be carried out to full depth of the topsoil or to field capacity. Watering operations should be carried out as required to ensure the continued establishment and thriving of the hedgerow planting.
- 12.2 Weeding should be carried out regularly to ensure minimal competition with new scrub planting. The density of planting will require that all weeding is carried out by hand, using the appropriate tools. All resultant material should be removed from site. Weeding should be carried out until planting has established and will no longer compete with weed growth.
- 12.3 During the establishment the scrub planting will require thinning to minimise competition between plants and ensure a healthy scrub area. Thinning should take place when branches of plants start overlapping, in which case the strongest plant should be retained and weaker plants should be removed.
- 12.4 Where appropriate, mulch areas should be topped up annually to minimise weed growth.

Long term maintenance

- 12.5 Once established areas of scrub planting will require limited maintenance.
- 12.6 Pruning should be carried out as required to ensure scrub planting retains a balanced shape and does not pose a risk to health and safety, ensuring any pruning is carried out outside the bird nesting season (generally from March to August).

13. Ornamental planting

Maintenance objectives

- Create high quality, well-maintain landscaped front gardens
- Establishment of shrub planting to front gardens
- Create and maintain a well-balance shrub structure

Maintenance operations

Establishment of ornamental planting

- 13.1 Shrub planting should be watered regularly during dry periods until established. Watering should be carried out to full depth of the topsoil or to field capacity. Watering operations should be carried out as required to ensure the continued establishment and thriving of the hedgerow planting.
- 13.2 Weeding should be carried out regularly to ensure minimal competition with new scrub planting. The density of planting will require that all weeding is carried out by hand, using the appropriate tools. All resultant material should be removed from site.
- 13.3 During the establishment the shrub and perennial planting will require thinning to minimise competition between plants and ensure a healthy shrub structure. Thinning should take place when branches of plants start overlapping, in which case the strongest plant should be retained and weaker plants should be removed.
- 13.4 Mulch areas should be topped up annually to minimise weed growth until proposed planting fully covers the bare soil.
- 13.5 A fertiliser, as specified in the landscape specification, should be applied annually to ensure plants continue to thrive.

Long term maintenance

- 13.6 Once established areas of shrub planting will require annual pruning to maintain a balanced shape.
- 13.7 Pruning should be carried out as required to ensure shrub planting retains a balanced shape and does not obscure doors, windows, access paths or sightlines or pose a risk to health and safety. Pruning of deciduous species is generally carried out in late autumn or early spring with evergreen species best pruned in mid to late spring.
- 13.8 Where shrub planting is located within sight lines it has been specified to not exceed 600mm in height, where this is exceeded pruning will need to be carried out below carefully cut shrubs back to below 600mm out to ensure it does not interfere with visibility.
- 13.9 Once climbers reach the top of the supporting frame/wire they should be pruned as required to maintain a neat and tidy appearance. Shoots can be cut back to approx. 300mm of the top of the adjacent wall and thinned to avoid overcrowding. Pruning is generally carried out in late autumn after flowering.

- I3.10 Herbaceous perennial planting will die back fully during the winter and should be cut back to ground level in late autumn to create a neat and tidy appearance and aid with new shoot coming up in spring.
- I3.11 A slow-release fertiliser, as specified in the landscape specification, should be applied annually to ensure plants continue to thrive. Fertiliser should be lightly worked into the soil, without disturbing the roots. During the establishment period fertiliser should be applied before the mulch is topped up.

14. Hard surfacing

Maintenance objectives

- Create a safe, clean and tidy environment

Maintenance operations

- 14.1 All surfacing shall be inspected on a monthly basis and will be kept safe and usable. Ensuring and overhanging vegetation or broken branches are pruned/removed as required. Any items considered unsafe must be removed or made safe and replaced as soon as possible.
- 14.2 Repairs will be carried out as required. With surfacing replaced when necessary to retain safe use.
- 14.3 An annual herbicide spray will be undertaken to both sides of tarmac paths and the full surface of bound gravel paths to prevent encroachment of vegetation.

15. Fencing and railing

Maintenance objectives

- Create a safe and aesthetically pleasing environment

Maintenance operations

- 15.1 All fencing and railings will be inspected during the monthly site inspection and repairs will be carried out as required.

16. Site furniture

Maintenance objectives

- Create a safe, clean and tidy environment

Maintenance operations

- 16.1 Bins should be emptied as set out at the start of this document and cleaned bi-monthly.
- 16.2 All pieces of site furniture shall be inspected during the monthly site inspections.
- 16.3 Any bins or benches considered unsafe will be removed, or made safe and replaced as soon as possible. The use of materials for repairs and replacements will confirm to the original design specification.
- 16.4 Graffiti removal will be carried out as required.

17. Play Areas

Maintenance objectives

- Create a safe environment to be enjoyed
- All surfacing and play equipment should be checked to conform to EN 1176, BS 7188 and EN 1177

Maintenance operations

- 17.1 The play area shall be inspected weekly by a competent person, preferably with some basic training.
- 17.2 All litter is to be removed from play area.
- 17.3 Appropriate maintenance and repairs shall be carried out and records kept.
- 17.4 In addition to the weekly visual checks, the following should also be undertaken at a monthly frequency:
- All wooden components in an acceptable condition i.e. fastenings, splinters, ladder rungs
 - All metal parts are well connected and not worn down or loose. Particular attention should be paid to any swing joints and chain connections.
 - All screwed connections and bolted joints are tight. If not, then these should be tightened. Some moving parts may require greasing and oiling.
 - All surfaces satisfactory and have no sharp edges.
 - All plastic and rubber components in a satisfactory condition.
- 17.5 Any vandalism that is found during the inspections is to be reported immediately to the LPA or Management Company and if any equipment is deemed unsafe the play area is to be closed immediately until the equipment can be made good. Any repair works to be undertaken as a matter of urgency to keep the play area open and maintain a safe environment.
- 17.6 Annual inspection by an independent specialist (such as RoSPA) shall be undertaken.
- 17.7 The Annual Inspection should be completed after winter months to ensure that all aspects of the play area and its surrounds are safe and to determine if any equipment or surfacing requires to be replaced in the following year. In addition to the previously identified checks above, the following must be completed:
- All foundations stable and the equipment securely anchored.
 - Replace joints that show severe corrosion or heavy wear and tear
 - All wooden components that have been exposed to the weather conditions are to be checked with particular attention to the parts installed within the ground along with connection joints to other components which are required for equipment stability.