

## Foul and Surface Water Drainage Report

**The Grange, Westergate**

**For**

**Deborah and Christopher Blows**

Rev – P1

Reference C3388

Date 10<sup>th</sup> June 2025

Revision	Date of Issue	Comments	Prepared By	Checked By
PL-	10/06/2025	Initial Issue	MR	CS
P1	06/11/2025	Updated ADC requirements	MR	CS

## Contents

<b>1</b>	<b>INTRODUCTION .....</b>	<b>3</b>
<b>2</b>	<b>EXECUTIVE SUMMARY:.....</b>	<b>4</b>
<b>3</b>	<b>SITE GEOLOGY .....</b>	<b>4</b>
<b>4</b>	<b>EXISTING DRAINAGE.....</b>	<b>6</b>
<b>5</b>	<b>PROPOSED DRAINAGE STRATEGY .....</b>	<b>8</b>
<b>6</b>	<b>SUMMARY AND CONCLUSIONS .....</b>	<b>14</b>
<b>7</b>	<b>APPENDICES .....</b>	<b>15</b>

## 1 Introduction

- 1.1.1 CGS Civils Ltd has been appointed to undertake a drainage strategy report for a proposed development at Land north of the Grange, Westergate.
- 1.1.2 The purpose of this drainage strategy is to demonstrate how the development area can be satisfactorily drained without increasing flood risk onsite and elsewhere.
- 1.1.3 The site currently contains a mobile home. The proposed development will compromise a new residential dwelling with a garage and, driveway and associated parking space. The proposed development is located as OS Grid Reference **SU 93979 04401** and has the post code **PO20 3SQ**.
- 1.1.4 The proposed site layout can be found in **Appendix A**.

**Fig 1. Site Location**



## 2 Executive Summary:


- 2.1.1 Surface water runoff is to be discharged into the existing ditch located to the north of the site. All roof and hard paved areas are to be collected into a positive drainage network before discharging into the ditch at restricted flow rate of 1.0 l/s. The proposed drainage network has been designed to cater for the 1 in 100-year +45% storm + 10% urban creep allowance.
- 2.1.2 The foul water will discharge to an existing foul water manhole located onsite. This connection is subject to Southern Water approval under a Section 106 agreement.


## 3 Site Geology

### 3.1 British Geological Survey information

- 3.1.1 The British Geological Survey confirms the bedrock geology to be made up London Clay Formation- Clay, Silt and Sand. The BGS website confirms the superficial deposits on site to be made up of River Terrace Deposits- Sand, Silt and Clay.
- 3.1.2 The British Geological survey also holds records of historical boreholes near the site which give some insight into the ground geology.
  - Borehole **SU90SW51** (Located approx. 600m North-East of the site) – Ground geology (Clay, clayey sand)
  - Borehole **SU90NW72** (Located approx. 750m North of the site) – Ground geology (Silt, clayey gravel, pebbly sand)
  - Borehole **SU90SW56** (Located approx. 400m South of the site) – Ground geology (sandy brown clay, clay with stones)

**Fig 2. British Geological Survey**





**Snippet from BGS Website showing Bedrock geology and superficial deposits**  
<http://mapapps.bgs.ac.uk/geologyofbritain/home.html?>



**Snippet from BGS Website showing Historical Borehole Logs location**

3.1.3 The Historical Borehole Logs can be found in **Appendix B**.

### 3.2 Geological Assessment

3.2.1 Groundwater monitoring and soakage testing was carried out by Ground Management Ltd on 2nd May 2025. The investigation included the excavation of 2 No. boreholes, each to a depth of 3 metres below ground level (mbgl). A standpipe was installed in each borehole to facilitate ongoing groundwater level monitoring. Groundwater levels were recorded regularly between 3rd December 2024 and 30th March 2025. The highest groundwater levels observed were 0.780 mbgl in BH1 and 0.830 mbgl in BH2.

3.2.2 An infiltration test to BRE365 was conducted within a trial pit on site. As per BRE365, 3 No. tests were performed within a trial pit measuring 0.3 x 0.5 x 0.6m deep. The worst-case recorded infiltration rate is  $3.04 \times 10^{-6}$  m/s. No groundwater was encountered within the trial pit during testing


3.2.3 The groundwater monitoring and soakage testing report can be found in **Appendix C**.

## 4 Existing Drainage

4.1.1 It is not currently known how existing site discharges surface water runoff, however it is presumed that all surface water runoff is discharged into ground via infiltration.

4.1.2 A ditch has been identified along the northern site boundary within the tree area, and it is assumed that this ditch connects to the existing watercourse located approximately 290 m to the east.

**Fig 4. Existing ditch draft on Statutory Main River Map**



**Fig 4. Existing ditch photos**



## 5 Proposed Drainage Strategy

### 5.1 SuDS Hierarchy

5.1.1 All options for the destination of run-off generated on site have been assessed in line with the SuDS hierarchy as set out in Building Regulations Part H document and DEFRA's Draft National Standards for SuDS.

**Table 1. SuDS Hierarchy**

Discharge Destination	
Rainwater Harvesting	<b>YES</b> - Rainwater harvesting tank has been proposed
Discharge to Ground	<b>NO</b> - Due to high groundwater levels onsite infiltration method for surface water discharge has been ruled out
Discharge to Watercourse	<b>YES</b> - All surface water runoff from roofs and hard paved area is to be discharged into the existing ditch located to the north of the site at restricted flow rate of 1.0 l/s
Discharge to Surface Water Sewer	N/A
Discharge to Other Sewer	No surface water discharge permitted to existing foul sewer owned by Southern Water.

### 5.2 Proposed Hydraulic Calculation Specifications:

**Table 2. SuDS Hierarchy**

Hydraulic Calculations Settings:	
Rainfall Methodology	<b>FEH-22</b>
Volumetric Run-off Coefficient Cv	<b>1.00</b>
CV Winter and Summer	<b>1.00 / 1.00</b>
Additional Storage (m <sup>3</sup> / ha)	<b>0.0</b>
Flow Control	0.458 Head 1.0 l/s
Permeable Paving Design	Base Coefficient (m/hr): <b>0.0000</b> Side Coefficient (m/hr): <b>0.00000</b> Factor of Safety: <b>2</b> Porosity: <b>30%</b>

### 5.3 Surface Water Drainage

5.3.1 Based upon the groundwater monitoring report, it is proposed that the site will discharge all surface water into the existing ditch located to the north of the site. All roof and hard paved areas are to be collected into a positive drainage network before being discharged into ditch at restricted flow discharge rate of 1.0 l/s.

5.3.2 Groundwater monitoring and soakage testing confirmed that the site is underlain by a relatively high groundwater table. The highest recorded groundwater level was 0.830 m below ground level (mbgl) within borehole BH2, located in the area of the proposed driveway. As a result, the use of infiltration methods for surface water disposal has been ruled out, as the site conditions do not meet the required 1m clearance (freeboard) between the base of any infiltration device and the maximum groundwater level.

5.3.3 All surface water runoff will be discharged into the permeable paving system, which incorporates a 470 mm thick voided sub-base providing the required surface water storage volume of 29.61 m<sup>3</sup>. Surface water runoff from roof areas will be conveyed to the voided sub-base via distribution tanks. The permeable paving system is protected against groundwater ingress through the use of an impermeable geomembrane liner with protection fleece.

5.3.4 A discharge rate of 1.0 l/s has been adopted to minimise the risk of potential blockages within the flow control orifice chamber and the proposed drainage network, thereby reducing the likelihood of flooding on-site and to neighbouring property.

5.3.5 The proposed bioretention planter is designed to reduce the required storage volume within the permeable paving voided subbase by providing additional storage. Surface water runoff will be temporarily held with the planter before discharging into the voided subbase. To comply with *Standard 2 of National standards for SuDS*, a lined bioretention planter unit is proposed and designed to capture, convey, and store the first 5 mm of rainfall.

5.3.6 To ensure that the drainage system remains free from obstruction by leaves, debris, and sediment, it is proposed to install a RainTaina filter chamber at locations where rainwater downpipes are not connected directly to a catchpit chamber.

5.3.7 The drainage network has been designed to accommodate a critical 1 in 100-year storm event with an additional 45% allowance for climate change + 10% urban creep.

5.3.8 The proposed rainwater harvesting tank is proposed to enable water reuse and to provide additional surface water storage within the drainage system.

5.3.9 The only alternative surface water discharge point identified is an existing foul water sewer owned by Southern Water. However, Southern Water does not permit the discharge of surface water into the foul sewer network.

5.3.10 Proposed Drainage Strategy, Contributing Area Plan & Exceedance Flow Routes, Proposed Typical Construction Details and Hydraulic calculations have been carried out which can be found at **Appendix D**.

## 5.4 Water Quality

5.4.1 A key requirement of any SuDS system is that it protects the receiving water body from the risk of pollution.

5.4.2 Frequent and short duration rainfall events are those that are most loaded with potential contaminants (silts, fines, heavy metals, and various organic and inorganic contaminants) Therefore the first 5-10mm of rainfall should be adequately treated with SuDS.

5.4.3 The new SuDS Manual (Ciria C753, November 2015) introduces slightly different approach compared to the previous version for the water quality management of surface water. The Manual describes risks posed by the surface water runoff to the receiving environment as a function of:

- The pollution hazard at a particular site (i.e., the pollution source)
- The effectiveness of SuDS treatment components in reducing levels of pollutants to environmentally acceptable levels
- The sensitivity of the receiving environment

5.4.4 The recommended approaches for water quality risk management are given in the SuDS Manual Table 26.1.

**Table 26.1 from SuDS manual. Approaches to Water Quality Risk Management**

<b>Table 26.1 Approaches to Water Quality Risk Management</b>			
<b>Design method</b>	<b>Hazard Characterisation</b>	<b>Risk Reduction</b>	
		<b>For Surface Water</b>	<b>For Groundwater</b>
Simple Index Approach	Simple pollution hazard indices based on land use (Table 26.2)	Simple SuDS hazard mitigation indices (Table 26.3)	Simple SuDS hazard mitigation indices (Table 26.4)
Risk Screening	Factors characterising traffic density and extent of infiltration likely to occur (Table 26.5)	N/A	Factors characterising unsaturated soil depth and type, and predominant flow type through the soils (Table 26.5)
Detailed Risk Assessment	Site specific information used to define likely pollutants and their significance	More detailed, component specific performance information used to demonstrate that the proposed SuDS components reduce the hazard to acceptable levels	
Process-based treatment modelling	Time series rainfall used with generic pollution characteristics to determine statistical distributions of likely concentrations and loadings in the runoff	Models that represent the treatment processes in the proposed SuDS components give estimates of reductions in even mean discharge concentrations and total annual load reductions delivered by the system	

5.4.5 As per Table 26.1 Simple Index approach will be used as a design method for this site.

5.4.6 Table 26.2 will provide hazard classification of different land uses. The land uses for the surface water drainage for this site are.

- Residential Roofs
- Individual Property driveways and residential car parks
- Low traffic roads

5.4.7 To deliver adequate treatment, the selected SuDS components should have a total pollution mitigation index for each contaminant type that equals or exceeds the pollution hazard index for each contaminant type. Therefore, the following must be achieved for the surface running off the site.

**Total SuDS mitigation index >=pollution hazard index**

5.4.8 Pollution Hazard Indices are given for different land uses in Table 26.2 of the SuDS manual;

**Table 26.2 from SuDS manual. Pollution Hazard Indices for Different Land Use Classifications**

<b>Table 26.2 Pollution hazard indices for different land use classifications</b>					
<b>Land Use</b>	<b>Pollution Hazard Level</b>	<b>Total Suspended solids (TSS)</b>	<b>Metals</b>	<b>Hydro-Carbons</b>	
Residential roofs	Very Low	0.2	0.2	0.05	
Other roofs (Typically commercial/industrial roofs)	Low	0.3	0.2 (up to 0.8 where there is potential for metals to leach from the roof)	0.05	
Individual property driveways, residential car parks, low traffic roads (e.g., cul-de-sacs, homezones and general access roads) and non-residential car parking with infrequent change (e.g., schools, offices) i.e., < 300 traffic movements/day	Low	0.5	0.4	0.4	
Commercial yard and delivery areas, non-residential car parking with frequent change (e.g., hospitals, retail), all roads except low traffic roads and trunk roads/motorways	Medium	0.7	0.6	0.7	
Sites with heavy pollution (e.g., haulage yards, lorry parks, highly frequented lorry approaches to industrial estates, waste sites), sites where chemicals and fuels (other than domestic fuel oil) are to be delivered, handled, stored, used or manufactured; industrial sites; trunk roads and motorways	High	0.8	0.8	0.9	

5.4.9 From Table 26.2 the following information is tabulated in Table 1

**Table 3: Pollution hazard index and destination of runoff for the proposed site**

<b>Table 3: Pollution Hazard Index and Destination of runoff for the proposed Site</b>					
<b>Land Use</b>	<b>Destination of Runoff</b>	<b>Pollution Hazard Level</b>	<b>Total Suspended Solids</b>	<b>Metals</b>	<b>Hydrocarbons</b>
Residential Roof	Surface Water	Very Low	0.2	0.2	0.05
Individual driveways, residential car parks and low traffic roads	Surface water	Low	0.5	0.4	0.4

5.4.10 The SuDS mitigation index will be obtained from Table 26.4 (for groundwater) of the SuDS manual.

**Table 26.3 from SuDS manual. Indicative SuDS Mitigation Indices for discharges to surface waters.**

<b>Table 26.3 Indicative SuDS mitigation indices for discharges to surface waters</b>				
<b>Type of SuDS Components</b>		<b>Mitigation Indices</b>		
		<b>TSS</b>	<b>Metals</b>	<b>Hydrocarbons</b>
Filter Strip		0.4	0.4	0.5
Filter Drain		0.4	0.4	0.4
Swale		0.5	0.6	0.6
Bioretention System		0.8	0.8	0.8
Permeable Pavement		0.7	0.6	0.7
Detention Basin		0.5	0.5	0.6
Pond		0.7	0.7	0.5
Wetland		0.8	0.8	0.8
Proprietary treatment systems		These must demonstrate that they can address each of the contaminant types to acceptable levels for inflow concentrations relevant to the contributing drainage area		

**Table 4: SuDS mitigation index**

<b>Table 4 Mitigation Indices</b>						
<b>Runoff Source</b>	<b>Destination of Runoff</b>	<b>Mitigation Index Source</b>	<b>Type of SuDS Component</b>	<b>Total Suspended Solids (TSS)</b>	<b>Metals</b>	<b>Hydrocarbons</b>
Residential Roof	Ground water	Table 26.3 (for surface waters)	Bioretention Planter	0.8	0.8	0.8
Individual driveways, residential car parks and low traffic roads	Ground water	Table 26.3 (for surface waters)	Permeable Pavement	0.7	0.6	0.7

5.4.11 The above analysis demonstrates that the SuDS devices within the design will mitigate any pollution present within the surface water system.

## 5.5 Foul water drainage

5.5.1 The foul water will discharge into the existing foul water manhole located onsite. This connection subject to approval of a S106 application by Southern Water.

5.5.2 A CCTV survey should be undertaken to confirm if a connection onsite is possible and if remedial works are required.

## 5.6 Construction Phase Drainage

5.6.1 It is an offence to cause or knowingly permit the entry of any polluting, poisonous or noxious material in the water environment. If the pollution is serious enough to lower the ecological status of the water body as set out in terms by the Water Framework Directive (2000/60/EC) than prosecution may occur.

5.6.2 Remediation of any damage caused will not require the polluter to be prosecuted first. If the water pollution is serious enough to be classed an environmental damage, the damage will require to be remediated such that the area is returned to the condition it would have been in if the damage had not occurred.

5.6.3 If any pollution has not been reported or the polluter has not taken actions to prevent any further damage; they would then be causing an offence. Third parties (e.g., Private water supply users, landowners, recreation users and the public) who may be affected by possible damage may also report the risk of any environmental damage to the enforcing authority.

5.6.4 The principles of SuDS (Sustainable Drainage Systems) shall be applied to all components of design and construction regarding surface water management. Any design or site works that may impact on the site drainage or the water quality shall:

- Soakaway where soils allow
- Consider and manage erosion
- Remove pollutants in surface water
- Retain any silts on site and prevent silts from discharging to watercourses or drains
- Keep runoff rates at existing greenfield runoff
- Prevent accidental spillages reaching watercourse

5.6.5 As infiltration on site is viable, the temporary drainage for the development will be in the form of land drains which will discharge into the ground.

5.6.6 Pollution will be controlled via the use of catchpit manholes and geotextiles.


5.6.7 Any potential hazardous substances will be within a controlled compound with a separate drainage system that will contain a penstock valve / containment kit in the event of a spillage.

## 6 Summary and Conclusions

- 6.1.1 CGS Civils has been instructed by to produce a Drainage statement under National Planning Policy Framework (NPPF) to support the Planning Application for the construction of a new residential dwelling with garage and associated driveway.
- 6.1.2 The Surface Water will discharge into the existing ditch at restricted flow discharge rate of 1.0 l/s. The drainage network has been designed for a critical 1 in 100 year + 45% storm event + 10% for urban creep allowance.
- 6.1.3 The Foul water will discharge into the existing foul water manhole located within the site boundary. The proposed connection is to be agreed under Southern Water S106 application.
- 6.1.4 The report has demonstrated that the proposed drainage measures ensure that suitable means of surface water and foul drainage can be achieved for the proposed development.

## 7 Appendices

### 7.1 Appendix A – Site Plan



PROPOSED SITE PLAN

0 10 25m

Scale 1:500 @ A3



- DRAFT -

## 7.2 Appendix B – Borehole Logs

SU 90 NW 72 9359 0501

Westergate

Surface level +10.8 m  
Water struck at +7.8 m  
September 1981

Block G

Overburden 2.2 m  
Mineral 3.8 m  
Bedrock 0.8 m+

LOG

Geological classification

Lithology

Thickness Depth  
m m

	Soil	0.3	0.3
Brickearth	Silt, brown	0.4	0.7
	Clay, silty, brown, with a few pebbles near base	1.5	2.2
Head Gravel	<p>a 'Very clayey' gravel Gravel: fine with coarse, angular to subrounded; flint, some white and porous Sand: coarse with fine and medium Fines: clay</p> <p>b 'Clayey' pebbly sand Gravel: coarse and fine, angular to subrounded; flint, some white and porous Sand: fine with traces of medium and coarse; quartz Fines: silt, brown</p> <p>c Sandy gravel Gravel: fine and coarse, angular to well rounded; flint (some white and porous), chalk and other rock fragments Sand: fine with coarse and medium; quartz</p>	0.8	3.0
Raised Beach Deposits (younger)		2.0	5.0
London Clay	Clay, stiff, dark olive grey with a few rounded flint pebbles	0.8+	6.8

GRADING

	Mean for deposit percentages			Depth below surface (m)	Percentages							
	Fines	Sand	Gravel		Fines				Sand			
					-½	½-1	1-2	+1-4	+4-16	+16-64	+64 mm	
a	37	17	46	2.2-3.0	37	5	4	8	29	17	0	
b	15	79	6	3.0-4.0	15	70	1	1	6	7	0	
				4.0-5.0	15	84	1	0	0	0	0	
				Mean	15	77	1	1	3	3	0	
c	3	56	41	5.0-6.0	3	41	7	8	19	22	0	
b+c	11	72	17	3.0-6.0	11	66	3	3	8	9	0	
a+b+c	16	60	24	2.2-6.0	16	53	3	4	13	11	0	

7.3 **Appendix C – Groundwater Monitoring and Soakage Testing Report**

GROUNDWATER MONITORING  
AT  
SITE ADJACENT TO THE GRANGE, WESTERGATE  
FOR  
DEBORAH AND CHRISTOPHER BLOWS

SITE RECORDS

G6625

20 February 2025



**Ground Management Ltd**  
Civil and Geotechnical Engineering Services

**DOCUMENT CONTROL**

Report Title: G6625 Site Adjacent to The Grange, Westergate  
Groundwater Monitoring

Report No./ Issue: G6625-01/1

Report Status: Issued for Client Comment

Distribution: Deborah & Christopher Blows PDF copy 20 February 2025

Prepared by: Alistair Tyler BSc MSc DIC CEng MICE

Signed:

Ground Management Ltd Robin Hill Farm Clay Lane Fishbourne Chichester West Sussex PO18 8AB

Phone/Fax [REDACTED]

## CONTENTS

### 1.0 Introduction

Figure 1: Site Location Plan

Figure 2: Exploratory Hole Location Plan

Exploratory Hole Logs: Boreholes BH1 & BH2

Dynamic Probe (DPSH) DP2

Ground Water Monitoring Observations

## 1.0 INTRODUCTION

- 1.1 Ground Management Ltd have carried out standpipe installation and provided support with groundwater monitoring on the site adjacent to The Grange, Westergate, located as indicated on Figure 1.
- 1.2 The work included excavation of two boreholes referenced as BH1 and BH2 each to a depth of 3m at the locations indicated on Figure 2. Copies of the typed exploratory hole logs are attached.
- 1.3 A dynamic probe (DPSH) referenced as DP2 was driven adjacent to BH2 to help assess the condition of the soil strata. The probe test results are appended.
- 1.4 Groundwater levels have been recorded with the assistance of the Client during regular monitoring since installation on 3/12/24. A copy of the recorded observations is appended. Monitoring will continue to the end of March 2025.
- 1.5 The work was carried out for Deborah and Christopher Blows and nothing in this report confers or purports to confer on any third party, any benefit or any right to enforce any term of this report pursuant to the Contract (Rights of Third Parties) Act 1999.

# Ground Management Ltd

Civil and Geotechnical Engineering Services

Robin Hill Farm, Clay Lane, Fishbourne  
CHICHESTER, West Sussex PO18 8AB

PROJECT NO: G6625

FIGURE REF: Figure 1

PROJECT: Site Adjacent to The Grange, Westergate

PREPARED: AJHT

SECTION: Standpipe Installation

CHECKED: AJHT


TITLE: Site Location Plan

DATE: Feb 2025



North

(Not to scale)



Site Location

# Ground Management Ltd

Civil and Geotechnical Engineering Services

Robin Hill Farm, Clay Lane, Fishbourne,  
CHICHESTER, West Sussex PO18 8AB

PROJECT NO: G6625

FIGURE REF: Figure 2

PROJECT: Site Adjacent to The Grange, Westergate

PREPARED: AJHT

SECTION: Standpipe Installation

CHECKED: AJHT

TITLE: Exploratory Hole Location Plan

DATE: Feb 2025

Exploratory hole locations are indicative only unless dimensioned



Based on Google Maps Image

# Ground Management Ltd

Civil and Geotechnical Engineering Services

Robin Hill Farm Clay Lane Fishbourne  
CHICHESTER West Sussex PO18 8AB

Site

Site Adjacent to The Grange, Westergate

Number  
**BH1**

Excavation Method		Dimensions	Ground Level (mOD)		Client		Job Number
Dynamic (windowless) sampling using Archway Dart		80mm to 1.00m 70mm to 2.00m 60mm to 3.00m			Deborah & Christopher Blows		G6625
		Location	Dates	Engineer		Sheet	
Depth (m)	Sample / Tests	Water Depth (m)	Field Records	Level (mOD)	Depth (m) (Thickness)	Description	
0.80-1.00	D1		HV at 0.8m : 30, 30, 30 kPa		(0.30)	Grass over moist brown slightly sandy (fine) slightly clayey silt TOPSOIL with a little coarse medium and fine subangular to subrounded flint gravel. Occasional glass fragments	
1.20-1.60	D2				0.30	Soft to firm becoming firm orange brown silty CLAY with occasional coarse medium and fine subangular flint gravel. Occasional fine root up to 2mm dia.	
1.60-2.00	D3		HV at 1.5m : 45, 50, 50 kPa		(0.90)		
					1.20	Firm orange brown mottled grey silty CLAY with a little coarse medium and fine angular to subangular flint gravel.	
					(0.40)		
					1.60	Yellow brown slightly silty fine to medium SAND	
					(1.40)		
					3.00	Complete at 3.00m	
<b>Remarks</b> Borehole remained open during excavation Some seepage with groundwater rising to 0.9m below ground level 1hr after excavation 19mm dia.standpipe installed on completion - 2m slotted with geosoc and gravel surround, then plain with bentonite pellet seal							Scale (approx) 1:20
							Logged By AT
							Figure No. G6625.BH1

# Ground Management Ltd

Civil and Geotechnical Engineering Services

Robin Hill Farm Clay Lane Fishbourne  
CHICHESTER West Sussex PO18 8AB


Site

Site Adjacent to The Grange, Westergate


Number  
**BH2**

Excavation Method		Dimensions	Ground Level (mOD)		Client		Job Number
Dynamic (windowless) sampling using Archway Dart		80mm to 1.00m 70mm to 2.00m 60mm to 3.00m			Deborah & Christopher Blows		G6625
Location		See Location Plan	Dates		Engineer		Sheet 1/1
Depth (m)	Sample / Tests	Water Depth (m)	Field Records	Level (mOD)	Depth (m) (Thickness)	Description	
					(0.10) 0.10	Grass over moist brown slightly sandy (fine) slightly clayey silt TOPSOIL with a little medium and fine subangular to subrounded flint gravel.	
					(0.30)	MADE GROUND of coarse medium and fine subangular to subrounded flint gravel with some firm brown sandy clay / silt	
					0.40	Soft to firm becoming firm brown mottled red brown silty CLAY with occasional medium and fine subangular flint gravel.	
			HV at 0.8m : 40, 40, 40 kPa		(1.20)		
			HV at 1.5m : 45,50, 55 kPa		1.60	Wet yellow brown slightly silty fine to medium SAND	
					(1.40)		
					3.00	Complete at 3.00m	
<b>Remarks</b> Borehole remained open during excavation Some seepage with groundwater rising to 0.95m below ground level 1hr after excavation 19mm dia.standpipe installed on completion - 2m slotted with geosoc and gravel surround, then plain with bentonite pellet seal Dynamic probe (super heavy) driven adjacent to borehole - results on separate sheet							Scale (approx) 1:20
							Logged By AT
							Figure No. G6625.BH2

Ground Management Ltd  
Site Adjacent to The Grange, Westergate  
Dynamic Probe DPSH Results (DP2)



**Ground Management Ltd**  
**Site Adjacent to The Grange, Westergate**  
**Dynamic Probe DPSH Results (DP2)**  
**Correlated to SPT**



Project No: G6625

### **Site adjacent to The Grange, Westergate**


02-Feb-25

	BH1	BH2		
Upstand (m)	0.400	0.400		
Ground Level (mAOD)				
Cover level (mAOD)	0.400	0.400		
Base dip (m)				

mAOD: metres Above Ordnance Datum

Ground levels estimated by reference to survey (Not available)

**G6625 Site Adjacent to The Grange, Westergate**  
**Water Level Monitoring (relative to ground level)**



GROUNDWATER MONITORING AND SOAKAGE TESTING  
AT  
SITE ADJACENT TO THE GRANGE, WESTERGATE  
FOR  
DEBORAH AND CHRISTOPHER BLOWS

G6625

02 May 2025



**Ground Management Ltd**  
Civil and Geotechnical Engineering Services

**DOCUMENT CONTROL**

Report Title: G6625 Site Adjacent to The Grange, Westergate  
Groundwater Monitoring and Soakage Testing

Report No./ Issue: G6625-02/1

Report Status: Issued for Client Comment

Distribution: Deborah & Christopher Blows PDF copy 02 May 2025

Prepared by: Alistair Tyler BSc MSc DIC CEng MICE

Signed:

Ground Management Ltd Robin Hill Farm Clay Lane Fishbourne Chichester West Sussex PO18 8AB

Phone/Fax [REDACTED]

## **CONTENTS**

### 1.0 Introduction

Figure 1: Site Location Plan

Figure 2: Exploratory Hole Location Plan

Exploratory Hole Logs: Boreholes BH1 & BH2

Trial Pit TP1

Dynamic Probe (DPSH) DP2

Soakage Test Results Summary

Soakage Test Results

Ground Water Monitoring Observations

Site Photographs

## 1.0 INTRODUCTION

- 1.1 Ground Management Ltd have carried out standpipe installation and provided support with groundwater monitoring and soakage testing on the site adjacent to The Grange, Westergate, located as indicated on Figure 1.
- 1.2 The work included excavation of two boreholes referenced as BH1 and BH2 each to a depth of 3m at the locations indicated on Figure 2. A 19mm diameter standpipe was installed in each completed borehole to allow monitoring of groundwater levels.
- 1.3 A dynamic probe (DPSH) referenced as DP2 was driven adjacent to BH2 to help assess the condition of the soil strata. The probe test results are appended.
- 1.4 Groundwater levels have been recorded with the assistance of the Client during regular monitoring from installation on 3/12/24 to final readings on 30/3/25. A copy of the recorded observations is appended.
- 1.5 Following an initial period of groundwater monitoring a return visit was made on 31/3/25 to set up soakage testing within a hand dug trial pit referenced as TP1. The testing comprised 3 fills of the pit in accordance with BRE365 and continued to 2/4/25. A summary of the results and derived infiltration coefficients is attached together with the plotted test data. The pit was subsequently backfilled.
- 1.6 Copies of the typed exploratory hole logs are attached.
- 1.7 The work was carried out for Deborah and Christopher Blows and nothing in this report confers or purports to confer on any third party, any benefit or any right to enforce any term of this report pursuant to the Contract (Rights of Third Parties) Act 1999.

# Ground Management Ltd

Civil and Geotechnical Engineering Services

Robin Hill Farm, Clay Lane, Fishbourne,  
CHICHESTER, West Sussex PO18 8AB

PROJECT NO: G6625

FIGURE REF: Figure 1

PROJECT: Site Adjacent to The Grange, Westergate

PREPARED: AJHT

SECTION: Groundwater Monitoring and Soakage Testing

CHECKED: AJHT


TITLE: Site Location Plan

DATE: Mar 2025



North

(Not to scale)



Site Location

# Ground Management Ltd

Civil and Geotechnical Engineering Services

Robin Hill Farm, Clay Lane, Fishbourne,  
CHICHESTER, West Sussex PO18 8AB

PROJECT NO: G6625

FIGURE REF: Figure 2

PROJECT: Site Adjacent to The Grange, Westergate

PREPARED: AJHT

SECTION: Groundwater Monitoring and Soakage Testing

CHECKED: AJHT

TITLE: Exploratory Hole Location Plan

DATE: Mar 2025

Exploratory hole locations are indicative only unless dimensioned



Based on Google Maps Image

## Ground Management Ltd

Civil and Geotechnical Engineering Services

Robin Hill Farm Clay Lane Fishbourne  
CHICHESTER West Sussex PO18 8AB

## Sites

Site Adjacent to The Grange, Westergate

Number  
**BH1**

### Remarks

**Remarks** Borehole remained open during excavation

Some seepage with groundwater rising to 0.9m below ground level 1hr after excavation

19mm dia.standpipe installed on completion - 2m slotted with geosoc and gravel surround, then plain with bentonite pellet seal

Scale  
(approx)

Logged  
By

47

1:20 AM

**Figure No.**

# Ground Management Ltd

Civil and Geotechnical Engineering Services

Robin Hill Farm Clay Lane Fishbourne  
CHICHESTER West Sussex PO18 8AB

Site

Site Adjacent to The Grange, Westergate

Number  
**BH2**

Excavation Method		Dimensions	Ground Level (mOD)		Client	Number	
Dynamic (windowless) sampling using Archway Dart		80mm to 1.00m 70mm to 2.00m 60mm to 3.00m			Deborah & Christopher Blows	BH2	
		Location	Dates	Engineer		Job Number	
		See Location Plan				Sheet	
						1/1	
Depth (m)	Sample / Tests	Water Depth (m)	Field Records	Level (mOD)	Depth (m) (Thickness)	Description	
					(0.10) 0.10	Grass over moist brown slightly sandy (fine) slightly clayey silt TOPSOIL with a little medium and fine subangular to subrounded flint gravel.	
					(0.30)	MADE GROUND of coarse medium and fine subangular to subrounded flint gravel with some firm brown sandy clay / silt	
					0.40	Soft to firm becoming firm brown mottled red brown silty CLAY with occasional medium and fine subangular flint gravel.	
			HV at 0.8m : 40, 40, 40 kPa		(1.20)		
			HV at 1.5m : 45,50, 55 kPa		1.60	Wet yellow brown slightly silty fine to medium SAND	
					(1.40)		
					3.00	Complete at 3.00m	
<b>Remarks</b> Borehole remained open during excavation Some seepage with groundwater rising to 0.95m below ground level 1hr after excavation 19mm dia.standpipe installed on completion - 2m slotted with geosoc and gravel surround, then plain with bentonite pellet seal Dynamic probe (super heavy) driven adjacent to borehole - results on separate sheet						Scale (approx)	Logged By
						1:20	AT
						<b>Figure No.</b> G6625.BH2	

# Ground Management Ltd

Civil and Geotechnical Engineering Services

Robin Hill Farm Clay Lane Fishbourne  
CHICHESTER West Sussex PO18 8AB


Site

Site Adjacent to The Grange, Westergate


Trial Pit  
Number  
**TP1**

Excavation Method Hand dug		Dimensions 0.3 x 0.55	Ground Level (mOD)		Client Deborah & Christopher Blows		Job Number G6625
		Location See Location Plan	Dates 31/03/2025- 02/04/2025		Engineer		Sheet 1/1
Depth (m)	Sample / Tests	Water Depth (m)	Field Records	Level (mOD)	Depth (m) (Thickness)	Description	Legend
						Grass over slightly moist dark brown slightly sandy slightly clayey silt with some coarse medium and fine subangular flint gravel and occasional brick and concrete fragment up to cobble size. Reworked TOPSOIL/made ground, possible relic topsoil at base of stratum	
					(0.50)		
					0.50 (0.10)	Firm orange brown silty CLAY	
					0.60	Complete at 0.60m	
Plan				Remarks			
				Pit sides stable and vertical during excavation Groundwater was not encountered			
				Scale (approx)	Logged By	Figure No.	
				1:10	AT	G6625.TP1	

Ground Management Ltd  
Site Adjacent to The Grange, Westergate  
Dynamic Probe DPSH Results (DP2)



**Ground Management Ltd**  
**Site Adjacent to The Grange, Westergate**  
**Dynamic Probe DPSH Results (DP2)**  
**Correlated to SPT**



G6625 Site Adj. to The Grange, Westergate  
 Soakage Test Results Summary

Trial Pit	Pit Dimensions LxWxD (metres)	Test No.	Water Level at start of test (mm below ground level)	Duration of test (mins)	Fall of water level during test (mm)	Infiltration Coefficient (m/s) (see note)
TP1	0.3 x 0.5 x 0.6	1	75	235	482	$1.11 \times 10^{-5}$
		2	70	618	430	$3.04 \times 10^{-6}$
		3	65	588	475	$3.34 \times 10^{-6}$

## TP1 Test 1

Dimensions (m):


width = 0.30

length = 0.55

depth = 0.60

## Weather

mainly dry  
sunny  
spells



0  
0 Projected

Time (mins)

5

14

5

120

0

0.525

0.61125

1

5 m/s

Infiltration Coefficient = 1.11E-05 m/s

TP1 Test 2

Dimensions (m):

width = 0.30


length = 0.55

depth = 0.60

Date	Time	Date and time	Elapsed	Dip	End Fit
01/04/2025	08:00	01/04/2025 08:00	start	dry	
01/04/2025	08:02:00	01/04/2025 08:02	0	70	
01/04/2025	08:04:00	01/04/2025 08:04	2	80	
01/04/2025	08:06:00	01/04/2025 08:06	4	80	
01/04/2025	08:08:00	01/04/2025 08:08	6	80	
01/04/2025	08:10:00	01/04/2025 08:10	8	90	
01/04/2025	08:14:00	01/04/2025 08:14	12	90	
01/04/2025	08:18:00	01/04/2025 08:18	16	110	
01/04/2025	08:22:00	01/04/2025 08:22	20	120	
01/04/2025	08:30:00	01/04/2025 08:30	28	130	
01/04/2025	08:38:00	01/04/2025 08:38	36	140	
01/04/2025	08:54:00	01/04/2025 08:54	52	160	
01/04/2025	09:10:00	01/04/2025 09:10	68	180	
01/04/2025	09:42:00	01/04/2025 09:42	100	220	
01/04/2025	10:14:00	01/04/2025 10:14	132	260	
01/04/2025	10:46:00	01/04/2025 10:46	164	280	
01/04/2025	11:50:00	01/04/2025 11:50	228	330	
01/04/2025	12:50:00	01/04/2025 12:50	288	370	
01/04/2025	13:50:00	01/04/2025 13:50	348	400	
01/04/2025	14:50:00	01/04/2025 14:50	408	440	
01/04/2025	15:20:00	01/04/2025 15:20	438	440	
01/04/2025	15:50:00	01/04/2025 15:50	468	460	
01/04/2025	16:20:00	01/04/2025 16:20	498	480	
01/04/2025	16:50:00	01/04/2025 16:50	528	480	
01/04/2025	18:20:00	01/04/2025 18:20	618	500	

End Fit

Weather  
mainly dry  
sunny  
spells



Time (mins)

t0 70

t25 202.5 90

t50 335

t75 467.5 480

t100 600

fall 0.53

t25 - t75 0.265

Area t50 0.6155

0  
0 Projected

Infiltration Coefficient = 3.04E-06 m/s

## TP1 Test 3

### Dimensions (m):

width = 0.30

length = 0.55


depth = 0.60

Date	Time	Date and time	Elapsed	Dip
02/04/2025	07:59	02/04/2025 07:59	start	wet
02/04/2025	08:00:00	02/04/2025 08:00	0	65
02/04/2025	08:02:00	02/04/2025 08:02	2	70
02/04/2025	08:04:00	02/04/2025 08:04	4	80
02/04/2025	08:08:00	02/04/2025 08:08	8	90
02/04/2025	08:12:00	02/04/2025 08:12	12	90
02/04/2025	08:20	02/04/2025 08:20	20	110
02/04/2025	08:28:00	02/04/2025 08:28	28	120
02/04/2025	08:36:00	02/04/2025 08:36	36	130
02/04/2025	08:44:00	02/04/2025 08:44	44	140
02/04/2025	09:00:00	02/04/2025 09:00	60	170
02/04/2025	09:16:00	02/04/2025 09:16	76	190
02/04/2025	09:48:00	02/04/2025 09:48	108	230
02/04/2025	10:20:00	02/04/2025 10:20	140	270
02/04/2025	11:24:00	02/04/2025 11:24	204	330
02/04/2025	12:28:00	02/04/2025 12:28	268	380
02/04/2025	13:32:00	02/04/2025 13:32	332	420
02/04/2025	14:36:00	02/04/2025 14:36	396	450
02/04/2025	15:40:00	02/04/2025 15:40	460	480
02/04/2025	16:44	02/04/2025 16:44	524	510
02/04/2025	17:48	02/04/2025 17:48	588	540

## Fit

## Weather

mainly dry  
sunny  
spells



Time (mins)

t0 65

198.75 85

t50 332.5

466.25 440

t100 600

fall 0.535

t25 - t75 0.2675

Area t50 0.61975

0  
0 Projected

Infiltration Coefficient = 3.34E-06 m/s

Project No: G6625

### **Site adjacent to The Grange, Westergate**


30-Mar-25

	BH1	BH2		
Upstand (m)	0.400	0.400		
Ground Level (mAOD)				
Cover level (mAOD)	0.400	0.400		
Base dip (m)				

mAOD: metres Above Ordnance Datum

Ground levels estimated by reference to survey (Not available)

**G6625 Site Adjacent to The Grange, Westergate**  
**Water Level Monitoring (relative to ground level)**





Photograph 1 : BH1 Location



Photograph 2 : BH1 Extracted Samples



Photograph 3 : BH2 Location



Photograph 4 : BH2 Extracted Samples



Photograph 1 : TP1 Excavation Location



Photograph 2 : TP1 Excavation




Photograph 3 : TP1 Arisings

**7.4 Appendix D – Proposed Drainage Strategy, Contributing Area Plan & Exceedance Flow Routes, Proposed Typical Construction Details and Hydraulic Calculations.**




STANDARD DRAINAGE NOTES

- DO NOT SCALE FROM THIS DRAWING, REFER TO FIGURED DIMENSIONS ONLY. THE CONTRACTOR SHOULD CHECK ALL DIMENSIONS ON SITE.
- ALL DIMENSIONS IN MILLIMETRES AND ALL LEVELS ARE IN METERS UNLESS NOTED OTHERWISE.
- THIS DRAWING SHOULD BE READ IN CONJUNCTION WITH ALL OTHER RELEVANT ARCHITECT AND ENGINEERING DETAILS, DRAWINGS AND SPECIFICATIONS.
- ANY DISCREPANCIES SHOULD BE REPORTED TO THE ARCHITECT AND/OR ENGINEER IMMEDIATELY, SO THAT CLARIFICATION CAN BE SOUGHT PRIOR TO THE COMMENCEMENT OF WORK.
- BEFORE COMMENCING CONSTRUCTION THE CONTRACTOR MUST CHECK THE INVERT LEVELS OF EXISTING SEWERS TO WHICH CONNECTIONS ARE MADE. IN ADDITION THE CONTRACTOR MUST LOCATE AND DETERMINE INVERT LEVELS OF THE EXISTING SPURS TO WHICH CONNECTIONS ARE PROPOSED. ANY DISCREPANCIES ARE TO BE NOTIFIED TO THE ENGINEER IMMEDIATELY, PRIOR TO CONSTRUCTION.
- ALL DRAINAGE WORKS SHOULD COMMENCE AT THE PROPOSED DOWNSTREAM CONNECTION POINT. THE WORKS CONTINUING PROVIDED THE LOWEST CONVENIENT CONNECTION INVERT LEVELS TO THE ENGINEER. CONNECTIONS TO MANHOLES OR LARGER SIZED PIPES ETC. SHOULD BE SOFFIT TO SOFFIT UNLESS OTHERWISE INSTRUCTED BY THE ENGINEER. IF THIS IS NOT POSSIBLE INFORM THE ENGINEER IMMEDIATELY.
- COVER LEVELS SHOWN ARE APPROXIMATE. COVERS AND FRAMES SHALL BE SET TO FINISHED GROUND LEVELS AND FALLS.
- ALL UN-REFERENCED PIPES ARE TO BE 100mm DIA.
- ALL PIPES TO BE ADOPTED, OR CONNECTING TO ADOPTED SEWERS, TO BE VITRIFIED CLAY TO BS EN 295 AND BS585 (SWS ONLY), OR CONCRETE PIPES TO BE EN 1916 AND BS5911:PART 1.
- ROAD GULLY OUTLET PIPES ARE TO BE 150mm DIA. WITH CONCRETE SURROUND AND FLEXIBLE GRATES. GULLIES SHALL BE SET TO A 1:40 GRADIENT GRATES AND FRAMES TO BS EN 125 UNLESS OTHERWISE STATED.
- ADOPTABLE SEWERS SHALL BE CONSTRUCTED TO THE STANDARDS AND SPECIFICATION LAID DOWN IN SEWERS FOR ADOPTION 6th EDITION, WITH A VIEW TO ADOPTION UPON COMPLETION OF WORKS.
- ALL PRIVATE DRAINAGE TO BE IN ACCORDANCE WITH THE BUILDING REGULATIONS APPROVED DOCUMENT PART-H, AND TO THE SATISFACTION OF THE BUILDING CONTROL INSPECTOR.
- THE CONTRACTOR IS TO KEEP A RECORD OF ANY VARIATIONS MADE ON SITE, INCLUDING THE RELOCATION OF SEWERS OR DRAINS, SO THAT AS CONSTRUCTED DRAWING CAN BE PREPARED UPON COMPLETION OF THE PROJECT.
- STUB CONNECTIONS TO ADOPTABLE MANHOLES SHALL BE MADE FROM VITRIFIED CLAY AND CONSIST OF TWO ROCKER PIPES LAID AT THE SAME GRADIENT AS THE UP OR DOWNSTREAM PIPE.
- IF ANY SUB SOIL DRAINAGE SYSTEMS ARE UNCOVERED DURING THE WORKS CONTACT THE ENGINEER FOR INSTRUCTIONS. SUB SOIL DRAINS ARE TO BE DIVERTED AROUND NEW WORKS AND CONNECTED INTO THE SURFACE WATER.
- NO PRIVATE AREAS ARE TO DRAIN ONTO ADOPTABLE AREAS AND VICE VERSA.
- ALL EXISTING MANHOLE COVERS, GULLIES, ETC, ARE TO BE RAISED/LOWED TO SUIT NEW LEVELS.
- IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO CONFIRM THE LOCATION AND DEPTH OF ALL EXISTING SERVICES AND UTILITIES THAT MAY BE PRESENT.
- UPON COMPLETION BUT PRIOR TO HANDOVER, CONTRACTOR TO CARRY OUT FULL CCTV SURVEY OF DRAINAGE SYSTEM WHICH IS TO BE REVIEWED BY ENGINEER TO ENSURE SATISFACTORY INSTALLATION.
- PROPRIETARY PRODUCTS TO BE INSTALLED IN FULL ACCORDANCE WITH MANUFACTURER'S GUIDANCE.
- MANHOLE AND CHAMBER COVER GRADES:  
  - A15' IN ALL LANDSCAPED AREAS AND ON FOOTPATHS
  - B125' IN ALL DRIVEWAYS
  - C250' IN PRIVATE PARKING AREAS
  - D400' IN CARRIAGeway/ACCESS ROAD




CONTRIBUTING AREA PLAN (scale 1:200)

Proposed Catchment	Drainage Area (ha)
Roof Area	0.0150 ha
Driveway and Parking Space	0.0200 ha
Total catchment areas included in the proposed calculations	0.0350 ha



EXCEEDANCE FLOW ROUTES (scale 1:200)



Prefixed to drawing numbers shall signify the following:	
PL = PLANNING	Shall not be used for contract or construction purposes
P = PRELIMINARY	Shall not be used for contract or construction purposes
T = TENDER	Shall not be used for construction purposes
C = CONSTRUCTION	These are the only drawings that shall be used for construction purposes
R = RECORD	Record of actual completed work

FOR PLANNING ONLY

**cgs**  
civils  
Consulting Civil Engineers

CLIENT: DEBORAH AND CHRISTOPHER BLOWS

ARCHITECT: SMITH SIMMONS & PARTNERS

JOB TITLE: LAND NORTH OF THE GRANGE, WESTERGATE, PO20 3SQ

DRAWING TITLE: CONTRIBUTING AREA PLAN & EXCEEDANCE FLOW ROUTES

DRAWN	MR	ENGINEER	CS	CHECKED	CS	APPROVED	
DATE	JUNE 2025	SCALE @ A1	1:200				
JOB No.	C3388	STATUS	DRAWING No.				
REV.	P1	PL	201				

STANDARD DRAINAGE NOTES


- DO NOT SCALE FROM THIS DRAWING, REFER TO FIGURED DIMENSIONS ONLY. THE CONTRACTOR SHOULD CHECK ALL DIMENSIONS ON SITE.
- ALL DIMENSIONS IN MILLIMETRES AND ALL LEVELS ARE IN METRES UNLESS NOTED OTHERWISE.
- THIS DRAWING SHOULD BE READ IN CONJUNCTION WITH ALL OTHER RELEVANT ARCHITECT AND ENGINEERING DETAILS, DRAWINGS AND SPECIFICATIONS.
- ANY DISCREPANCIES SHOULD BE REPORTED TO THE ARCHITECT AND/OR ENGINEER IMMEDIATELY, SO THAT CLARIFICATION CAN BE SOUGHT PRIOR TO THE COMMENCEMENT OF WORK.
- BEFORE COMMENCING CONSTRUCTION THE CONTRACTOR MUST CHECK THE INVERT LEVELS OF EXISTING SEWERS TO WHICH CONNECTIONS ARE MADE. IN ADDITION THE CONTRACTOR MUST LOCATE AND DETERMINE INVERT LEVELS OF THE EXISTING SPURS TO WHICH CONNECTIONS ARE PROPOSED. ANY DISCREPANCIES ARE TO BE NOTIFIED TO THE ENGINEER IMMEDIATELY, PRIOR TO CONSTRUCTION.
- ALL DRAINAGE WORKS SHOULD COMMENCE AT THE PROPOSED DOWNTREAM POINT OF CONNECTION. THE WORKS CONTINUING PROVIDED THE LOWEST CONSTRUCTION INVERT LEVELS TO THE ENGINEER. CONNECTIONS TO MANHOLES OR LARGER SIZED PIPES ETC. SHOULD BE SOFFIT TO SOFFIT UNLESS OTHERWISE INSTRUCTED BY THE ENGINEER. IF THIS IS NOT POSSIBLE INFORM THE ENGINEER IMMEDIATELY.
- COVER LEVELS SHOWN ARE APPROXIMATE. COVERS AND FRAMES SHALL BE SET TO FINISHED GROUND LEVELS AND FALLS.
- ALL UN-REFERENCED PIPES ARE TO BE 100mm DIA.
- ALL PIPES TO BE ADOPTED, OR CONNECTING TO ADOPTED SEWERS, TO BE VITRIFIED CLAY TO BS EN 295 AND BS585 (SWS ONLY), OR CONCRETE PIPES TO BE EN 1916 AND BS5911:PART 1.
- ROAD GULLY OUTLET PIPES ARE TO BE 150mm DIA. WITH CONCRETE SURROUND AND FLEXIBLE GRATES. GULLIES SHALL BE TESTED AND GRADED/GRATINGS AND FRAMES TO BS EN 125 UNLESS OTHERWISE STATED.
- ADOPTABLE SEWERS SHALL BE CONSTRUCTED TO THE STANDARDS AND SPECIFICATION LAID DOWN IN SEWERS FOR ADOPTION 6TH EDITION, WITH A VIEW TO ADOPTION UPON COMPLETION OF WORKS.
- ALL PRIVATE DRAINAGE TO BE IN ACCORDANCE WITH THE BUILDING REGULATIONS APPROVED DOCUMENT PART H, AND TO THE SATISFACTION OF THE BUILDING CONTROL INSPECTOR.
- THE CONTRACTOR IS TO KEEP A RECORD OF ANY VARIATIONS MADE ON SITE, INCLUDING THE RELOCATION OF DRAINS OR DRAINS, SO THAT AS CONSTRUCTED DRAWING CAN BE PREPARED UPON COMPLETION OF THE PROJECT.
- STUB CONNECTIONS TO ADOPTABLE MANHOLES SHALL BE MADE FROM VITRIFIED CLAY AND CONSIST OF TWO ROCKER PIPES LAID AT THE SAME GRADIENT AS THE UP OR DOWNSTREAM PIPE.
- IF ANY SUB SOIL DRAINAGE SYSTEMS ARE UNCOVERED DURING THE WORKS CONTACT THE ENGINEER FOR INSTRUCTIONS. SUB SOIL DRAINS ARE TO BE DIVERTED AROUND NEW WORKS AND CONNECTED INTO THE SURFACE WATER.
- NO PRIVATE AREAS ARE TO DRAIN ONTO ADOPTABLE AREAS AND VICE VERSA.
- ALL EXISTING MANHOLE COVERS, GULLIES, ETC, ARE TO BE RAISED/LOWERED TO SUIT NEW LEVELS.
- IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO CONFIRM THE LOCATION AND DEPTH OF ALL EXISTING SERVICES AND UTILITIES THAT MAY BE PRESENT.
- UPON COMPLETION BUT PRIOR TO HANDOVER, CONTRACTOR TO CARRY OUT FULL CCTV SURVEY OF DRAINAGE SYSTEM WHICH IS TO BE REVIEWED BY ENGINEER TO ENSURE SATISFACTORY INSTALLATION.
- PROPRIETARY PRODUCTS TO BE INSTALLED IN FULL ACCORDANCE WITH MANUFACTURER'S GUIDANCE.
- MANHOLE AND CHAMBER COVER GRADES:
  - A15 IN ALL LANDSCAPED AREAS AND ON FOOTPATHS
  - B125 IN ALL DRIVEWAYS
  - C250 IN PRIVATE PARKING AREAS
  - D400 IN CARRIAGEWAY/ACCESS ROAD

Prefix to drawing numbers shall signify the following:

PL = PLANNING	Shall not be used for contract or construction purposes
P = PRELIMINARY	Shall not be used for contract or construction purposes
T = TENDER	Shall not be used for construction purposes
C = CONSTRUCTION	These are the only drawings that shall be used for construction purposes
R = RECORD	Record of actual completed work


P1	06.11.25	UPDATED TO ADC REQUIREMENTS	MR	CS	CS
P-	10.06.25	PRELIMINARY ISSUE	MR	CS	CS
REV	DATE	DESCRIPTION	BY	CHK	APP
 <b>CLIENT</b> DEBORAH AND CHRISTOPHER BLOWS <b>ARCHITECT</b> SMITH SIMMONS & PARTNERS <b>JOB TITLE</b> LAND NORTH OF THE GRANGE, WESTERGATE, PO20 3SQ <b>DRAWING TITLE</b> PROPOSED TYPICAL CONSTRUCTION DETAILS, SHEET 1 <b>DRAWN</b> MR <b>ENGINEER</b> CS <b>CHECKED</b> CS <b>APPROVED</b> CS <b>DATE</b> JUNE 2025 <b>SCALE @ A1</b> AS SHOWN <b>JOB No.</b> C3388 <b>STATUS</b> DRAWING No. REV. <b>PL</b> 301 P1					

FOR PLANNING ONLY



Pipes near buildings  
(not to scale)


Pipes near buildings  
(not to scale)



Pipes through wall detail  
(not to scale)


Pipes through wall with lintel detail  
(not to scale)

### FIGURE B 23 TYPICAL INSPECTION CHAMBER DETAIL - TYPE E




Note: Where the access chamber is in the highway (including any footway) the highway Authority can have specific requirements

(not to scale)




300mmØ SHALLOW  
INSPECTION CHAMBER DETAIL

(scale 1:20)




Typical Silt Trap Detail

(not to scale)




DESIGNED BASED ON ASSUMED CBR >5%  
FINAL SUBBASE AND CAPPING LAYER DEPTH SUBJECT TO CBR VALUE  
Proposed Permeable Block Paving  
Private Driveway and Parking Spaces  
Construction (PP1)


(scale 1:20)



Rodding eye detail  
(not to scale)



Proposed Downpipe Filter Chamber  
with discharge connection to Distribution Tank



Sel Controlflow 500  
Orifice Chamber

SEL Environmental LTD  
Phone: 01254 589987  
Email: sales@selenvironmental.com


(scale 1:20)

External Rainwater  
Pipe to Drain

(scale 1:20)

STANDARD DRAINAGE NOTES

- DO NOT SCALE FROM THIS DRAWING, REFER TO FIGURED DIMENSIONS ONLY. THE CONTRACTOR SHOULD CHECK ALL DIMENSIONS ON SITE.
- ALL DIMENSIONS IN MILLIMETRES AND ALL LEVELS ARE IN METERS UNLESS NOTED OTHERWISE.
- THIS DRAWING SHOULD BE READ IN CONJUNCTION WITH ALL OTHER RELEVANT ARCHITECT AND ENGINEERING DETAILS, DRAWINGS AND SPECIFICATIONS.
- ANY DISCREPANCIES SHOULD BE REPORTED TO THE ARCHITECT AND/OR ENGINEER IMMEDIATELY, SO THAT CLARIFICATION CAN BE SOUGHT PRIOR TO THE COMMENCEMENT OF WORK.
- BEFORE COMMENCING CONSTRUCTION THE CONTRACTOR MUST CHECK THE INVERT LEVELS OF EXISTING SEWERS TO WHICH CONNECTIONS ARE MADE. IN ADDITION THE CONTRACTOR MUST LOCATE AND DETERMINE INVERT LEVELS OF THE EXISTING SPURS TO WHICH CONNECTIONS ARE PROPOSED. ANY DISCREPANCIES ARE TO BE NOTIFIED TO THE ENGINEER IMMEDIATELY, PRIOR TO CONSTRUCTION.
- ALL DRAINAGE WORKS SHOULD COMMENCE AT THE PROPOSED DOWNSTREAM CONNECTION POINT. THE WORKS CONTINUING DOWNSTREAM SHOULD NOT LOWER THE CONTRACTOR'S INVERT LEVELS TO THE ENGINEER'S CONNECTIONS TO MANHOLES OR LARGER SIZED PIPES ETC. SHOULD BE SOFFIT TO SOFFIT UNLESS OTHERWISE INSTRUCTED BY THE ENGINEER, IF THIS IS NOT POSSIBLE INFORM THE ENGINEER IMMEDIATELY.
- COVER LEVELS SHOWN ARE APPROXIMATE. COVERS AND FRAMES SHALL BE SET TO FINISHED GROUND LEVELS AND FALLS.
- ALL UN-REFERENCED PIPES ARE TO BE 100mm DIA.
- ALL PIPES TO BE ADOPTED, OR CONNECTING TO ADOPTED SEWERS, TO BE VITRIFIED CLAY TO BS EN 295 OR BS585 (SWS ONLY), OR CONCRETE PIPES TO BE EN 1916 AND BS5911:PART 1.
- ROAD GULLY OUTLET PIPES ARE TO BE 150mm DIA. WITH CONCRETE SURROUNDED BY FLEXIBLE JONITE. GULLIES SHALL BE SETTED WITH GRADE 400 GRATING AND FRAMES TO BS EN 1251 UNLESS OTHERWISE STATED.
- ADOPTABLE SEWERS SHALL BE CONFORMED TO THE STANDARDS AND SPECIFICATION LAID DOWN IN SEWERS FOR ADOPTION 6th EDITION, WITH A VIEW TO ADOPTION UPON COMPLETION OF WORKS.
- ALL PRIVATE DRAINAGE TO BE IN ACCORDANCE WITH THE BUILDING REGULATIONS APPROVED DOCUMENT PART H, AND TO THE SATISFACTION OF THE BUILDING CONTROL INSPECTOR.
- THE CONTRACTOR IS TO KEEP A RECORD OF ANY VARIATIONS MADE ON SITE, INCLUDING THE RELOCATION OF SEWERS OR DRAINS, SO THAT AN AS CONSTRUCTED DRAWING CAN BE PREPARED UPON COMPLETION OF THE PROJECT.
- STUB CONNECTIONS TO ADOPTABLE MANHOLES SHALL BE MADE FROM VITRIFIED CLAY AND CONSIST OF TWO ROCKER PIPES LAID AT THE SAME GRADIENT AS THE UP OR DOWNSTREAM PIPE.
- IF ANY SUB SOIL DRAINAGE SYSTEMS ARE UNCOVERED DURING THE WORKS CONTACT THE ENGINEER FOR INSTRUCTIONS. SUB SOIL DRAINS ARE TO BE DIVERTED AROUND NEW WORKS AND CONNECTED INTO THE SURFACE WATER.
- NO PRIVATE AREAS ARE TO DRAIN ONTO ADOPTABLE AREAS AND VICE VERSA.
- ALL EXISTING MANHOLE COVERS, GULLIES, ETC, ARE TO BE RAISED/LOWED TO SUIT NEW LEVELS.
- IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO CONFIRM THE LOCATION AND DEPTH OF ALL EXISTING SERVICES AND UTILITIES THAT MAY BE PRESENT.
- UPON COMPLETION BUT PRIOR TO HANDOVER, CONTRACTOR TO CARRY OUT FULL CCTV SURVEY OF DRAINAGE SYSTEM WHICH IS TO BE REVIEWED BY ENGINEER TO ENSURE SATISFACTORY INSTALLATION.
- PROPRIETARY PRODUCTS TO BE INSTALLED IN FULL ACCORDANCE WITH MANUFACTURER'S GUIDANCE.
- MANHOLE AND CHAMBER COVER GRADES:
  - A15' IN ALL LANDSCAPED AREAS AND ON FOOTPATHS
  - B125' IN ALL DRIVEWAYS
  - C250' IN PRIVATE PARKING AREAS
  - D400' IN CARRIAGEWAY/ACCESS ROAD



### Biofiltration Planter Detail

(scale 1:20)

Prefixed to drawing numbers shall signify the following:-	
PL = PLANNING	Shall not be used for contract or construction purposes
P = PRELIMINARY	Shall not be used for contract or construction purposes
T = TENDER	Shall not be used for construction purposes
C = CONSTRUCTION	These are the only drawings that shall be used for construction purposes
R = RECORD	Record of actual completed work

P1	06.11.25	UPDATED TO ADC REQUIREMENTS	MR	CS	CS
P-	10.06.25	PRELIMINARY ISSUE	MR	CS	CS
REV	DATE	DESCRIPTION	BY	CHK	APP



CLIENT DEBORAH AND CHRISTOPHER BLOWS

ARCHITECT SMITH SIMMONS & PARTNERS

JOB TITLE LAND NORTH OF THE GRANGE,  
WESTERGATE, PO20 3SQ

DRAWING TITLE PROPOSED TYPICAL CONSTRUCTION DETAILS, SHEET 2

DRAWN MR ENGINEER CS CHECKED CS APPROVED CS

DATE JUNE 2025 AS SHOWN

JOB No. C3388 STATUS DRAWING No. REV. P1

FOR PLANNING ONLY

Design Settings

Rainfall Methodology	FEH-22	Minimum Velocity (m/s)	1.00
Return Period (years)	2	Connection Type	Level Soffits
Additional Flow (%)	0	Minimum Backdrop Height (m)	0.200
CV	1.000	Preferred Cover Depth (m)	1.200
Time of Entry (mins)	4.00	Include Intermediate Ground	✓
Maximum Time of Concentration (mins)	30.00	Enforce best practice design rules	✓
Maximum Rainfall (mm/hr)	75.0		

Nodes

	Name	Area (ha)	T of E (mins)	Cover Level (m)	Diameter (mm)	Easting (m)	Northing (m)	Depth (m)
	Permeable Paving Storage	0.022	4.00	10.150	450	104364.161	494023.354	0.580
	Existing Ditch			10.000	150	104350.463	494044.185	0.649
	S2			10.120	500	104363.011	494030.537	0.604
	RE2	0.003	4.00	10.150	150	104360.418	494030.704	0.400
	Bioretention Planter	0.006	4.00	10.200	150	104349.154	494021.552	0.450
	S1	0.002	4.00	10.150	450	104351.876	494014.203	0.455
	RE1	0.002	4.00	10.150	150	104352.456	494007.262	0.380
	S3			10.000	450	104351.658	494037.900	0.616

Links

Name	US Node	DS Node	Length (m)	ks (mm / n)	US IL (m)	DS IL (m)	Fall (m)	Slope (1:X)	Dia (mm)	T of C (mins)	Rain (mm/hr)
1.001	Permeable Paving Storage	S2	6.500	0.600	9.570	9.516	0.054	120.0	150	4.44	56.6
1.000	RE2	Permeable Paving Storage	15.900	0.600	9.750	9.570	0.180	88.3	100	4.32	56.6
3.000	Bioretention Planter	S1	5.700	0.600	9.750	9.695	0.055	103.6	100	4.13	56.6
2.000	RE1	S1	7.400	0.600	9.770	9.695	0.075	98.7	100	4.16	56.6
2.001	S1	Permeable Paving Storage	4.900	0.600	9.695	9.570	0.125	39.2	100	4.23	56.6
1.002	S2	S3	13.200	0.600	9.516	9.384	0.132	100.0	100	4.73	0.0
1.003	S3	Existing Ditch	3.300	0.600	9.384	9.351	0.033	100.0	100	4.80	0.0

Name	Vel (m/s)	Cap (l/s)	Flow (l/s)	US Depth (m)	DS Depth (m)	Σ Area (ha)	Σ Add Inflow (l/s)	Pro Depth (mm)	Pro Velocity (m/s)
1.001	0.916	16.2	6.9	0.430	0.454	0.034	0.0	68	0.879
1.000	0.819	6.4	0.5	0.300	0.480	0.003	0.0	19	0.486
3.000	0.755	5.9	1.2	0.350	0.355	0.006	0.0	31	0.594
2.000	0.774	6.1	0.3	0.280	0.355	0.002	0.0	15	0.397
2.001	1.235	9.7	1.8	0.355	0.480	0.009	0.0	29	0.946
1.002	0.769	6.0	0.0	0.504	0.516	0.034	0.0	0	0.000
1.003	0.769	6.0	0.0	0.516	0.549	0.034	0.0	0	0.000


Pipeline Schedule

Link	Length (m)	Slope (1:X)	Dia (mm)	Link Type	US CL (m)	US IL (m)	US Depth (m)	DS CL (m)	DS IL (m)	DS Depth (m)
1.001	6.500	120.0	150	Circular	10.150	9.570	0.430	10.120	9.516	0.454
1.000	15.900	88.3	100	Circular	10.150	9.750	0.300	10.150	9.570	0.480
3.000	5.700	103.6	100	Circular	10.200	9.750	0.350	10.150	9.695	0.355
2.000	7.400	98.7	100	Circular	10.150	9.770	0.280	10.150	9.695	0.355
2.001	4.900	39.2	100	Circular	10.150	9.695	0.355	10.150	9.570	0.480
1.002	13.200	100.0	100	Circular	10.120	9.516	0.504	10.000	9.384	0.516
1.003	3.300	100.0	100	Circular	10.000	9.384	0.516	10.000	9.351	0.549

Link	US Node	Dia (mm)	Node Type	MH Type	DS Node	Dia (mm)	Node Type	MH Type
1.001	Permeable Paving Storage	450	Manhole	Adoptable	S2	500	Manhole	Adoptable
1.000	RE2	150	Manhole	Adoptable	Permeable Paving Storage	450	Manhole	Adoptable
3.000	Bioretention Planter	150	Manhole	Adoptable	S1	450	Manhole	Adoptable
2.000	RE1	150	Manhole	Adoptable	S1	450	Manhole	Adoptable
2.001	S1	450	Manhole	Adoptable	Permeable Paving Storage	450	Manhole	Adoptable
1.002	S2	500	Manhole	Adoptable	S3	450	Manhole	Adoptable
1.003	S3	450	Manhole	Adoptable	Existing Ditch	150	Manhole	Adoptable

Manhole Schedule

Node	Easting (m)	Northing (m)	CL (m)	Depth (m)	Dia (mm)	Connections	Link	IL (m)	Dia (mm)	
Permeable Paving Storage	104364.161	494023.354	10.150	0.580	450		1	2.001	9.570	100
						2	1.000	9.570	100	
						0	1.001	9.570	150	
Existing Ditch	104350.463	494044.185	10.000	0.649	150		1	1.003	9.351	100
S2	104363.011	494030.537	10.120	0.604	500		1	1.001	9.516	150
						0	1.002	9.516	100	
RE2	104360.418	494030.704	10.150	0.400	150		0	1.000	9.750	100
Bioretention Planter	104349.154	494021.552	10.200	0.450	150		0	3.000	9.750	100
S1	104351.876	494014.203	10.150	0.455	450		1	3.000	9.695	100
						2	2.000	9.695	100	
						0	2.001	9.695	100	

### Manhole Schedule

Node	Easting (m)	Northing (m)	CL (m)	Depth (m)	Dia (mm)	Connections	Link	IL (m)	Dia (mm)	
RE1	104352.456	494007.262	10.150	0.380	150		0	2.000	9.770	100
S3	104351.658	494037.900	10.000	0.616	450		1	1.002	9.384	100
							0	1.003	9.384	100

### Simulation Settings

Rainfall Methodology	FEH-22	Analysis Speed	Normal	Starting Level (m)
Rainfall Events	Singular	Skip Steady State	x	Check Discharge Rate(s)
Summer CV	1.000	Drain Down Time (mins)	240	Check Discharge Volume
Winter CV	1.000	Additional Storage (m³/ha)	0.0	x

### Storm Durations

15	30	60	120	180	240	360	480	600	720	960	1440
----	----	----	-----	-----	-----	-----	-----	-----	-----	-----	------

Return Period (years)	Climate Change (CC %)	Additional Area (A %)	Additional Flow (Q %)
1	0	0	0
2	0	0	0
10	0	0	0
30	0	0	0
30	40	0	0
100	0	0	0
100	45	10	0

### Node S2 Online Orifice Control

Flap Valve	x	Design Depth (m)	0.600	Discharge Coefficient	0.600
Replaces Downstream Link	x	Design Flow (l/s)	1.0		
Invert Level (m)	9.516	Diameter (m)	0.025		

### Node Permeable Paving Storage Carpark Storage Structure

Base Inf Coefficient (m/hr)	0.00000	Invert Level (m)	9.570	Slope (1:X)	500.0
Side Inf Coefficient (m/hr)	0.00000	Time to half empty (mins)		Depth (m)	0.470
Safety Factor	2.0			Inf Depth (m)	
Porosity	0.30	Width (m)	10.000		
		Length (m)	20.000		

### Node Bioretention Planter Depth/Area Storage Structure

Base Inf Coefficient (m/hr)	0.00000	Safety Factor	2.0	Invert Level (m)	9.700
Side Inf Coefficient (m/hr)	0.00000	Porosity	1.00	Time to half empty (mins)	208

Depth (m)	Area (m²)	Inf Area (m²)	Depth (m)	Area (m²)	Inf Area (m²)	Depth (m)	Area (m²)	Inf Area (m²)
0.000	8.1	0.0	0.200	8.1	0.0	0.400	8.1	0.0
0.100	8.1	0.0	0.300	8.1	0.0	0.450	8.1	0.0

Results for 1 year Critical Storm Duration. Lowest mass balance: 100.00%

Node Event	US Node	Peak (mins)	Level (m)	Depth (m)	Inflow (l/s)	Node Vol (m³)	Flood (m³)	Status
180 minute summer	Permeable Paving Storage	120	9.630	0.060	1.9	2.4213	0.0000	OK
180 minute summer	Existing Ditch	120	9.369	0.018	0.4	0.0000	0.0000	OK
180 minute summer	S2	128	9.632	0.116	1.0	0.0227	0.0000	SURCHARGED
15 minute summer	RE2	11	9.765	0.015	0.3	0.0003	0.0000	OK
30 minute summer	Bioretention Planter	19	9.771	0.021	0.7	0.1656	0.0000	OK
30 minute summer	S1	18	9.715	0.020	0.9	0.0032	0.0000	OK
15 minute winter	RE1	11	9.782	0.012	0.2	0.0002	0.0000	OK
180 minute summer	S3	120	9.402	0.018	0.4	0.0029	0.0000	OK
Link Event (Upstream Depth)	US Node	Link	DS Node	Outflow (l/s)	Velocity (m/s)	Flow/Cap	Link Vol (m³)	Discharge Vol (m³)
180 minute summer	Permeable Paving Storage	1.001	S2	1.0	0.232	0.060	0.0689	
180 minute summer	S2	1.002	S3	0.4	0.427	0.067	0.0126	
15 minute summer	RE2	1.000	Permeable Paving Storage	0.3	0.295	0.047	0.0260	
30 minute summer	Bioretention Planter	3.000	S1	0.5	0.480	0.090	0.0065	
30 minute summer	S1	2.001	Permeable Paving Storage	0.9	0.508	0.090	0.0102	
15 minute winter	RE1	2.000	S1	0.2	0.269	0.033	0.0061	
180 minute summer	S3	1.003	Existing Ditch	0.4	0.428	0.067	0.0031	

4.9

Results for 2 year Critical Storm Duration. Lowest mass balance: 100.00%

Node Event	US Node	Peak (mins)	Level (m)	Depth (m)	Inflow (l/s)	Node Vol (m³)	Flood (m³)	Status
180 minute winter	Permeable Paving Storage	132	9.653	0.083	1.8	3.8060	0.0000	OK
180 minute winter	Existing Ditch	132	9.369	0.018	0.4	0.0000	0.0000	OK
180 minute winter	S2	132	9.653	0.137	0.9	0.0269	0.0000	<b>SURCHARGED</b>
15 minute summer	RE2	10	9.769	0.019	0.5	0.0003	0.0000	OK
15 minute summer	Bioretention Planter	11	9.777	0.027	1.3	0.2167	0.0000	OK
15 minute summer	S1	11	9.721	0.026	1.5	0.0042	0.0000	OK
15 minute summer	RE1	11	9.785	0.015	0.3	0.0003	0.0000	OK
180 minute winter	S3	132	9.403	0.019	0.4	0.0031	0.0000	OK
Link Event (Upstream Depth)	US Node	Link	DS Node	Outflow (l/s)	Velocity (m/s)	Flow/Cap	Link Vol (m³)	Discharge Vol (m³)
180 minute winter	Permeable Paving Storage	1.001	S2	0.9	0.226	0.057	0.0875	
180 minute winter	S2	1.002	S3	0.4	0.439	0.074	0.0135	
15 minute summer	RE2	1.000	Permeable Paving Storage	0.5	0.310	0.078	0.0378	
15 minute summer	Bioretention Planter	3.000	S1	0.9	0.537	0.150	0.0096	
15 minute summer	S1	2.001	Permeable Paving Storage	1.5	0.616	0.152	0.0130	
15 minute summer	RE1	2.000	S1	0.3	0.299	0.049	0.0089	
180 minute winter	S3	1.003	Existing Ditch	0.4	0.440	0.074	0.0034	7.3

Results for 10 year Critical Storm Duration. Lowest mass balance: 99.30%

Node Event	US Node	Peak (mins)	Level (m)	Depth (m)	Inflow (l/s)	Node Vol (m³)	Flood (m³)	Status
120 minute winter	Permeable Paving Storage	112	9.716	0.146	3.9	7.5599	0.0000	OK
120 minute winter	Existing Ditch	112	9.371	0.020	0.6	0.0000	0.0000	OK
120 minute winter	S2	112	9.715	0.199	1.1	0.0391	0.0000	SURCHARGED
15 minute summer	RE2	10	9.777	0.027	1.0	0.0005	0.0000	OK
15 minute summer	Bioretention Planter	11	9.792	0.042	2.4	0.3348	0.0000	OK
15 minute summer	S1	11	9.734	0.039	3.0	0.0063	0.0000	OK
15 minute summer	RE1	10	9.791	0.021	0.6	0.0004	0.0000	OK
120 minute winter	S3	112	9.405	0.021	0.6	0.0034	0.0000	OK
Link Event (Upstream Depth)	US Node	Link	DS Node	Outflow (l/s)	Velocity (m/s)	Flow/Cap	Link Vol (m³)	Discharge Vol (m³)
120 minute winter	Permeable Paving Storage	1.001	S2	1.1	0.275	0.065	0.1140	
120 minute winter	S2	1.002	S3	0.6	0.465	0.091	0.0157	
15 minute summer	RE2	1.000	Permeable Paving Storage	1.0	0.374	0.155	0.0631	
15 minute summer	Bioretention Planter	3.000	S1	2.0	0.678	0.330	0.0170	
15 minute summer	S1	2.001	Permeable Paving Storage	3.0	0.785	0.310	0.0220	
15 minute summer	RE1	2.000	S1	0.6	0.324	0.099	0.0148	
120 minute winter	S3	1.003	Existing Ditch	0.6	0.467	0.091	0.0039	9.4

Results for 30 year Critical Storm Duration. Lowest mass balance: 99.26%

Node Event	US Node	Peak (mins)	Level (m)	Depth (m)	Inflow (l/s)	Node Vol (m³)	Flood (m³)	Status
120 minute winter	Permeable Paving Storage	116	9.759	0.189	4.9	10.1636	0.0000	<span style="color: orange;">SURCHARGED</span>
120 minute winter	Existing Ditch	116	9.373	0.022	0.6	0.0000	0.0000	OK
120 minute winter	S2	116	9.759	0.243	1.1	0.0476	0.0000	<span style="color: orange;">SURCHARGED</span>
15 minute summer	RE2	10	9.780	0.030	1.3	0.0005	0.0000	OK
15 minute summer	Bioretention Planter	11	9.800	0.050	3.1	0.3991	0.0000	OK
120 minute winter	S1	116	9.759	0.064	1.3	0.0102	0.0000	OK
15 minute summer	RE1	10	9.794	0.024	0.8	0.0004	0.0000	OK
120 minute winter	S3	116	9.407	0.023	0.6	0.0036	0.0000	OK
Link Event (Upstream Depth)	US Node	Link	DS Node	Outflow (l/s)	Velocity (m/s)	Flow/Cap	Link Vol (m³)	Discharge Vol (m³)
120 minute winter	Permeable Paving Storage	1.001	S2	1.1	0.280	0.069	0.1144	
120 minute winter	S2	1.002	S3	0.6	0.479	0.102	0.0169	
15 minute summer	RE2	1.000	Permeable Paving Storage	1.3	0.408	0.202	0.0721	
15 minute summer	Bioretention Planter	3.000	S1	2.6	0.733	0.443	0.0213	
120 minute winter	S1	2.001	Permeable Paving Storage	1.3	0.291	0.132	0.0321	
15 minute summer	RE1	2.000	S1	0.8	0.334	0.131	0.0189	
120 minute winter	S3	1.003	Existing Ditch	0.6	0.481	0.102	0.0042	10.6

Results for 30 year +40% CC Critical Storm Duration. Lowest mass balance: 99.34%

Node Event	US Node	Peak (mins)	Level (m)	Depth (m)	Inflow (l/s)	Node Vol (m³)	Flood (m³)	Status
180 minute winter	Permeable Paving Storage	172	9.837	0.267	5.0	14.8714	0.0000	SURCHARGED
180 minute winter	Existing Ditch	172	9.374	0.023	0.7	0.0000	0.0000	OK
180 minute winter	S2	172	9.837	0.321	1.0	0.0629	0.0000	FLOOD RISK
180 minute winter	RE2	172	9.837	0.087	0.4	0.0016	0.0000	OK
180 minute winter	Bioretention Planter	172	9.837	0.087	0.9	0.7033	0.0000	OK
180 minute winter	S1	172	9.837	0.142	1.3	0.0226	0.0000	SURCHARGED
180 minute winter	RE1	172	9.837	0.067	0.2	0.0012	0.0000	OK
180 minute winter	S3	172	9.408	0.024	0.7	0.0039	0.0000	OK
Link Event (Upstream Depth)	US Node	Link	DS Node	Outflow (l/s)	Velocity (m/s)	Flow/Cap	Link Vol (m³)	Discharge Vol (m³)
180 minute winter	Permeable Paving Storage	1.001	S2	1.0	0.271	0.064	0.1144	
180 minute winter	S2	1.002	S3	0.7	0.498	0.118	0.0189	
180 minute winter	RE2	1.000	Permeable Paving Storage	0.4	0.182	0.062	0.1198	
180 minute winter	Bioretention Planter	3.000	S1	0.9	0.543	0.154	0.0429	
180 minute winter	S1	2.001	Permeable Paving Storage	1.3	0.230	0.130	0.0383	
180 minute winter	RE1	2.000	S1	0.2	0.222	0.033	0.0496	
180 minute winter	S3	1.003	Existing Ditch	0.7	0.501	0.118	0.0047	14.5

Results for 100 year Critical Storm Duration. Lowest mass balance: 99.35%

Node Event	US Node	Peak (mins)	Level (m)	Depth (m)	Inflow (l/s)	Node Vol (m³)	Flood (m³)	Status
180 minute winter	Permeable Paving Storage	168	9.804	0.234	4.5	12.8754	0.0000	<span style="color: orange;">SURCHARGED</span>
180 minute winter	Existing Ditch	168	9.374	0.023	0.7	0.0000	0.0000	OK
180 minute winter	S2	168	9.804	0.288	1.0	0.0564	0.0000	<span style="color: orange;">SURCHARGED</span>
180 minute winter	RE2	168	9.804	0.054	0.3	0.0010	0.0000	OK
15 minute summer	Bioretention Planter	11	9.808	0.058	3.9	0.4657	0.0000	OK
180 minute winter	S1	168	9.804	0.109	1.2	0.0173	0.0000	<span style="color: orange;">SURCHARGED</span>
180 minute winter	RE1	168	9.804	0.034	0.2	0.0006	0.0000	OK
180 minute winter	S3	168	9.408	0.024	0.7	0.0038	0.0000	OK
Link Event (Upstream Depth)	US Node	Link	DS Node	Outflow (l/s)	Velocity (m/s)	Flow/Cap	Link Vol (m³)	Discharge Vol (m³)
180 minute winter	Permeable Paving Storage	1.001	S2	1.0	0.271	0.064	0.1144	
180 minute winter	S2	1.002	S3	0.7	0.490	0.111	0.0181	
180 minute winter	RE2	1.000	Permeable Paving Storage	0.3	0.172	0.047	0.0965	
15 minute summer	Bioretention Planter	3.000	S1	3.4	0.776	0.566	0.0256	
180 minute winter	S1	2.001	Permeable Paving Storage	1.2	0.241	0.123	0.0383	
180 minute winter	RE1	2.000	S1	0.2	0.221	0.033	0.0376	
180 minute winter	S3	1.003	Existing Ditch	0.7	0.493	0.111	0.0045	13.6

Results for 100 year +45% CC +10% A Critical Storm Duration. Lowest mass balance: 98.98%

Node Event	US Node	Peak (mins)	Level (m)	Depth (m)	Inflow (l/s)	Node Vol (m³)	Flood (m³)	Status
180 minute winter	Permeable Paving Storage	176	9.952	0.382	6.7	21.7618	0.0000	FLOOD RISK
180 minute winter	Existing Ditch	176	9.376	0.025	0.8	0.0000	0.0000	OK
180 minute winter	S2	176	9.951	0.435	1.0	0.0853	0.0000	FLOOD RISK
180 minute winter	RE2	176	9.952	0.202	0.5	0.0036	0.0000	FLOOD RISK
180 minute winter	Bioretention Planter	172	9.952	0.202	1.3	1.6333	0.0000	FLOOD RISK
180 minute winter	S1	176	9.952	0.257	1.9	0.0408	0.0000	FLOOD RISK
180 minute winter	RE1	176	9.952	0.182	0.3	0.0033	0.0000	FLOOD RISK
180 minute winter	S3	176	9.411	0.027	0.8	0.0042	0.0000	OK
Link Event (Upstream Depth)	US Node	Link	DS Node	Outflow (l/s)	Velocity (m/s)	Flow/Cap	Link Vol (m³)	Discharge Vol (m³)
180 minute winter	Permeable Paving Storage	1.001	S2		1.0	0.279	0.065	0.1144
180 minute winter	S2	1.002	S3		0.8	0.520	0.138	0.0212
180 minute winter	RE2	1.000	Permeable Paving Storage		0.5	0.215	0.078	0.1244
180 minute winter	Bioretention Planter	3.000	S1		1.3	0.564	0.212	0.0446
180 minute winter	S1	2.001	Permeable Paving Storage		1.7	0.334	0.180	0.0383
180 minute winter	RE1	2.000	S1		0.3	0.213	0.049	0.0579
180 minute winter	S3	1.003	Existing Ditch		0.8	0.523	0.138	0.0053

7.5 **Appendix E – Maintenance Schedule**

## Maintenance Schedule

**Land north of the Grange, Westergate**

**For**

**Deborah and Christopher Blows**

Rev – **P1**

Reference **C3388**

Date **10<sup>th</sup> June 2025**

Revision	Date of Issue	Comments	Prepared By	Checked By
PL-	10/06/2024	Initial Issue	MR	CS
<b>P1</b>	06/11/2025	Updated to ADC requirements	MR	CS

## 1 Maintenance

### 1.1 Introduction

- 1.1.1 During construction, the Contractor will be responsible for maintaining the drainage and SuDS (Sustainable Drainage Systems). Upon handover, the occupier will take on the responsibility of these duties as laid out in this report.
- 1.1.2 The maintenance schedule for the proposed development will be split down into two separate categories; SuDS features and regular private drainage.

### 1.2 SuDS at Land north of the Grange, Westergate

- 1.2.1 As listed above, in section 5.1.2, the SuDS features used on site will be **Permeable Paving and Bioretention Planter**
- 1.2.2 The SuDS features have been designed for easy maintenance and comprise:
  - Regular Day-to-Day care – litter collection, regular gardening to control vegetation growth and checking inlets where water enters the SuDS features
  - Occasional tasks – checking the SuDS features and removing any silt that builds up in the SuDS feature
  - Remedial work – repairing damage where necessary

## 1.3 SuDS Drainage Maintenance Specification

### 1.3.1 Permeable Paving

In order to maintain the functioning of the permeable paving, the following maintenance requirements should be adhered to:

Table 21.3 Operation and maintenance requirements for permeable paving		
Maintenance Schedule	Required Action	Typical Frequency
Regular Maintenance	Brushing and vacuuming (standard cosmetic sweep over whole surface)	Once a year, after autumn leaf fall, or reduced frequency as required, based on site-specific observations of clogging or manufacturer's recommendations – pay particular attention to areas where water runs onto pervious surface from adjacent impermeable areas as this area is most likely to collect the most sediment
Occasional maintenance	Stabilise and mow contributing and adjacent areas Removal of weeds or management using glyphosate applied directly into the weeds by an applicator rather than spraying	As required As required – once per year on less frequently used pavements
Remedial Actions	Remediate any landscaping which, through vegetation maintenance or soil slip, has been raised to within 50mm of level of the paving	As required
	Remedial work to any depressions, rutting and cracked or broken blocks considered detrimental to the structural performance or a hazard to users, and replace lost jointing material	As required
	Rehabilitation of surface and upper substructure by remedial sweeping	Every 10 to 15 years or as required (if infiltration performance is reduced due to significant clogging)
Monitoring	Initial inspection	Monthly for three months after installation
	Inspect for evidence of poor operation and/or weed growth – if required take remedial action	Three-monthly, 48h after large storms in first six months
	Inspect silt accumulation rate and establish appropriate brushing frequencies	Annually
	Monitor inspection chambers	Annually

### 1.3.1 Bio retention systems

In order to maintain the functioning of the bio retention systems, the following maintenance requirements should be adhered to:

**Table 18.3 Operation and maintenance requirements for bio retention systems**

Maintenance Schedule	Required Action	Typical Frequency
Regular Inspections	Inspection infiltration surfaces for silting and ponding, record de-watering time of the facility and assess standing water levels in underdrain (if appropriate) to determine if maintenance is necessary	Quarterly
	Check operation of underdrains by inspection of flows after rain	Annually
	Assess plants for disease infection, poor growth, invasive species etc and replace as necessary	Quarterly
	Inspect inlets and outlets for blockages	Quarterly
Regular maintenance	Remove litter and surface debris and weeds	Quarterly (or more frequently for tidiness or aesthetic reasons)
	Replace any plants, to maintain planting density	As required
	Remove sediment, litter and debris build-up from around inlets or from forebays	Quarterly to biannually
Occasional maintenance	Infill any holes or scour in the filter medium, improve erosion protection if required	As required
	Repair minor accumulations of silt by raking away surface mulch, scarifying surface of medium and replacing mulch	As required
Remedial actions	Remove and replace filter medium and vegetation above	As required but likely to be > 20 years

## 1.4 General Drainage Maintenance Specification

### 1.4.1 Inlet Structures and Inspection Chambers

- Inlet structures such as rainwater downpipes, road gullies and channel drains should be free from obstruction at all times to allow free flow through the SuDS
- Inspection Chambers and Rodding Eyes are used on bends or where pipes come together. They allow access and cleaning to the system if necessary.

Inlet Structures and Inspection Chambers	
Regular Maintenance	Frequency
<b>Inlet Structures</b>  <b>Inspect rainwater downpipes, channel drains and road gullies, removing obstructions and silt as necessary. Check that there is no physical damage.</b>  <b>Trim vegetation 1m min surround to structures and keep area free from silt and debris</b>	Monthly
<b>Inspections Chambers and below ground control chambers.</b>  <b>Remove cover and inspect, ensuring that the water is flowing freely and that the exit route for water is unobstructed.</b> <b>Remove debris and silt.</b>  <b>Undertake inspection after leaf fall in Autumn</b>	Annually
<b>Occasional Maintenance</b>  <b>Check topsoil levels are 20mm above edges of chambers to avoid mower damage.</b>	As necessary
<b>Remedial Work</b>  <b>Repair physical damage if necessary</b>	As required

## 1.4.2 Below ground drainage pipes

- Below ground drainage pipes convey water to the SuDS system. They should always be free from obstruction to allow free flow.

<b>Below Ground Drainage Pipes</b>	
<b>Regular Maintenance</b>	<b>Frequency</b>
<b>Inspect and identify any areas that are not operating correctly. If required, take remedial action.</b>	Monthly for 3 months then annually
<b>Remove debris from the catchment surface (where it may cause risks to performance)</b>	Monthly
<b>Remove sediment from pre-treatment inlet structures and inspection chambers.</b>	Annually or as required
<b>Maintain vegetation to designed limits within the vicinity of below ground drainage pipes and tanks.</b>	Monthly or as required
<b>Remedial Work</b>	
<b>Repair physical damage if necessary</b>	As required
<b>Monitoring</b>	
<b>Inspect all inlets, outlets and vents to ensure that they are in good conditions and operating as designed.</b>	Annually
<b>Survey inside of pipe runs for sediment build up and remove if necessary.</b>	Every 5 years or as required