



From: Fiona Fitzgerald
Sent: 12 May 2014 11:58
To: Simon Davis
Subject: RE: AW/114/14/PL Southern Co-op - 68 Rose Green Road, Bognor Regis, Hampshire, PO21 3BQ

Hi Simon,

Further to my voicemail, thank you for the updated version of the BS4142 report. I still have some concerns with regard to this report.

Could you please ask the applicant to address the following points:

1. The distance used in Version 1 of the report (17.9m) has been amended in the text of the report in Version 2. However it does not seem to have been amended in the tables in Section 4.3.1 and 4.3.2. The fact that the distance used has changed should mean that there is a difference in the 'Geometric Divergence' value.
2. I have some concerns that the values recorded by the applicant for the background levels do not accurately represent the background levels present at the site. This is because they were taken at a distance of 17.9m from the proposed plant, on the road side. The assessment position is to the rear of the buildings, away from the roadside. As an example, a BS4142 carried out by this Authority in 2005 recorded a daytime background level of 32dB(A).
3. The applicant does not appear to have replied to my previous query as to whether the fact that there are two units to be installed has been taken into account in the assessment.

Many thanks

Fiona Fitzgerald