



KEY
① Install new standard 570mm projecting sign to box fascia as indicated and as standard details.
② Existing Fire Exit
③ New Pole Mounted Car Park Disclaimer Sign (600x600mm)
④ New Wall Mounted Car Park Disclaimer Sign (600x600mm)
⑤ New Wall Mounted Reserved for Staff (225x225mm)
⑥ New Wall Mounted Condenser Unit



Legals:

Not listed building and not in conservation area
Contractors should not undertake works without written notification of Landlord's and Planning approval.

General Notes:

- Approved security contractor to install CCTV cameras externally to comply with Barclays security standards. All cameras and associated equipment required to be coordinated with the design team before installation.
- Remove existing signage/fascia panel and associated fixings ready to receive new brand signage. Ensure all weatherproof treatments and fixings are retained in good order and are fit for purpose. Replace/repair weatherproofing treatment and fixings as required.
- Remove all redundant power supply fixtures and fittings and make good any visible fixings not covered by new installations.
- Clean brick/stone facade using suitable method. Extent of facade cleaned as indicated or as agreed with Clients project manager.
- Install vinyl information signage to inside face of glazing as indicated including opening hours, general information and security signage. Ensure setting out complies with Design guidance.
- Install vinyl safety manifestations as indicated to match RAL 5004 Black blue applied to the inside face of the glazing. Manifestations formed from two rows of 10 x 50mm vertical 'ticks' set out 50mm apart c/c and 950mm and 1525mm to the top of each row respectively.
- Signage to be installed complete with single phase 240v power with concealed containment suitable for box fascia signage and as approved details. Visible unsightly cables and conduit will not be acceptable.

NOTE

This drawing has been prepared from historical information that cannot be guaranteed accurate
Responsibility is not accepted for errors made by others in scaling from this drawing. All construction information should be taken from figured dimensions only.
All dimensions should be checked on site prior to the manufacture of any components

HATCHING

	New Secure partition wall		Amico Stone
	New Fire Resistant Secure Partition wall		Amico Steamed Ash Flooring
	New Partition wall		Barrier matting
	New Fire Resistant Partition wall		2008 Hard Flooring
	Book Room Secure wall		1200x600 2008 Hard Flooring
	Existing Partition wall		600x300
	Solid wall		Area not in scope
	Dry Lining		

PLEASE NOTE:

PLEASE READ THIS DRAWING IN CONJUNCTION WITH THE COVER SHEET AND SCOPE OF WORKS NOTES FROM ISV.
THE BUILDING IS NOT LISTED AND IS NOT IN A CONSERVATION AREA.

DWG :
REV :
DRAWN :
CHECKED :
NOTES :



Project

BOGNOR REGIS ROSE GREEN

6 NYETIMBER LANE
BOGNOR REGIS, WEST SUSSEX
PO21 3HG
PIM No.13113



Drawing Title

SIDE ELEVATION
AS PROPOSED
REFRESH 2012

Branch Sort Code	Branch ID	Supplier Project No
20-20-62	05	A0941
Scale	Drawn	Checked
1:100@A3	PC	
Drg.No	A0941_133	Date
		09/05/2012
		Revision
Barclays FM Project No.		