

NEW



Heritage Clay Tiles Ltd

The

Conservation

Range

50
Year
Guarantee

Conservation Dark Tile

A traditional handmade clay tile with a finely sanded surface,
suitable for main roof and vertical applications

Description	Roof	Vertical
Minimum Roof Pitch	35°	75°
Headlap (Minimum)	65mm	38mm
Batten Spacing at Maximum Gauge	100mm	114mm
Size of Tile	265 x 165mm	265 x 165mm
Covering Capacity	60 per m2	53 per m2
Cover Width	265 x 165mm	265 x 165mm
Weight as Laid	75kg per m2	66.25kg per m2
Battens per M2	10m	8.7m
Batten Size	38 x 25mm	38 x 25mm
Recommended Nail Type	40 x 2.65mm Alloy Clout	40 x 2.65mm Alloy Clout

ARUN DISTRICT COUNCIL AW/154/21/DOC

Heritage Clay Tiles Ltd

Hangman's Wood Ind Park
Stifford Road, South Ockendon
Essex RM15 6RL
tel: 01708 853 953
fax: 01708 851 852

email: sales@heritagetiles.co.uk
website: www.heritagetiles.co.uk

YOUR REF AW/154/21/DOC

Fittings

More Available.....Call For Details



YOUR REF AW/154/21/DOC.



TILE SAMPLE - CONSERVATION DARK - LAID ON EXISTING ROOF
ILLUSTRATING CLOSENESS OF MATCHING EXISTING ROOF TILES.

APPROVAL NO: AW/225/20/L.

FOR CONSERVATORY EXTENSION TO WEST HOUSE,
151, BARRACK LANE, ALDWICK, BOGNOR REGIS,
WEST SUSSEX, PO21 4ED.

ADD. REF: AW/154/21/DOC.