







				Trial Pit Log			Trialpit No SA1 Sheet 1 of 1		
Project Name: 34-44 Carlton Avenue				Project No. 19.1088		Co-ords: - Level:		Date 28/03/2019	
Location: Rose Green, Bognor Regis, West Sussex						Dimensions (m):		Scale 1:10	
Client: Counterpoint Properties						Depth 0.55		Logged SR	
Water Strike	Samples and In Situ Testing			Depth (m)	Level (m)	Legend	Stratum Description		
	Depth	Type	Results						
				0.35			MADE GROUND: Grass over Firm to stiff brown slightly gravelly sandy CLAY/SILT. Sand is fine to medium. Gravel is fine, subrounded to subangular flint and rare brick. Abundant rootlets. Occasional roots.		
				0.55			Stiff orangish greyish brown locally slightly gravelly very sandy clayey SILT. Sand is fine to coarse. Gravel is fine to medium, subrounded to angular flint and mudstone/siltstone.		
							End of pit at 0.55 m		
1									
2									
Remarks: Pit hand-excavated by client prior to CE arrival, to a maximum depth of 0.55mbgl. No groundwater encountered. BRE365 Infiltration Test completed within.									
Stability:									



				Trial Pit Log			Trialpit No SA2 Sheet 1 of 1		
Project Name: 34-44 Carlton Avenue				Project No. 19.1088		Co-ords: - Level:		Date 28/03/2019	
Location: Rose Green, Bognor Regis, West Sussex						Dimensions (m):		Scale 1:10	
Client: Counterpoint Properties						Depth 0.65		Logged SR	
Water Strike	Samples and In Situ Testing			Depth (m)	Level (m)	Legend	Stratum Description		
	Depth	Type	Results						
				0.30			MADE GROUND: Grass over TOPSOIL of Dark blackish brown soft to firm sandy gravelly locally very gravelly CLAY/SILT. Sand is fine to coarse. Gravel is fine to medium - fine to coarse where very gravelly - rounded to angular flint (pea shingle) slate and rare brick. Abundant rootlets. Occasional roots up to 8mm diameter.		
				0.65			Stiff brown to orangish brown slightly gravelly sandy very silty locally very sandy CLAY. Sand is fine to coarse. Gravel is fine to coarse, rounded to subangular flint and mudstone/siltstone.		
							End of pit at 0.65 m		
Remarks: Pit hand-excavated by client prior to CE arrival, to a maximum depth of 0.65mbgl. No groundwater encountered. BRE365 Infiltration Test completed within.									
Stability:									



				Trial Pit Log			Trialpit No SA3 Sheet 1 of 1		
Project Name: 34-44 Carlton Avenue				Project No. 19.1088		Co-ords: - Level:		Date 28/03/2019	
Location: Rose Green, Bognor Regis, West Sussex						Dimensions (m):		Scale 1:10	
Client: Counterpoint Properties						Depth 0.65		Logged SR	
Water Strike	Samples and In Situ Testing			Depth (m)	Level (m)	Legend	Stratum Description		
	Depth	Type	Results						
				0.10			MADE GROUND: Grass over TOPSOIL of Soft dark blackish brown locally gravelly sandy silty CLAY. Sand is fine to medium. Gravel is fine, subrounded to angular flint, rare brick and rare glass. Frequent roots and rootlets.		
				0.30			MADE GROUND: Firm brown slightly gravelly slightly sandy silty CLAY. Sand is fine to medium. Gravel is fine to medium, subrounded to angular flint, mudstone and rare brick.		
				0.65			Stiff brown to orangish brown locally slightly gravelly slightly sandy locally sandy silty CLAY. Sand is fine to medium. Gravel is fine to coarse, subrounded to subangular flint. Rare rootlets.		
							End of pit at 0.65 m		
Remarks: Pit hand-excavated by client prior to CE arrival, to a maximum depth of 0.65mbgl. No groundwater encountered. BRE365 Infiltration Test completed within.									
Stability:									

