

NOTES

This drawing is the copyright of the Architect and must not be reproduced or used without the Architect's permission. Figured dimensions are to take precedence over scaled dimensions. The Contractor is responsible for checking all figured dimensions on drawings against actual site dimensions. Scaled dimensions are not to be used for construction and setting out purposes. Any discrepancies are to be reported to the Architect. This drawing should be read in conjunction with schedules, specifications and engineers drawings and details where applicable.

ROOF STRUCTURE

Roof structure subject to engineers calculations but generally as follows. Roof to be constructed in treated sw rafters 150 x 50 C24 at 400ccs, supported on 100mm sw framed skaeeling wall.

Double up rafters and trim to receive Velux rooflight to En Suite Bathroom, Velux top hung rooflight reference GA3059C04, trim opening externally using standard Velux flashing kit.

Wall plates to be 100 x 75 treated sw bedded on internal skin of blockwork and restrained with holding down straps comprising 1.2m long 30x5mm galvanized twice bent straps taken down internal face of wall and twice fixed.

Ceiling joists to be 150 x 50mm sw twice bolted through rafters with M16 bolts and timber connectors.

DORMERS

Dormer construction to Dressing Room on south elevation to be as existing to Master Bedroom, in 100x50mm treated sw, dormer cheeks clad in 15mm EQ ply sheet and clad in tile hanging to match existing. Existing dormer to Master Bedroom to be adapted to suit pair of inward opening doors.

Flat roof section below doors to be finished in Code 5 lead on 19 EQ ply decking, all in accordance with LDA detail sheets.

ROOF ALTERATIONS

Form new opening for Velux rooflight to Bedroom 3, double up existing rafters in sections to match existing and trim opening to suit top hung Velux reference GH13059C04. Trim opening externally using standard Velux flashing kit.

Strip back ties as necessary, extend ridge and rafters in sections to match existing to continue main roof slope over former barn end.

