

Option	Description
Roof Finish Option A	413mm x 330mm interlocking concrete roofing tiles to BS EN 491, colour and pattern to match existing dwelling laid in accordance with manufacturers instructions and fixed in accordance with BS5534. 75mm Minimum headlap. 50x25mm treated s/w battens. All roof tiles including ridges, hips, verges, etc. are to be mechanically fixed with nails or manufactured clips to comply with BS5534:2014
	Ridges: Form ridge with 240mm diameter x 457mm long concrete half-round ridge capping tiles to BS EN 490 and 491. Bed edges of tiles and joint and point in coloured cement mortar (1:4) incorporating bonding agent. Fill exposed ends of ridges at gables with coloured cement mortar (1:4) incorporating bonding agent, finished flush.
Option B	Hips: As Ridges with neat and accurate mitred tiles at junctions with ridges.
	265mm x 165mm. Plain clay or concrete roofing tiles to BS EN 491, colour and pattern to match existing dwelling laid in accordance with manufacturers instructions and fixed in accordance with BS5534. Lay each course to a half lap bond with tails aligned and joints slightly open. 50x25mm treated s/w battens. All roof tiles including ridges, hips, verges, etc. are to be mechanically fixed with nails or manufactured clips to comply with BS5534:2014
Option C	Ridges: Form ridge with 240mm diameter x 457mm long concrete half-round ridge capping tiles to BS EN 490 and 491. Bed edges of tiles and joint and point in coloured cement mortar (1:4) incorporating bonding agent. Fill exposed ends of ridges at gables with coloured cement mortar (1:4) incorporating bonding agent, finished flush.
	Hips: As Ridges with neat and accurate mitred tiles at junctions with ridges
Option D	600mm x 300mm Asbestos-free mineral fibre cement slates to BS EN 492, type NT colour and pattern to match existing dwelling laid in accordance with manufacturers instructions and fixed in accordance with BS5534. Lay each course to a half lap bond with tails aligned and joints slightly open. Minimum end lap. 100mm. 50x25mm treated s/w battens. All roof tiles including ridges, hips, verges, etc. are to be mechanically fixed with nails or manufactured clips to comply with BS5534:2014
	Ridges and Hips: Form ridge and hips with plain angle fibre cement ridge slates to suit main slating fixed to timber battens with screws. Bed and point with coloured cement mortar (1:4) incorporating bonding agent. Accurately cut slates at hip. -OR- Form ridge and hips with plain angle concrete ridge tiles to suit main slating. Bed and point with coloured cement mortar (1:4) incorporating bonding agent. Accurately cut slates at hip.
Option E	Form ridge and hips with plain angle concrete ridge tiles to suit main slating. Bed and point with coloured cement mortar (1:4) incorporating bonding agent. Accurately cut slates at hip.
	360mm x 340mm Lightweight interlocking single lap slate Britblock by Sandicof. Colour to match existing dwelling laid in accordance with manufacturers instructions and fixed in accordance with BS5534. Minimum headlap 75mm. 50x25mm treated s/w battens. All roof tiles including ridges, hips, verges, etc. are to be mechanically fixed with nails or manufactured clips to comply with BS5534:2014
Roof Structure	Ridges and Hips: Form ridge and hips with plain angle fibre cement ridge slates to suit main slating fixed to timber battens with screws. Bed and point with coloured cement mortar (1:4) incorporating bonding agent. Accurately cut slates at hip. -OR- Form ridge and hips with plain angle fibre cement ridge slates to suit main slating fixed to timber battens with screws. Bed and point with coloured cement mortar (1:4) incorporating bonding agent. Accurately cut slates at hip.
	Form ridge and hips with plain angle concrete ridge tiles to suit main slating. Bed and point with coloured cement mortar (1:4) incorporating bonding agent. Accurately cut slates at hip. Roofing Felt: Reinforced roofing felt to BS747:1977, Class 1, Type IF min 150mm lap on treated s/w rafters at 400mm crs size as shown on drawing. Roof laid to pitch as shown on drawing. Rafters: All rafters birdsmouthed over 100x38mm wallplates. Wallplates to be secured to walls with 800x30x6mm anchor straps at 1200mm max crs. Ventilation: Provide above fascia ventilation equal to a continuous 25mm gap along the length of the fascia. Install roof ventilator between rafters to be installed in accordance with Glidevale instructions. Provide ridge ventilation equal to a continuous 5mm gap along the length of the ridge.
Flat roof	Flat roof construction: 12.5mm exterior quality ply wood sheets on flat roof rafters at 400mm crs (size as shown on drawings). Roof covering: RubberBond EPDM Premium FR 1.52MM (.060) fully adhered with RubberBond Deck Adhesive and fitted with flex plate strip around the perimeter. Laid to falls as shown on drawings.
Ceiling Joists	Ceilings joists (size as shown on drawing) at 400mm crs.
Ceiling Insulation	Provide 100mm glassfibre insulation to between ceiling joists and 200mm over ceiling joists.
Roof Insulation	Provide 100mm thick Celotex FR4000 insulation board k=0.022 w/mk between and along the slope of rafters and 50mm thick Celotex FR4000 insulation board k=0.022 w/mk to underside of rafters. Provide 50mm airspace between insulation and felt. Provide 500gauge polythene vapour barrier between insulation and ceiling.
Gutters	100mm half round uPVC gutters Colour to match main building fixed at 900mm crs with brass screws Pipes, fittings and accessories: PVCu to BS 4576:Part 1, 1989. 63mm dia PVC-u downpipes at positions as shown on plan to BS4576:Part 1 plugged and screwed to brickwork at 1800mm crs with brass screws.
Option 1A	100mm rectangular Upvc gutters Colour to match main building fixed at 900mm crs with brass screws Pipes, fittings and accessories: 63mm square uPVC downpipes at positions as shown on plan plugged and screwed to brickwork at 1800mm crs with brass screws.
Option 1B	100mm Ogce uPVC gutters Colour to match main building fixed at 900mm crs with brass screws Pipes, fittings and accessories: PVCu to BS 4576:Part 1, 1989. 63mm dia PVC-u downpipes at positions as shown on plan to BS4576:Part 1 plugged and screwed to brickwork at 1800mm crs with brass screws.
Option 2A	100mm half round Aluminium gutters with eared sockets, light grade, Colour to match main building fixed at 900mm crs with brass screws. Pipes, fittings and accessories To BS 2997: 1980. 63mm dia Aluminium downpipes at positions as shown on plan plugged and screwed to brickwork at 1800mm crs with brass screws.
Option 2B	100mm rectangular Aluminium gutters with eared sockets, light grade, Colour to match main building fixed at 900mm crs with brass screws. Pipes, fittings and accessories To BS 2997: 75mm square Aluminium downpipes at positions as shown on plan plugged and screwed to brickwork at 1800mm crs with brass screws.
Option 2C	100mm Ogce Aluminium gutters with eared sockets, light grade, Colour to match main building fixed at 900mm crs with brass screws. Pipes, fittings and accessories To BS 2997: 75mm square Aluminium downpipes at positions as shown on plan plugged and screwed to brickwork at 1800mm crs with brass screws.
Option 3A	100mm half round Cast Iron gutters with eared sockets, Colour to match main building fixed at 900mm crs fascia with galvanised mild steel brackets and sherardized screws. Pipes, fittings and accessories to BS 460 63mm dia Cast Iron downpipes at positions as shown on plan plugged and screwed to brickwork at 1800mm crs with brass screws.
Option 3B	100mm rectangular Cast Iron gutters with eared sockets, light grade, Colour to match main building fixed at 900mm crs fascia with galvanised mild steel brackets and sherardized screws. Pipes, fittings and accessories to BS 460 63mm dia Cast Iron downpipes at positions as shown on plan plugged and screwed to brickwork at 1800mm crs with brass screws.
Option 3C	100mm Ogce Cast Iron gutters with eared sockets, light grade, Colour to match main building fixed at 900mm crs fascia with galvanised mild steel brackets and sherardized screws. Pipes, fittings and accessories to BS 460 63mm dia Cast Iron downpipes at positions as shown on plan plugged and screwed to brickwork at 1800mm crs with brass screws.
Eaves and Fascias	
Fascias	Flush Fascia As per detail
Option A	100mm Soffit As per detail
Option B	100mm slopping Soffit As per detail
Option C	
Option D	250mm Soffit As per detail
Valley's	Valley Construction: Code No 4 lead to BS1178 laid to 900mm lengths with welled joints and give free movement between lead and 1 No layer of roofing felt on 225x25mm valley boards.
Dormers	Construct dormers as per detail on double rafters using 100x50mm framing at 400mm crs. Provide 150x25mm t&g mahogany boarding on untearable breathable roofing membrane run 150mm lap on framing. Provide 100mm thick Kooltherm K7 insulation board between framing and 32.5mm Kooltherm K118 (incorporating 12.5 plasterboard) to inside face of dormer. Provide 300mm glassfibre between and over ceiling joists. Provide 12mm plasterboard and skim internal finish. Pitch roof over constructed as per main roof with 100x50mm rafters and ceiling joists. Roof pitch to be as shown on drawings. Soffits and fascias to match main building. Gutters and downpipes to match.
Velux	780 x 980mm Velux window(s) GGL-M04-3000 in positions as shown on drawing fitted in accordance with manufacturers instructions. Incorporating Slate flashings EDL-M04-000 or tile flashings EDZ-M04-2002.
Windows	Provide internal lining LSB-M04-2002.
Cavity Walls	300mm Cavity Walls: 100mm outer leaf, 100mm cavity and 100mm inner leaf.
Option 1A	Brickwork in outer leaf of external cavity walls 215x65x100mm facing brick to match existing dwelling to BS3921 Mortar: Cement/lime/sand 1:1:6. Bond: As per drawing. Joints: Weather struck pointing as work proceeds.
Option 1B	-or- Smooth Render Blockwork: Blocks in outer leaf of external cavity walls, dense, to BS 6073 Parts 1, natural gravel or crushed stone to BS 882. Average compressive strength: 7 N/mm sq. with no block from any 10 Nr. tested having a strength less than 5.6 N/mm sq and density not less than 1990 kg/m cu. Work size 440x215x100mm. Mortar: 1:1:6 cement:lime:sand. Bond: Stretcher. Render Finish Undercoat: Cement: BS 12. Sand: BS 1199 Table 1. Admixture: Waterproofing agent. Mix proportions: Cement:sand (1:3). Thickness (excluding dubbing out): 10mm. Final Coat: White cement: BS 12. Hydrated lime: BS 890, Part 2. Sand: BS 1199, Table 1. Mix proportions: Cement:lime:sand (1:1:6). Thickness: 10mm. Finish: Smooth.
Option 1C	-or- Drydash Render Blockwork: Blocks in outer leaf of external cavity walls, dense, to BS 6073 Parts 1, natural gravel or crushed stone to BS 882. Average compressive strength: 7 N/mm sq. with no block from any 10 Nr. tested having a strength less than 5.6 N/mm sq and density not less than 1990 kg/m cu. Work size 440x215x100mm. Mortar: 1:1:6 cement:lime:sand. Bond: Stretcher. Render Finish Undercoat: Cement: BS 12. Sand: BS 1199 Table 1. Admixture: Waterproofing agent. Mix proportions: Cement:sand (1:3). Thickness (excluding dubbing out): 10mm. Final Coat: White cement: BS 12. Hydrated lime: BS 890, Part 2. Sand: BS 1199, Table 1. Mix proportions: Cement:lime:sand (1:1:6). Thickness: 10mm. Finish: White limestone chippings.
Option 1D	-or- Timber cladding: Blocks in outer leaf of external cavity walls, dense to BS 6073 Parts 1, natural gravel or crushed stone to BS 882. Average compressive strength: 7 N/mm sq. with no block from any 10 Nr. tested having a strength less than 5.6 N/mm sq and density not less than 1990 kg/m cu. Work size 440x215x100mm. Mortar: 1:1:6 cement:lime:sand. Bond: Stretcher. Finish: Fairface. 50x25mm vertical battens fixed to wall at 400mm centres with 150x25mm tapered cladding laid horizontally.
Cavity Walls	-with- Blocks in inner leaf of cavity wall, insulation block compressive strength: 7 N/mm sq. Work size 440mm x 215mm. Mortar: 1:1:6 cement/lime/sand. 'K' Value: 0.55 w/m. sq. deg. c. Bond: Stretcher. Finish as per drawing proceeds.



GaragePlans.co.uk

1 Thorndale Road North, Hillsborough Road, Carryduff, Belfast BT8 8HY

Tel: 028 9081 4106 Mobile: 077 2007 7465 info@garageplans.co.uk

www.garageplans.co.uk

	Wall ties to be as recommended by insulation manufacturer to BS1243, 1978. Galvanised/stainless steel wire. Max Centre of 750mm horizontally and 450mm vertically. Wall ties to be spaced not more than 300mm crs apart vertically within 225mm of openings and unbonded jambs. All cavities closed below wallplate level with insulation blockwork to prevent cold bridging. Cavities closed at gables with 12.5mm masterboard or equal. Concrete cavity: fill to ground level and minimum 225mm below DPC. Brickwork in outer leaf of 225mm walls 215x65x100mm facing brick to match existing dwelling to BS3921 Mortar: Cement/lime/sand 1:1:6. Bond: Stretcher. Joints: Weather struck pointing as work proceeds. Blocks in inner leaf of external 225mm walls, dense, to BS 6073 Parts 1, natural gravel or crushed stone to BS 882. Average compressive strength: 7 N/mm sq. with no block from any 10 Nr. tested having a strength less than 5.6 N/mm sq and density not less than 1990 kg/m cu. Work size 440x215x100mm. Mortar: 1:1:6 cement:lime:sand. Bond: Stretcher. Outer and inner leafs of 225mm walls to be tied together with wall ties Galvanised/stainless steel wire. Max Centre of 750mm horizontally and 450mm vertically. Wall ties to be spaced not more than 300mm crs apart vertically. Within 225mm of openings and unbonded jambs. 225mm Smooth Render Blockwork: Blocks in 225mm thick block walls, dense, to BS 6073 Parts 1, natural gravel or crushed stone to BS 882. Average compressive strength: 7 N/mm sq. with no block from any 10 Nr. tested having a strength less than 5.6 N/mm sq and density not less than 1990 kg/m cu. Work size 440x215x100mm. Mortar: 1:1:6 cement:lime:sand. Bond: Stretcher. Render Finish Undercoat: Cement: BS 12. Sand: BS 1199 Table 1. Admixture: Waterproofing agent. Mix proportions: Cement:sand (1:3). Thickness (excluding dubbing out): 10mm. Final Coat: White cement: BS 12. Hydrated lime: BS 890, Part 2. Sand: BS 1199, Table 1. Mix proportions: Cement:lime:sand (1:1:4). Thickness: 10mm. Finish: Smooth. 225mm Drydash Render Blockwork: Blocks in 225mm thick block walls, dense, to BS 6073 Parts 1, natural gravel or crushed stone to BS 882. Average compressive strength: 7 N/mm sq. with no block from any 10 Nr. tested having a strength less than 5.6 N/mm sq and density not less than 1990 kg/m cu. Work size 440x215x100mm. Mortar: 1:1:6 cement:lime:sand. Bond: Stretcher. Render Finish Undercoat: Cement: BS 12. Sand: BS 1199 Table 1. Admixture: Waterproofing agent. Mix proportions: Cement:sand (1:3). Thickness (excluding dubbing out): 10mm. Final Coat: White cement: BS 12. Hydrated lime: BS 890, Part 2. Sand: BS 1199, Table 1. Mix proportions: Cement:lime:sand (1:1:4). Thickness: 10mm. Finish: White limestone chippings. 225mm Blockwork: Blocks in 225mm thick block walls, dense, to BS 6073 Parts 1, natural gravel or crushed stone to BS 882. Average compressive strength: 7 N/mm sq. with no block from any 10 Nr. tested having a strength less than 5.6 N/mm sq and density not less than 1990 kg/m cu. Work size 440x215x100mm. Mortar: 1:1:6 cement:lime:sand. Bond: Stretcher. Finish: Fairface. 100mm Walls Option 3A Brick walls 215x65x100mm facing brick to match existing dwelling to BS3921 Mortar: Cement/lime/sand 1:1:6. Bond: Stretcher. Joints: Weather struck pointing as work proceeds. 225x125mm Brickwork piers at 3000mm max crs. Option 3B 100mm Smooth Render Blockwork: Blocks in 100mm thick block walls, dense, to BS 6073 Parts 1, natural gravel or crushed stone to BS 882. Average compressive strength: 7 N/mm sq. with no block from any 10 Nr. tested having a strength less than 5.6 N/mm sq and density not less than 1990 kg/m cu. Work size 440x215x100mm. Mortar: 1:1:6 cement:lime:sand. Bond: Stretcher. Render Finish Undercoat: Cement: BS 12. Sand: BS 1199 Table 1. Admixture: Waterproofing agent. Mix proportions: Cement:sand (1:3). Thickness (excluding dubbing out): 10mm. Final Coat: White cement: BS 12. Hydrated lime: BS 890, Part 2. Sand: BS 1199, Table 1. Mix proportions: Cement:lime:sand (1:1:4). Thickness: 10mm. Finish: Smooth. Option 3C 100mm Drydash Render Blockwork: Blocks in 100mm walls, dense, to BS 6073 Parts 1, natural gravel or crushed stone to BS 882. Average compressive strength: 7 N/mm sq. with no block from any 10 Nr. tested having a strength less than 5.6 N/mm sq and density not less than 1990 kg/m cu. Work size 440x215x100mm. Mortar: 1:1:6 cement:lime:sand. Bond: Stretcher. Finish: Fairface. Option 3D 100mm Blockwork: Blocks in 100mm walls, dense, to BS 6073 Parts 1, natural gravel or crushed stone to BS 882. Average compressive strength: 7 N/mm sq. with no block from any 10 Nr. tested having a strength less than 5.6 N/mm sq and density not less than 1990 kg/m cu. Work size 440x215x100mm. Mortar: 1:1:6 cement:lime:sand. Bond: Stretcher. Finish: Fairface. DPC's & DPM's DPC s to BS 6315 : 1984, DPC widths in all internal 100mm wall to be min 250mm to project 75mm clear of wall and capable of bonding with DPM in floor to form a waterproof joint. DPC in internal leaf of cavity wall to be 200mm and project 100mm clear of wall as for internal walls. DPC in external leaf of cavity walls to be min 110mm and located 150mm min above finished ground level. DPC in single skin external walls to be located 150mm min above finished ground level and bonded to DPM in floor. DPM's Type: P.F.F.A. Standard 6/83A:1988. 1200 gauge. Cement Plaster Cement: BS12. Sand: BS 1199, Table 1. Mix proportions: Cement:sand (1:4). Thickness: 13mm. Finish: Finish with wood or other suitably faced float to give an even, smooth, open texture. Do not apply water while working up. Do not draw excessive laitance to surface either by overworking or by use of steel trowel. Plaster Plaster: First undercoat: premixed lightweight bonding plaster: BS 1191, Part 2. Thickness: 13mm. Finish coat: Premixed lightweight finish plaster: BS 1191, Part 2. Thickness: 2mm. Finish: Trowel or float to produce a tight, matt, smooth surface with no hollows, abrupt changes of level or trowel marks. Do not use water brush and avoid excessive trowelling and over polishing. Ground Floor Cone Cills Option A Option B Option C First Floor To consist of 100mm concrete on 1200 gauge polythene drum overlapped with dpc on 25mm binding on 250mm well compacted hardcore base. Provide self levelling screed over concrete garage floor. Cills to be concrete single course on dpc. Cills to be concrete double course on dpc. 137x19mm Tongued and grooved softwood to BS 1297. Moisture content not exceeding 19% on joists at 400mm crs size as shown on drawing. All joists supported on masonry joist hangers built into walls or wallplates. Provide solid bridging between joists at positions shown on plan. Ground Floor Ceilings Option B Option C One layer of 12.5mm plasterlath with all joints taped and staggered and Bonding plaster: BS 1191, Part 2. Thickness: 8mm and finish plaster: BS 1191, Part 2. Thickness: 2mm. To provide half hour fire resistance to consist of 2 layers of 12.5mm plasterlath with all joints taped and staggered and Bonding plaster: BS 1191, Part 2. Thickness: 8mm and finish plaster: BS 1191, Part 2. Thickness: 2mm. First Floor Ceilings Option A Option B Option C Ceiling Joists left exposed One layer of 12.5mm plasterlath with all joints taped and staggered and Bonding plaster: BS 1191, Part 2. Thickness: 8mm and finish plaster: BS 1191, Part 2. Thickness: 2mm. Windows Option A Option B Option C To be uPVC white 20mm hermetically sealed double glazed units fully reinforced with Aluminium sections and fitted in accordance with manufacturer's instructions. Designs as per drawing. To be hardwood 20mm hermetically sealed double glazed units. Design as per drawing. To be Selected softwood 20mm hermetically sealed double glazed units. Design as per drawing. First Floor escape window Glazing Fire escape windows to have a clear opening at least 450mm high and 450mm wide with an unobstructed opening area of a least 0.33m2. The lower edge of the window shall not be less than 800mm and not more than 1100mm above finished floor level. All glazing to be fitted with 4mm toughened safety glass to both panes of double glazed units within 800mm of floor level. Provide 100mm opening restrictors to all windows above ground floor level. Glazing to doors and side lights within 1500mm of finished floor level to be toughened safety glass to both panes of glazed units. All glazing to achieve a WER band C or 1.6 W/m2K rating. Internal Wall Stud Walls: To consist of 100x50mm s/w vertical studs at 400mm crs with 9.5mm plasterboard and skim finish Staircase Staircase: 900mm wide overall. Risers & Gongs as shown on drawing. All risers and goings equal, max rake of stair 42. degrees. 260x2.5mm s/w treads let into 275x38mm string. Provide 50x75mm h/w handrail fixed to wall to outside side of windows. Handrail 900mm above pitch line. Balustrade to landing to have 32x32mm h/w balusters at 100mm crs to 50x75mm handrail at 900mm above landing level finished into half newel at wall. Generally: All structural timbers to be stress graded C16 (SC3) unless otherwise stated. Kln dried and pressure impregnated with preservative. Mechanical Ventilation Toilet to be provided with 'Vent Axia' mechanical ventilation unit discharging to the external air and capable of discharging at a rate of not less than 6 litres/sec connected to light switch and provided with 15 minute overrun facility. Concrete Lintels Max Span (mm) Depth (mm) No. of Bars Diam. of Bars Bearing (mm) 1200 150 Y12 2 Y12 150 1500 150 Y12 2 Y12 150 2000 225 Y12 2 Y12 225 2400 250 Y16 2 Y16 225 3000 300 Y20 2 Y20 225 For spans 1500mm and over, lintels to have Y10 bars at top with 6mm stirrups at 150mm centres Metal Lintels Cavity Walls Code Max Span Steel Thickness Reference Height CG90/100 1200 1200 1.6 140 150 1500 1500 2.0 140 150 1800 1800 2.5 140 150 2100 2100 2.5 160 150 2400 2400 2.5 180 150 3000 3000 2.5 220 150 CX90/100 3900 3.1 232 150 CXL290 4800 4.0 213 200 225mm walls Code Reference Max Span Steel Thickness Product codes refer to 'Carnie' lintels CG90/100 2700 2.0 143 Foundations Option A Option B Option C Concrete strip foundations 13:6 max, 15N/mm2 at 28 days, to bear on suitable firm undisturbed ground to satisfaction of the Local Building Control Officer, minimum depth 750mm. (See Section). Concrete strip size 600mm wide x 225mm deep Concrete strip size 450mm wide x 225mm deep Concrete strip size 750mm wide x 225mm deep Drainage Gully traps to be horizontal or vertical B.I.G.Ts in PVC with rebated tops to receive 150x150mm galvanised ms gratings. Gulleys to be haunched and bedded in concrete with 75x75mm precast concrete gully surrounds on 3 no sides and in-filled with concrete and weathered down to grating. Drains upvc wavin 100m dia drain pipes with precast 'O' ring connectors all tees and junctions to be upvc compatible with wavin system. All pipes to be laid evenly to falls shown and bedded and surrounded in maximum 150mm pea gravel. Where pipes pass through walls provide RC lintels over. Void around pipe to be filled with compressible material such as rockwool. Openings closed with slate externally either side of pipe. Long radius channel drains to be used at manholes. Wastes: All wastes to have 75mm dia deep seal traps. All wastes above floor level to be 38mm dia pvc. Both soil and storm drains to connect to local authority foul and storm water drains Garage Door Tracked up and over garage door size and type as per drawing Optional : Fitted with remote control opening system Side Door PVC external door style as per drawing fitted with 5 lever lock and 1½ pairs of hinges. All ironmongery to be brass. All glass to be safety glazing.
--	---



GaragePlans.co.uk

1 Thorndale Road North, Hillsborough Road, Carryduff, Belfast BT8 8HY
Tel: 028 9081 4106 Mobile: 077 2007 7465 info@garageplans.co.uk

www.garageplans.co.uk