

AW/148/13/BR

AW/44/14/BR

Plan 1A
Surface water Drainage Scheme
Into Soakaway

Driveway onto
Nuffield Close

11

9

Proposed dwelling

4 crate run

Blue line denotes 100m
underground pipe run at
400mm Invert level - picking
up gutter downpipes from
front and rear roofs

5 crate run

Soakaway system - Crates @ 1000 x 1000 x 300mm
each sufficient to drain 20 square metres of roof area.
9 crates in total to be set at 600mm invert level. 4
crate run - 4 metres long. 5 crate run - 5 metres long.
One crate depth (300mm) with 200mm soil above.

Lower Bognor Road



SCALE 1:200