Merry England Nursery

DAPPERS LANE

1.8m Timber close board fence between properties

Exisitng mature boundary

Exisitng mature hedgerow and 3m fence

Paved patios and side paths Grey smooth flags

Exisitng mature boundary

1.8m Timber close board fence

Jay's Roost

Crown lift trees where necessary, Prune and tidy, to highways spec for visibility splay

Resin Bound Gravel to driveways

1No. Amelanchier lamarckii 10/12

15 No. Olearia haastii

15 No. Spiraea 'Little Princess'

Sewage treatment

378 No. Vinca major

1No. Amelanchier lamarckii 10/12 with 'Root Barrier'

21No. Cistus purpureus

21 No. Hebe - in variety

1No. Sorbus a. 'Sheerwater seedling' 10/12

13 No. Hypericum hidcote

13 No. Euonymus 'E.Ga'

13 No. Lonicera pileata

1No. Betula pendula 12/14 with 'Root Barrier'

1 No. Prunus 'Kanzan' 12/14

9 No. Rosmarinus officinalis

18 No. Rosmarinus officinalis

60 No. Ligustrum vulgare

15 No. Hydrangea

1No. Sorbus a. 'Lutescens'10/12

Sinage

18 No. Hebe - in variety

24 No. Hebe - in variety

12 No. Lonicera pileata

13 No. Euonymus 'E.Go'

10 No. Hebe - in variety

1No. Sorbus a. 'Lutescens'10/12

Site entrance - existing gate replaced with new gate

15 No. Cistus purpureus

3 No. Hydrangea

TARMAC

9 No. Hebe - in variety

1No. Sorbus a. 'Sheerwater Seedling' 10/12

7 No. Hydrangea

15 No. Cistus purpureus

39 No. Hebe - in variety

Visibility splay

10 No. Rosmarinus officinalis

1No. Amelanchier lamarckii 10/12

48 No. Escallonia 'Apple Blossom'

Resin Bound Gravel to driveways

Crown lift trees where necessary, Prune and tidy, to highways spec for visibility splay

Exisitng building retained

Paved patios and side paths Grey smooth flags

Exisitng mature boundary

Exisitng mature boundary

SITE BOUNDARY

1.8m high close board fence between properties

1.8m high closeboard fence 1.2m post & rail at the front (towards the road)

Exisitng mature boundary

14

12

7

N

PLANTING SCHEDULE

QTY	SPECIES	SIZES	DENSITY
SHRUBS			
51 No.	Cistus purpureus	30/45 2/3L	3 M2
48 No.	Escallonia 'Apple Blossom'	30/45 2/3L	3 M2
13 No.	Euonymus f. 'Emerald Gaiety'	30/45 2/3L	3 M2
13 No.	Euonymus f. 'Emerald & Gold'	30/45 2/3L	3 M2
121 No.	Hebe - in variety	30/45 2/3L	3 M2
25 No.	Hydrangea	30/45 2/3L	3 M2
13 No.	Hypericum hidcote	30/45 2/3L	3 M2
37 No.	Rosmarinus officinalis	30/45 2/3L	3 M2
15 No.	Spiraea 'Little Princess'	30/45 2/3L	3 M2
15 No.	Olearia haastii	30/45 2/3L	3 M2
HEDGE			
60 No.	Ligustrum vulgare	90/120 2/3L	
TREES			
3 No.	Amelanchier lamarckii 10/12		
1 No.	Betula pendula 12/14		
1 No.	Prunus kanzan 12/14		
2 No.	Sorbus a. 'Lutescens' 10/12		
2 No.	Sorbus a. 'Sheerwater Seedling' 10/12		
GROUNDCOVER PLANTING			
378 No.	Vinca major	30/45 2/3L	3 M2

Trees container grown, or 'Rootball' planting Nov - March.
50mm mulch to new planting beds.
Read in conjunction with Horseshoe Projects Landscape Specification, & Tree and Shrub planting detail Drg. SLD.856 - 01

LANDSCAPE STRATEGY

The planting scheme will contain a reasonable amount of evergreen content for year round interest and structure, complemented by seasonal colour. See SLD.856 - 02 for details.

KEY

- Exisitng Boundary Planting
- Proposed Shrubs
- Proposed Hedge
- Proposed Trees
- Proposed Lawn
- Grouncover planting

REVISION	DESCRIPTION	DATE (DAY / MONTH / YEAR)	DRAWN	CHECKED
C	Fencing adjustments	24 07 19		
B	Planting amendments	22 07 19		
A	Planting amendments	18 07 19	JC	GF

Horseshoe Farm
Broomhill
Wimborne
Dorset
BH21 7AR
Telphone 01202 884957
www.horseshoegroup.co.uk

CLIENT: COUNTYOAK HOMES LTD

PROJECT TITLE: CRETE NURSERY, DAPPERS LANE, ANGMERING, WEST SUSSEX.

DRAWING TITLE: LANDSCAPE PLAN

DRAWING NUMBER: SLD.856 | REVISION: C

DATE: 11/07/2019 | DRAWN: JC | CHECKED: GF | SCALE: 1:200 @ A1

STATUS: