

NOTES:

1.

All dimensions are in meters unless expressed otherwise.

2.

This drawing shall be read in conjunction with the standard details.

3.

The road formation should have a minimum CBR value of 15%, where it is less, a minimum capping layer of 300mm of 6F1 material shall be provided, which should be increased as necessary to ensure a minimum CBR of 15% is achieved.

4.

For details of carriageway and footway construction refer to standard details.

5.

Cement bound materials shall not be used in the pavement construction where the curing period will cause unacceptable delays to the opening of the road.

6.

Longitudinal joints in the Wearing Course shall on the line of road marking, transverse joints shall be square between lane widths. Joints to existing carriageway shall be at a 45 to 60 degree angle.

7.

All kerbs and edgings shall comply to BS EN 1340.

8.

Edgings shall be used at the back of all footways where there is no hard features, wall etc.

KEY:

Full depth carriageway construction (WSCC S278/38/21) using Access Road construction with 350mm capping

Proposed tie in detail (WSCC S278/38/20)

Proposed full depth footway construction (WSCC S278/38/04)

Access road carriageway construction (Asphalt)

Permeable driveway construction (Resin Bound)

Topsol and seed 150mm thick

Footpath construction - paving slabs

Patio construction - paving slabs with permeable sub base

Landscaping by others

Proposed Tactile paving (WSCC S278/38/18)

Proposed half battered kerb (WSCC S278/38/02)

Proposed drop kerb (WSCC S278/38/02)

EF edging kerb laid flush

Keykerb laid flush

ACO channel

Transition kerbs

(refer to standard details for kerb types)

C

Minor amendments

RS

KBL

10/09/19

B

Revised to Client comments

RS

KBL

25/07/19

A

Revised to Client comments

RS

KBL

19/07/19

Rev

Amendment

LANMOR Consulting

Civil Engineers & Transport Planning

Thorngood House, 34 Tolworth Close, Surbiton, Surrey, KT6 7EW

Telephone: 0208 339 7899 Fax: 0208 339 7898

e-mail: info@lanmor.co.uk

www.lanmor.co.uk

Countyoak Homes Ltd

Pavement Construction

DRAWN

RS

CHECKED

KBL

APPROVED

KBL

DATE

Jul-19

DATE

Jul-19

DATE

Jul-19

SCALE

1:200

PRJ No.

191183

REV

SIZE

A1

DWG No.

191183/700/01

REV

C

ADJOINING PROPERTY