

ARCADY 6			
GUI Version: 6.2 AF			
Analysis Program: Release 5.0 (JANUARY 2009)			
(c) Copyright TRL Limited, 2004			
Adapted from ARCADY/3 which is Crown Copyright by permission of the controller of HMSO			
For sales and distribution information, program advice and maintenance, contact:			
The user of this computer program for the solution of an engineering problem is in no way relieved of their responsibility for the correctness of the solution.			

Run Information

Run with file:- I:\Projects\sprust 110601\Modelling\2011-07-21\2011 Saturday Observed+Committed.vai

At: 14:51:14 on Tuesday, July 19, 2011

Mode: **Drive On The Left**

Units: **Metric**

Arm Labelling

Arm	Full Arm Names
Arm A	Site Access (Golfers Lane)
Arm B	New Road (east)
Arm C	Mill Lane
Arm D	New Road (west)

Flow Scaling Factor

Arm	Flow Scaling Factor (%)
Arm A	100
Arm B	100
Arm C	100
Arm D	100

File Properties

Run Title	Rustington Golf and Leisure Club - 2011 Observed+Committed - Saturday Peak
Location	
Date	06/07/2011
Client	
Enumerator	JessicaShannon [TECHNICIAN-2]
Job Number	110601
Status	
Description	

Geometric Data

Data Item	Arm A	Arm B	Arm C	Arm D
Approach Road Half-Width (m)	3.50	8.00 *	7.50	7.50
Entry Width (m)	5.00	8.00	10.00	11.50
Flare Length (m)	3.00	68.00	14.00	32.00

Entry Radius (m)	10.00	20.00	25.00	35.00
Inscribed Circle Diameter (m)	56.00	56.00	56.00	56.00
Entry Angle (degrees)	28.00	26.00	22.00	26.50
Slope	0.475	0.719	0.798	0.866
Intercept (PCU/Min)	19.725	40.961	47.633	54.035

Demand Data

Demand Profiles are Synthesised using DIRECT Data

Period of interest (for Queue and Delay calculations): 11:45 to 12:45

Length of Time Period: 60 min

Length of Time Segment: 15 min

Direct Data for Demand Set: Rustington Golf and Leisure Club - 2011 Observed+Committed - Saturday Peak

Time Period	Arm	Demand Data (Veh/Min)
Segment : 1 - 11:45 to 12:00	A	1.47
	B	34.00
	C	11.10
	D	16.60
Segment : 2 - 12:00 to 12:15	A	1.60
	B	32.73
	C	15.03
	D	13.73
Segment : 3 - 12:15 to 12:30	A	1.13
	B	33.67
	C	12.10
	D	13.80
Segment : 4 - 12:30 to 12:45	A	1.07
	B	33.93
	C	10.83
	D	15.00

Turning Proportions for Demand Set: Rustington Golf and Leisure Club - 2011 Observed+Committed - Saturday Peak

Turning proportions vary over time and entry and calculated from turning count data (shaded)

Time Period	From/To	Arm A	Arm B	Arm C	Arm D
Segment : 1 - 11:45 to 12:00	Arm A	0.000	0.591	0.091	0.318
		0.0	13.0	2.0	7.0
	Arm B	0.014	0.194	0.354	0.438
		7.0	99.0	181.0	224.0
	Arm C	0.042	0.868	0.000	0.090
		7.0	145.0	0.0	15.0
	Arm D	0.032	0.908	0.060	0.000
		8.0	226.0	15.0	0.0
Segment : 2 - 12:00 to 12:15	Arm A	0.000	0.708	0.042	0.250
		0.0	17.0	1.0	6.0
	Arm B	0.012	0.163	0.376	0.449
		6.0	80.0	185.0	221.0
	Arm C	0.018	0.929	0.000	0.053
		4.0	210.0	0.0	12.0

	Arm D	0.034	0.888	0.078	0.000
		7.0	183.0	16.0	0.0
Segment : 3 - 12:15 to 12:30	Arm A	0.000	0.647	0.000	0.353
		0.0	11.0	0.0	6.0
	Arm B	0.022	0.170	0.364	0.445
		11.0	86.0	184.0	225.0
	Arm C	0.027	0.879	0.000	0.093
		5.0	160.0	0.0	17.0
	Arm D	0.029	0.908	0.063	0.000
		6.0	188.0	13.0	0.0
Segment : 4 - 12:30 to 12:45	Arm A	0.000	0.375	0.313	0.313
		0.0	6.0	5.0	5.0
	Arm B	0.008	0.206	0.375	0.412
		4.0	105.0	191.0	210.0
	Arm C	0.012	0.939	0.000	0.049
		2.0	153.0	0.0	8.0
	Arm D	0.009	0.956	0.036	0.000
		2.0	215.0	8.0	0.0

Heavy Vehicle Percentages for Demand Set: Rustington Golf and Leisure Club - 2011 Observed+Committed - Saturday Peak

Vary over entry

Time Period	From/To	Arm A	Arm B	Arm C	Arm D
11:45 to 12:00	Arm A	0.0	13.0	2.0	7.0
	Arm B	7.0	99.0	181.0	224.0
	Arm C	7.0	145.0	0.0	15.0
	Arm D	8.0	226.0	15.0	0.0

Queues and Delay:

Segment	Arm	Demand (Veh / Min)	Capacity (Veh / Min)	Demand / Capacity (RFC)	Ped Flow (Ped / Min)	Start Queue (Veh)	End Queue (Veh)	Delay (Veh.Min / Time Segment)	Geometric Delay (Veh.Min / Time Segment)	Arrival Delay (Min / Veh)
Segment : 1 - 11:45 to 12:00	A	1.47	4.36	0.337	-	0.0	0.5	6.8	-	0.339
	B	34.00	39.53	0.860	-	0.0	5.7	75.0	-	0.160
	C	11.10	29.62	0.375	-	0.0	0.6	8.7	-	0.054
	D	16.60	38.81	0.428	-	0.0	0.7	10.9	-	0.045
Segment : 2 - 12:00 to 12:15	A	1.60	4.16	0.385	-	0.5	0.6	8.7	-	0.389
	B	32.73	39.56	0.827	-	5.7	5.0	77.8	-	0.149
	C	15.03	30.64	0.490	-	0.6	1.0	14.0	-	0.064
	D	13.73	36.30	0.378	-	0.7	0.6	9.3	-	0.044
Segment : 3 - 12:15 to 12:30	A	1.13	5.49	0.206	-	0.6	0.3	4.2	-	0.232
	B	33.67	39.74	0.847	-	5.0	5.3	78.0	-	0.163
	C	12.10	29.89	0.405	-	1.0	0.7	10.5	-	0.056
	D	13.80	38.46	0.359	-	0.6	0.6	8.5	-	0.041
Segment : 4 - 12:30 to 12:45	A	1.07	4.42	0.242	-	0.3	0.3	4.5	-	0.298
	B	33.93	39.82	0.852	-	5.3	5.5	81.8	-	0.168
	C	10.83	30.10	0.360	-	0.7	0.6	8.6	-	0.052
	D	15.00	38.36	0.391	-	0.6	0.6	9.5	-	0.043