

Cover it faster!

Rex Fuller
RC Fuller Ltd

29th March 2021
Ref: UK24684 / P / MH

Dear Rex,

Thank you for your enquiry and I hope the following information is of interest.

Please note that for a marquee up for more than 28 days, planning permission may be required.

SPECIFICATION: Party structures are constructed from high quality extruded and anodised aluminium profiles, forming a modular system which can be extended or reduced as needed. All steel parts, pins and base plates are hot dip galvanised for long life. Supplied complete with stakes, bottom wall tension bars, all pins and clips for fast assembly. The white PVC covers are fire retardant to BS, DIN and M2 standards, all walls are centre laced for easy access and installation, with cord 'tie backs' for when left open. Wind-speed 80 mph.

P9m span x 21m length. Eave ht. 2.4m. Profile 110x48x3mm (4-Track)

Frame complete with white PVC roof & wall covers with straight valance

7 off 3m window wall upgrade, (panoramic window fitted into existing wall)

Flooring

Steel & aluminium modular substructure flooring system, 3m 'class A' T&G boarded surface.
or

Hoecker subfloor, Aluminium cross beams with 3m 'class A' boards & timber support battens

Doors (All doors provide 3 units of exit when calculating evacuation times)

2 off 3m aluminium / glazed double door set with panic bar fitted in centre of 3m bay

2 off 3 Part Door ramp set

Tools & equipment

Medium duty stake lifter (for removing ground anchor stakes)

10 rung Skymaster trade combo ladder

Please find our terms and conditions on the reverse of this quotation.
All prices quoted ex-works Kettering.

Kind Regards

Matthew Hunt