

Mr J Crulley

JPC Carpentry and Joinery

7 Walders Road

Rustington

West Sussex

BN16 3PF



QUOTE

26 April 2021

Mr S Holloway
Garden House
High Street
Angmering
West Sussex
BN16 4AG

Item 1:

Supply only, 12 no box frame windows.

Manufactured from hardwood linings and cills. Cheeks to be manufactured from Tricora, windows to match exactly to original windows.


Frames to accept hardwood sash windows with bars to match exactly to original windows.

Sashes to accept 12mm slim light glass, Krypton filled, low-e units, toughened where needed.

Sashes to have draft proof gasket to sides and meeting rails. Bottom rail to have Aquamac rubber seal.

Ironmongery to include weights, pullies, locking stays and lifts.

All joinery to receive, 1 no sealer, 2 no primer and 2 no top coats, all white both sides.



Page 1

Terms: If Quote is accepted a 25% Deposit is required, then 2 stage payments and balance due on completion.

Barclays
Mr J Crulley
Sort Code: 20-98-75
Account Number: 50338796

Mr J Crulley

JPC Carpentry and Joinery

7 Walders Road

Rustington

West Sussex

BN16 3PE

Item 2:

Supply only 14 no casement windows.

All joinery to be manufactured from hardwood. All frames to match original windows.

Frames to accept sash windows with bars.

Sashes to accept 12mm slim light glass, Krypton filled, low-e, double glazed units, toughened where needed.

Frames to have Aquamac rubber seals.

Ironmongery to include hinges, stay bar and handle locking. Up to £40 has been allowed for. Any choice above will be an extra cost. Cheaper will be deducted.

All joinery to accept 1 no sealer, 2 no primer and 2 no top coats, all white both sides.

Item 3:

Supply only 1 no bay window.

Joinery to be manufactured from hardwood. All frames to match original window.

Frame to accept sash windows with bars.

Sashes to accept 12mm slim light glass, Krypton filled, low-e, double glazed units, toughened where needed.

Frame to have Aquamac rubber seals.

Page 2

Terms: If Quote is accepted a 25% Deposit is required, then 2 stage payments and balance due on completion.

Mr J Crulley

JPC Carpentry and Joinery

7 Walders Road

Rustington

West Sussex

BN16 3PE

Ironmongery to include hinges, stay bar and handle locking [REDACTED] been allowed for. Any choice above will be an extra cost. Cheaper will be deducted.

All joinery to accept 1 no sealer, 2 no primer and 2 no top coats, all white both sides.

Item 4:

Supply only 3 no doors and frames.

All joinery to be manufactured from hardwood. All frames to match original doors.

Doors to accept 12mm slim light glass, Krypton filled, low-e, double glazed units, all toughened.

Frames to have Aquamac rubber seals.

Ironmongery to include hinges, five lever sash locks. Door handles to be supplied by yourselves.

All joinery to accept 1 no sealer, 2 no primer and 2 no top coats, all white both sides.

Cills to be stained with 3 no coats of Sadolins.

Item 5:

2 no doors on front elevation to be removed from site and re-sprayed to match new joinery.





FOC

Manufacturing Total


To fit all Joinery and remove all waste from site.

Page 3

Terms: If Quote is accepted a 25% Deposit is required, then 2 stage payments and balance due on completion.

Item (sizes)	Description	Qty	Unit Cost	Total Cost
	Sliding Sash Window Type: Traditional box frame sliding sash. Satin chrome fittings with Lead Weights Timber Type: Iroko - Hardwood Slimlite - 4-4-4 toughened Softcoat, Krypton/Xenon Gas - Clear (5.5mm sightline) Full Factory Finish (2 No. primer/undercoats and 2 No. Top Coats) 1514.27 kgs	12		
	Sliding Sash Window Type: Traditional box frame sliding sash. Satin chrome fittings with Lead Weights Timber Type: Iroko - Hardwood Slimlite - 4-4-4 toughened Softcoat, Krypton/Xenon Gas - Clear (5.5mm sightline) Full Factory Finish (2 No. primer/undercoats and 2 No. Top Coats) 41.06 kgs	1		
	Window Window type: Traditional flush /stormproof casement being double rebated and fully weather sealed throughout. Timber Type: Iroko - Hardwood Slimlite - 4-4-4 toughened Softcoat, Krypton/Xenon Gas - Clear (5.5mm sightline) Full Factory Finish (2 No. primer/undercoats and 2 No. Top Coats) 214.27 kgs	4		
Screen Stormproof Frame Timber Type: Iroko - Hardwood Slimlite - 4-4-4 toughened Softcoat, Krypton/Xenon Gas - Clear (5.5mm sightline) Full Factory Finish (2 No. primer/undercoats and 2 No. Top Coats) 158.92 kgs		1		
	Screen Casement Storm Casement with Friction Hinges Timber Type: Iroko - Hardwood Full Factory Finish (2 No. primer/undercoats and 2 No. Top Coats)			


Item (sizes)	Description	Qty	Unit Cost	Total Cost
Brought Forward				£0.00



Window

Window type: Traditional flush /stormproof casement being double rebated and fully weather sealed throughout.
 Timber Type: Iroko - Hardwood
 Slimlite - 4-4-4 toughened Softcoat, Krypton/Xenon Gas - Clear (5.5mm sightline)
 Full Factory Finish (2 No. primer/undercoats and 2 No. Top Coats)
 170.07 kgs

6



Window

Window type: Traditional flush /stormproof casement being double rebated and fully weather sealed throughout.
 Timber Type: Iroko - Hardwood
 Slimlite - 4-4-4 toughened Softcoat, Krypton/Xenon Gas - Clear (5.5mm sightline)
 Full Factory Finish (2 No. primer/undercoats and 2 No. Top Coats)
 179.34 kgs

2


Door & Frame

External Screen

Timber Type: Iroko - Hardwood

Full Factory Finish (2 No. primer/undercoats and 2 No. Top Coats)
 154.33 kgs

2



Door

Standard door 44mm thick
 Door(s) hang by others (no ironmongery supplied)
 Timber Type: Iroko - Hardwood
 Slimlite 4-6-4 toughened softcoat, Krypton gas - clear (8mm sightline)
 Full Factory Finish (2 No. primer/undercoats and 2 No. Top Coats)


Screen

External Screen

Timber Type: Iroko - Hardwood

Slimlite 4-6-4 toughened softcoat, Krypton gas - clear (8mm sightline)
 Full Factory Finish (2 No. primer/undercoats and 2 No. Top Coats)
 74.67 kgs

1



Door

Standard door 44mm thick
 Door(s) hang by others (no ironmongery supplied)
 Timber Type: Iroko - Hardwood
 Full Factory Finish (2 No. primer/undercoats and 2 No. Top Coats)

Total Weight 2506.92 kgs

NOTES:

Diagrams of windows, doors and frames indicate style viewed from the outside and do not reflect size. All weights shown on this document are approximate and are intended to assist in manual handling considerations.

From ARUN

Door Size Detail To Match Below

95 x 45 x STILES + HEADS
200 x 45 BTM RAIL

Box frame Sashes to match as below

