



LEGEND:

Existing Adopted Sewers

- Existing Foul
- Existing Storm
- Existing drainage to be removed

Private Storm Drainage

- S3 Type 3 inspection chamber (min1500)
- S4 Type 4 inspection chamber (min1800)
- RE Surface water rodding eye

Private Foul Drainage

- RG Road gully
- YG Yard gully
- PSA Private precast concrete ring soakaway
- Private trench soakaway
- ACO ACO channel

Highway Drainage for Adoption

- HW Highway po ring manhole
- RG Road gully
- HWSA Highway soakaway
- Highway drainage sewer

Private Foul Drainage

- Proposed foul water pipe

Foul Sewers for Adoption

- F01 Backdrop
- F3 Type 3 inspection chamber (min1500)
- F4 Type 4 inspection chamber (min1800)

Services Strip

- Tree protection zone
- Existing water main to be retained and easement

NOTES:

- For drainage construction details see drawing 2206/1900-505
- For manhole and soakaway schedules see drawing 2206/1226

NOTES:

- All dimensions to be checked on site. All details and dimensions relating to sub-construction work must be checked and agreed between the sub-contractor or supplier and the general Contractor.
- This drawing is to be read in conjunction with all relevant Architect and Engineer's drawings and specifications.
- The main Contractor is responsible for ensuring the stability of the structure whilst the works are in progress.
- Any information given regarding existing underground services is given in good faith after consultation with the relevant authority. No liability is accepted by the Consultant and the main Contractor is responsible for obtaining and checking all information and taking due care and attention whilst undertaking the works.
- All pipes, bends and junctions shall be vitrified clay to BS EN 295-1, with flexible joints and knemark certified. Alternatively all pipes and fittings can be UPVC conforming to BS EN 1401-1 and shall be laid in accordance with the manufacturers specification. If UPVC pipes are to be used then the manufacturer shall be approved by the Engineer prior to construction.
- All adoptable sewers shall be in strict accordance with the current edition of Sewers For Adoption. Unless otherwise stated adoptable sewers shall be 150mm diameter and shall be laid in a class S bedding. Where the depth to soffit is less than 1.2m under a public highway or 0.3m elsewhere the pipe shall be laid with a class Z bedding.
- All private building drainage shall be constructed in situ in accordance with BS EN 752:1998. Unless otherwise specified building drainage shall be 100mm diameter and shall be laid at a minimum gradient of 1 in 40 for foul drains and 1 in 80 for surface water drains. All building drains shall be laid in class B bedding unless otherwise specified.
- Where a pipe is within 1m of a foundation the trench shall be filled with class GEN 3 concrete up to the lowest level of the foundation. Where the trench is further than 1m from the foundation, the trench shall be filled with class GEN 3 concrete to a level below the lowest level for the foundation equal to the distance from the foundation less 150mm. In both cases the pipe shall be bedded and surrounded in 150mm thick class GEN 3 concrete.
- Where pipes, external to the structures, have a depth to soffit from ground level of less than 450mm they shall have a class GEN 3 concrete encasement (150mm thick). In all other cases the pipes shall be bedded and surrounded with 100mm thick granular material.
- In any circumstances where pipes are bedded and surrounded in concrete flexible joints should be provided. Compressible boards (fibreglass or polystyrene) shall be provided at a maximum of 8m centres (coinciding with pipe joints). The boards shall be provided to pipe diameter and to a height and width equal to the concrete cross section. A board thickness of 16mm for pipes up to 450mm nominal diameter and 30mm for pipes over 450mm nominal diameter.
- All sumps shall have rodding access plates fitted at their bases (ground floor level).
- Where existing pipes are to be abandoned they shall be dug out together with any abandoned manholes.

D: 02.09.14 :AJD: Drainage updated to suit new tree in yard
C: 06.08.14 :AJD: Drainage updated to suit 'value Engineering' comments. Site layout updated to suit current external works
B: 22.07.14 :AJD: Highway drainage design and private trench soakaway size updated to suit new soakaway rate
A: 17.06.14 :AJD: Drainage updated

REV DATE BY CHECKED BY

Issue Status

TENDER

11 Tongsten Building
George Street
Fishergate
Sussex
BN41 1RA
Tel: 01273 429424
Fax: 01273 429425
email: design@civil.co.uk

the
Civil
Engineering
Practice

CURP Barratt David Wilson Southampton

PROPERTY Swanbourne Park
Angmering

TITLE Site Layout
Proposed Drainage
Sheet 4 of 4

DESIGN A Davies DATE May 2014 PROJECT NO 22067

DRAWN A French CHECKED DATE NO 224

CHECK 1:250 @ A1 REV D