

Architectural Elements of Interest (Non-Listed and Listed)

Exterior of the House –

Elevations - the exterior walls comprise brickwork and flint, painted white.

Porch (Listed)– ornate detailing with fluted surround and fanlight.

Front Façade (Listed) – general arrangement of windows, venetian shutters, and porch.

Windows – in particular, the front elevation (east) and side elevation (south): small pane sliding sash windows with venetian shutters either side.

Roofs – there are several pitched roofs built to a traditional pitch, 47.5 degrees and steeper. The roof finishes are clay, on the and slate.

Boundary wall – the boundary wall is a combination of exposed brick pillars and flintstone, capped with rounded bricks, and is certainly a unique and attractive feature.

Outbuildings – one building, single storey, divided into two sections. Overall, this is a beautifully crafted structure. The exterior walls are a combination of flintstone framed by single horizontal brick courses set at roughly 800mm intervals. The roof structure is timber beams, not original, clad with clay craft tiles. The finished floor is probably compressed lime.

Overview: Waterton House is a Grade 2 listed property. The original building is circa 1600's but the property has since been extended and altered many times. The quality of the alterations is variable.

Listed Status – Grade 2. Formal Listing. TQ 0604 Angerming Arundel Road.

25/29 (west side)

Waterton House

GV

11

Early C19. Two storeys. Two windows and one window-space. Stuccoed. Slate roof.

Windows with venetian shutters and glazing bars intact. Porch with round-headed doorway in fluted surround with semi-circular fanlight and door of six moulded panels.

Entry Name: Waterton House.

Listing Date 20 September 1984.

Grade 11

Source:Historic England.

Source ID 1232836

English Heritage Legacy ID: 297697