

Paul Basham Associates		Page 0
Lancaster Court	189.5005 ANGMERING	
Fareham	PHASE 2 NE	
Hampshire, PO15 5TU	10% AEP +40% CC	
Date 08/10/2025	Designed by LEC	
File 251007_NE PHASE 2.MDX	Checked by COH	
Innovyze	Network 2020.1.3	

Time Area Diagram for Surface Network 5

Time (mins)	Area (ha)	Time (mins)	Area (ha)	Time (mins)	Area (ha)
0-4	0.487	4-8	1.408	8-12	0.187

Total Area Contributing (ha) = 2.082

Total Pipe Volume (m³) = 1856.722

Paul Basham Associates										Page 1		
Lancaster Court Fareham Hampshire, PO15 5TU					189.5005 ANGMERING PHASE 2 NE 10% AEP +40% CC							
Date 08/10/2025 File 251007_NE PHASE 2.MDX					Designed by LEC Checked by COH							
Innovyze					Network 2020.1.3							
STORM SEWER DESIGN by the Modified Rational Method												
Network Design Table for Surface Network 5												
« - Indicates pipe capacity < flow												
PN	Length (m)	Fall (m)	Slope (1:X)	I.Area (ha)	T.E. (mins)	Base Flow (l/s)	k (mm)	n	HYD SECT	DIA (mm)	Section Type	Auto Design
1.000	9.242	0.116	80.0	0.000	5.00	0.0	0.600		o	100	Pipe/Conduit	
1.001	6.570	0.068	96.6	0.000	0.00	0.0	0.600		o	100	Pipe/Conduit	
1.002	14.620	0.161	90.8	0.016	0.00	0.0	0.600		o	100	Pipe/Conduit	
1.003	14.599	0.151	97.0	0.014	0.00	0.0	0.600		o	150	Pipe/Conduit	
1.004	8.866	0.109	81.3	0.000	0.00	0.0	0.600		o	150	Pipe/Conduit	
1.005	27.310	0.140	195.1	0.020	0.00	0.0		0.045	3 \=/	100	1:3 Swale	
1.006	18.511	0.220	84.1	0.028	0.00	0.0		0.045	3 \=/	100	1:3 Swale	
1.007	16.872	0.330	51.1	0.000	0.00	0.0		0.045	3 \=/	100	1:3 Swale	
1.008	45.812	0.610	75.1	0.026	0.00	0.0		0.045	3 \=/	100	1:3 Swale	
1.009	23.174	0.290	79.9	0.084	0.00	0.0		0.045	3 \=/	100	1:3 Swale	
1.010	15.353	0.280	54.8	0.012	0.00	0.0		0.045	3 \=/	100	1:3 Swale	
1.011	51.987	1.270	40.9	0.014	0.00	0.0		0.045	3 \=/	100	1:3 Swale	
2.000	10.559	0.144	73.5	0.000	5.00	0.0	0.600		o	100	Pipe/Conduit	
2.001	16.124	0.620	26.0	0.000	0.00	0.0	0.600		o	100	Pipe/Conduit	
3.000	4.246	0.510	8.3	0.000	5.00	0.0	0.600		o	100	Pipe/Conduit	
3.001	16.329	0.210	77.8	0.000	0.00	0.0	0.600		o	100	Pipe/Conduit	
Network Results Table												
PN	Rain (mm/hr)	T.C. (mins)	US/IL (m)	Σ I.Area (ha)	Σ Base Flow (l/s)	Foul (l/s)	Add Flow (l/s)	Vel (m/s)	Cap (l/s)	Flow (l/s)		
1.000	50.00	5.18	40.054	0.000		0.0	0.0	0.0	0.86	6.8	0.0	
1.001	50.00	5.32	39.939	0.000		0.0	0.0	0.0	0.78	6.1	0.0	
1.002	50.00	5.62	39.870	0.016		0.0	0.0	0.0	0.81	6.3	2.9	
1.003	50.00	5.86	39.660	0.030		0.0	0.0	0.0	1.02	18.0	5.5	
1.004	50.00	5.99	39.509	0.030		0.0	0.0	0.0	1.12	19.7	5.5	
1.005	50.00	6.46	39.400	0.050		0.0	0.0	0.0	0.97	2916.4	9.1	
1.006	50.00	6.67	39.260	0.079		0.0	0.0	0.0	1.48	4440.6	14.2	
1.007	50.00	6.82	39.040	0.079		0.0	0.0	0.0	1.89	5696.6	14.2	
1.008	50.00	7.31	38.710	0.104		0.0	0.0	0.0	1.56	4700.2	18.9	
1.009	50.00	7.56	38.100	0.188		0.0	0.0	0.0	1.51	4556.6	34.0	
1.010	50.00	7.70	37.810	0.201		0.0	0.0	0.0	1.83	5500.8	36.2	
1.011	50.00	8.11	37.530	0.214		0.0	0.0	0.0	2.12	6366.5	38.7	
2.000	50.00	5.20	38.134	0.000		0.0	0.0	0.0	0.90	7.1	0.0	
2.001	50.00	5.37	37.990	0.000		0.0	0.0	0.0	1.52	11.9	0.0	
3.000	50.00	5.03	38.090	0.000		0.0	0.0	0.0	2.69	21.2	0.0	
3.001	50.00	5.34	37.580	0.000		0.0	0.0	0.0	0.87	6.9	0.0	
©1982-2020 Innovyze												

Paul Basham Associates										Page 2		
Lancaster Court Fareham Hampshire, PO15 5TU					189.5005 ANGMERING PHASE 2 NE 10% AEP +40% CC							
Date 08/10/2025					Designed by LEC							
File 251007_NE PHASE 2.MDX					Checked by COH							
Innovyze					Network 2020.1.3							
STORM SEWER DESIGN by the Modified Rational Method												
Network Design Table for Surface Network 5												
PN	Length (m)	Fall (m)	Slope (1:X)	I.Area (ha)	T.E. (mins)	Base Flow	k (l/s)	n	HYD SECT	DIA (mm)	Section Type	Auto Design
2.002	18.089	0.934	19.4	0.000	0.00	0.0	0.600		o	150	Pipe/Conduit	
4.000	11.304	0.141	80.0	0.002	5.00	0.0	0.600		o	100	Pipe/Conduit	
5.000	6.008	0.075	80.0	0.000	5.00	0.0	0.600		o	100	Pipe/Conduit	
4.001	14.028	0.140	100.0	0.007	0.00	0.0	0.600		o	100	Pipe/Conduit	
2.003	8.716	0.051	170.0	0.029	0.00	0.0	0.600		o	225	Pipe/Conduit	
1.012	32.342	1.340	24.1	0.024	0.00	0.0		0.045	3 \=/	100	1:3 Swale	
6.000	11.528	0.590	19.5	0.000	5.00	0.0	0.600		o	100	Pipe/Conduit	
6.001	15.089	0.130	116.1	0.010	0.00	0.0	0.600		o	100	Pipe/Conduit	
7.000	17.115	0.837	20.5	0.009	5.00	0.0	0.600		o	100	Pipe/Conduit	
6.002	11.187	0.170	65.8	0.000	0.00	0.0	0.600		o	150	Pipe/Conduit	
6.003	11.853	0.100	118.5	0.000	0.00	0.0	0.600		o	150	Pipe/Conduit	
8.000	11.467	0.143	80.3	0.018	5.00	0.0	0.600		o	100	Pipe/Conduit	
Network Results Table												
PN	Rain (mm/hr)	T.C. (mins)	US/IL (m)	Σ I.Area (ha)	Σ Base Flow	Foul (l/s)	Add Flow (l/s)	Vel (m/s)	Cap (l/s)	Flow (l/s)		
2.002	50.00	5.50	37.320	0.000	0.0	0.0	0.0	2.30	40.6	0.0		
4.000	50.00	5.22	36.718	0.002	0.0	0.0	0.0	0.86	6.8	0.4		
5.000	50.00	5.12	36.845	0.000	0.0	0.0	0.0	0.86	6.8	0.0		
4.001	50.00	5.52	36.577	0.009	0.0	0.0	0.0	0.77	6.0	1.7		
2.003	50.00	5.67	36.311	0.038	0.0	0.0	0.0	1.00	39.8	6.9		
1.012	50.00	8.31	36.260	0.276	0.0	0.0	0.0	2.72	7878.3	49.9		
6.000	50.00	5.11	36.300	0.000	0.0	0.0	0.0	1.76	13.8	0.0		
6.001	50.00	5.46	35.710	0.010	0.0	0.0	0.0	0.71	5.6	1.9		
7.000	50.00	5.17	36.417	0.009	0.0	0.0	0.0	1.72	13.5	1.7		
6.002	50.00	5.61	35.530	0.020	0.0	0.0	0.0	1.24	21.9	3.6		
6.003	50.00	5.83	35.360	0.020	0.0	0.0	0.0	0.92	16.3	3.6		
8.000	50.00	5.22	35.176	0.018	0.0	0.0	0.0	0.86	6.8	3.3		
©1982-2020 Innovyze												

Paul Basham Associates

Lancaster Court
Fareham
Hampshire, PO15 5TU

Date 08/10/2025
File 251007_NE PHASE 2.MDX

Innovyze

189.5005 ANGMERING
PHASE 2 NE
10% AEP +40% CC

Designed by LEC
Checked by COH

Network 2020.1.3

Page 3



STORM SEWER DESIGN by the Modified Rational Method

Network Design Table for Surface Network 5

PN	Length (m)	Fall (m)	Slope (1:X)	I.Area (ha)	T.E. (mins)	Base Flow (l/s)	k (mm)	n	HYD SECT	DIA (mm)	Section Type	Auto Design
6.004	9.840	0.099	99.5	0.000	0.00	0.0	0.600		o	150	Pipe/Conduit	
6.005	1.441	0.014	100.0	0.000	0.00	0.0	0.600		o	100	Pipe/Conduit	
1.013	13.059	0.570	22.9	0.020	0.00	0.0		0.045	3 \=/	100	1:3 Swale	
1.014	41.940	1.720	24.4	0.018	0.00	0.0		0.045	3 \=/	100	1:3 Swale	
1.015	6.165	0.230	26.8	0.000	0.00	0.0		0.045	3 \=/	100	1:3 Swale	
9.000	12.602	0.446	28.2	0.000	5.00	0.0	0.600		o	100	Pipe/Conduit	
9.001	6.771	0.300	22.6	0.000	0.00	0.0	0.600		o	150	Pipe/Conduit	
10.000	14.026	0.280	50.1	0.000	5.00	0.0	0.600		o	100	Pipe/Conduit	
9.002	18.872	0.463	40.8	0.000	0.00	0.0	0.600		o	150	Pipe/Conduit	
11.000	4.473	0.190	23.5	0.000	5.00	0.0	0.600		o	100	Pipe/Conduit	
11.001	12.736	0.473	26.9	0.002	0.00	0.0	0.600		o	100	Pipe/Conduit	
9.003	13.462	0.132	101.8	0.032	0.00	0.0	0.600		o	225	Pipe/Conduit	
1.016	33.597	1.350	24.9	0.021	0.00	0.0		0.045	3 \=/	100	1:3 Swale	

Network Results Table

PN	Rain (mm/hr)	T.C. (mins)	US/IL (m)	Σ I.Area (ha)	Σ Base Flow (l/s)	Foul (l/s)	Add Flow (l/s)	Vel (m/s)	Cap (l/s)	Flow (l/s)
6.004	50.00	5.99	35.033	0.038	0.0	0.0	0.0	1.01	17.8	6.8
6.005	50.00	6.02	34.934	0.038	0.0	0.0	0.0	0.77	6.0«	6.8
1.013	50.00	8.39	34.920	0.334	0.0	0.0	0.0	2.69	6954.7	60.4
1.014	50.00	8.66	34.350	0.353	0.0	0.0	0.0	2.62	6838.6	63.7
1.015	50.00	8.70	32.630	0.353	0.0	0.0	0.0	2.61	7867.6	63.7
9.000	50.00	5.14	33.866	0.000	0.0	0.0	0.0	1.46	11.4	0.0
9.001	50.00	5.20	33.370	0.000	0.0	0.0	0.0	2.13	37.6	0.0
10.000	50.00	5.21	33.350	0.000	0.0	0.0	0.0	1.09	8.6	0.0
9.002	50.00	5.41	33.070	0.000	0.0	0.0	0.0	1.58	27.9	0.0
11.000	50.00	5.05	33.320	0.000	0.0	0.0	0.0	1.60	12.5	0.0
11.001	50.00	5.19	33.130	0.002	0.0	0.0	0.0	1.49	11.7	0.4
9.003	50.00	5.59	32.532	0.034	0.0	0.0	0.0	1.30	51.5	6.2
1.016	50.00	8.91	32.400	0.408	0.0	0.0	0.0	2.65	7405.7	73.6

©1982-2020 Innovyze

Paul Basham Associates

Lancaster Court
Fareham
Hampshire, PO15 5TU

Date 08/10/2025
File 251007_NE PHASE 2.MDX

189.5005 ANGMERING
PHASE 2 NE
10% AEP +40% CC

Designed by LEC
Checked by COH

Page 4



Innovyze

Network 2020.1.3

STORM SEWER DESIGN by the Modified Rational Method

Network Design Table for Surface Network 5

PN	Length (m)	Fall (m)	Slope (1:X)	I.Area (ha)	T.E. (mins)	Base Flow (l/s)	k (mm)	n	HYD SECT	DIA (mm)	Section Type	Auto Design
12.000	13.238	0.280	47.3	0.000	5.00	0.0	0.600		o	100	Pipe/Conduit	
12.001	18.154	0.215	84.4	0.016	0.00	0.0	0.600		o	100	Pipe/Conduit	
12.002	16.097	0.700	23.0	0.000	0.00	0.0	0.600		o	150	Pipe/Conduit	
13.000	13.405	0.467	28.7	0.000	5.00	0.0	0.600		o	100	Pipe/Conduit	
13.001	16.307	0.370	44.1	0.004	0.00	0.0	0.600		o	100	Pipe/Conduit	
12.003	9.220	0.130	70.9	0.000	0.00	0.0	0.600		o	225	Pipe/Conduit	
1.017	4.083	0.170	24.0	0.000	0.00	0.0		0.045	3 \=/	100	1:3 Swale	
1.018	27.215	0.740	36.8	0.030	0.00	0.0		0.045	3 \=/	100	1:3 Swale	
1.019	10.151	0.280	36.3	0.000	0.00	0.0		0.045	3 \=/	100	1:3 Swale	
1.020	22.673	0.860	26.4	0.000	0.00	0.0		0.045	3 \=/	100	1:3 Swale	
14.000	10.212	0.003	3078.9	0.004	5.00	0.0	0.600		o	100	Pipe/Conduit	
14.001	9.041	1.110	8.1	0.009	0.00	0.0	0.600		o	100	Pipe/Conduit	
15.000	11.597	0.706	16.4	0.000	5.00	0.0	0.600		o	100	Pipe/Conduit	
14.002	3.415	0.655	5.2	0.000	0.00	0.0	0.600		o	100	Pipe/Conduit	

Network Results Table

PN	Rain (mm/hr)	T.C. (mins)	US/IL (m)	Σ I.Area (ha)	Σ Base Flow (l/s)	Foul (l/s)	Add Flow (l/s)	Vel (m/s)	Cap (l/s)	Flow (l/s)
12.000	50.00	5.20	32.500	0.000	0.0	0.0	0.0	1.12	8.8	0.0
12.001	50.00	5.56	32.220	0.016	0.0	0.0	0.0	0.84	6.6	2.9
12.002	50.00	5.68	31.955	0.016	0.0	0.0	0.0	2.11	37.3	2.9
13.000	50.00	5.15	32.017	0.000	0.0	0.0	0.0	1.45	11.4	0.0
13.001	50.00	5.39	31.550	0.004	0.0	0.0	0.0	1.16	9.1	0.8
12.003	50.00	5.78	31.180	0.020	0.0	0.0	0.0	1.55	61.8	3.7
1.017	50.00	8.93	31.050	0.428	0.0	0.0	0.0	2.76	8289.4	77.3
1.018	50.00	9.21	30.880	0.458	0.0	0.0	0.0	1.67	2090.4	82.7
1.019	50.00	9.28	30.140	0.458	0.0	0.0	0.0	2.25	6765.0	82.7
1.020	50.00	9.42	29.860	0.458	0.0	0.0	0.0	2.64	7933.0	82.7
14.000	50.00	6.31	32.123	0.004	0.0	0.0	0.0	0.13	1.0	0.7
14.001	50.00	6.36	32.120	0.012	0.0	0.0	0.0	2.73	21.4	2.2
15.000	50.00	5.10	31.716	0.000	0.0	0.0	0.0	1.91	15.0	0.0
14.002	50.00	6.38	31.010	0.012	0.0	0.0	0.0	3.41	26.8	2.2

©1982-2020 Innovyze

Paul Basham Associates										Page 5		
Lancaster Court Fareham Hampshire, PO15 5TU					189.5005 ANGMERING PHASE 2 NE 10% AEP +40% CC							
Date 08/10/2025 File 251007_NE PHASE 2.MDX					Designed by LEC Checked by COH							
Innovyze					Network 2020.1.3							
STORM SEWER DESIGN by the Modified Rational Method												
Network Design Table for Surface Network 5												
PN	Length (m)	Fall (m)	Slope (1:X)	I.Area (ha)	T.E. (mins)	Base Flow (l/s)	k (mm)	n	HYD SECT	DIA (mm)	Section Type	Auto Design
14.003	35.477	1.022	34.7	0.032	0.00	0.0	0.600		o	300	Pipe/Conduit	
16.000	7.565	0.661	11.4	0.000	5.00	0.0	0.600		o	100	Pipe/Conduit	
16.001	12.716	0.439	28.9	0.000	0.00	0.0	0.600		o	100	Pipe/Conduit	
17.000	15.621	0.400	39.1	0.000	5.00	0.0	0.600		o	100	Pipe/Conduit	
16.002	9.637	0.260	37.1	0.004	0.00	0.0	0.600		o	150	Pipe/Conduit	
16.003	9.340	0.450	20.8	0.000	0.00	0.0	0.600		o	150	Pipe/Conduit	
16.004	8.094	0.348	23.2	0.000	0.00	0.0	0.600		o	150	Pipe/Conduit	
18.000	11.055	0.184	60.0	0.000	5.00	0.0	0.600		o	100	Pipe/Conduit	
18.001	10.845	0.181	60.0	0.000	0.00	0.0	0.600		o	100	Pipe/Conduit	
18.002	7.087	0.123	57.6	0.000	0.00	0.0	0.600		o	100	Pipe/Conduit	
14.004	10.338	0.133	77.8	0.075	0.00	0.0	0.600		o	300	Pipe/Conduit	
1.021	16.473	0.230	71.6	0.000	0.00	0.0		0.045	3 \=/	100	1:3 Swale	
1.022	11.943	0.100	119.4	0.000	0.00	0.0		0.045	3 \=/	100	1:3 Swale	
1.023	27.876	0.470	59.3	0.026	0.00	0.0		0.045	3 \=/	100	1:3 Swale	
Network Results Table												
PN	Rain (mm/hr)	T.C. (mins)	US/IL (m)	Σ I.Area (ha)	Σ Base Flow (l/s)	Foul (l/s)	Add Flow (l/s)	Vel (m/s)	Cap (l/s)	Flow (l/s)		
14.003	50.00	6.60	30.155	0.044	0.0	0.0	0.0	2.68	189.3	8.0		
16.000	50.00	5.05	31.441	0.000	0.0	0.0	0.0	2.30	18.0	0.0		
16.001	50.00	5.20	30.779	0.000	0.0	0.0	0.0	1.44	11.3	0.0		
17.000	50.00	5.21	30.740	0.000	0.0	0.0	0.0	1.24	9.7	0.0		
16.002	50.00	5.31	30.340	0.004	0.0	0.0	0.0	1.66	29.3	0.7		
16.003	50.00	5.38	30.080	0.004	0.0	0.0	0.0	2.22	39.2	0.7		
16.004	50.00	5.44	29.630	0.004	0.0	0.0	0.0	2.10	37.1	0.7		
18.000	50.00	5.18	29.746	0.000	0.0	0.0	0.0	1.00	7.8	0.0		
18.001	50.00	5.37	29.562	0.000	0.0	0.0	0.0	1.00	7.8	0.0		
18.002	50.00	5.48	29.381	0.000	0.0	0.0	0.0	1.02	8.0	0.0		
14.004	50.00	6.69	29.133	0.124	0.0	0.0	0.0	1.78	126.1	22.3		
1.021	50.00	9.60	29.000	0.582	0.0	0.0	0.0	1.60	4813.1	105.0		
1.022	50.00	9.76	28.770	0.582	0.0	0.0	0.0	1.24	3727.2	105.0		
1.023	50.00	10.02	28.670	0.608	0.0	0.0	0.0	1.75	5205.0	109.8		
©1982-2020 Innovyze												

Paul Basham Associates										Page 6		
Lancaster Court Fareham Hampshire, PO15 5TU					189.5005 ANGMERING PHASE 2 NE 10% AEP +40% CC							
Date 08/10/2025 File 251007_NE PHASE 2.MDX					Designed by LEC Checked by COH							
Innovyze					Network 2020.1.3							
STORM SEWER DESIGN by the Modified Rational Method												
Network Design Table for Surface Network 5												
PN	Length (m)	Fall (m)	Slope (1:X)	I.Area (ha)	T.E. (mins)	Base Flow (l/s)	k (mm)	n	HYD SECT	DIA (mm)	Section Type	Auto Design
19.000	10.895	0.109	100.0	0.000	5.00	0.0	0.600		o	100	Pipe/Conduit	
19.001	5.821	0.058	100.0	0.000	0.00	0.0	0.600		o	100	Pipe/Conduit	
19.002	10.950	0.109	100.0	0.000	0.00	0.0	0.600		o	150	Pipe/Conduit	
20.000	9.088	0.126	72.4	0.005	5.00	0.0	0.600		o	100	Pipe/Conduit	
20.001	10.159	0.148	68.7	0.000	0.00	0.0	0.600		o	100	Pipe/Conduit	
21.000	5.833	0.655	8.9	0.005	5.00	0.0	0.600		o	100	Pipe/Conduit	
20.002	6.134	0.452	13.6	0.000	0.00	0.0	0.600		o	150	Pipe/Conduit	
22.000	9.002	0.728	12.4	0.000	5.00	0.0	0.600		o	100	Pipe/Conduit	
19.003	12.591	0.097	130.0	0.042	0.00	0.0	0.600		o	225	Pipe/Conduit	
23.000	15.021	0.150	100.0	0.000	5.00	0.0	0.600		o	100	Pipe/Conduit	
23.001	16.690	0.167	100.0	0.016	0.00	0.0	0.600		o	150	Pipe/Conduit	
24.000	9.618	0.133	72.2	0.009	5.00	0.0	0.600		o	100	Pipe/Conduit	
24.001	8.141	0.231	35.2	0.000	0.00	0.0	0.600		o	100	Pipe/Conduit	
Network Results Table												
PN	Rain (mm/hr)	T.C. (mins)	US/IL (m)	E I.Area (ha)	Σ Base Flow (l/s)	Foul (l/s)	Add Flow (l/s)	Vel (m/s)	Cap (l/s)	Flow (l/s)		
19.000	50.00	5.24	34.260	0.000	0.0	0.0	0.0	0.77	6.0	0.0		
19.001	50.00	5.36	34.151	0.000	0.0	0.0	0.0	0.77	6.0	0.0		
19.002	50.00	5.54	34.043	0.000	0.0	0.0	0.0	1.00	17.8	0.0		
20.000	50.00	5.17	34.659	0.005	0.0	0.0	0.0	0.91	7.1	0.9		
20.001	50.00	5.35	34.534	0.005	0.0	0.0	0.0	0.93	7.3	0.9		
21.000	50.00	5.04	35.041	0.005	0.0	0.0	0.0	2.61	20.5	0.8		
20.002	50.00	5.39	34.386	0.009	0.0	0.0	0.0	2.75	48.6	1.7		
22.000	50.00	5.07	34.863	0.000	0.0	0.0	0.0	2.21	17.4	0.0		
19.003	50.00	5.73	33.809	0.052	0.0	0.0	0.0	1.15	45.5	9.3		
23.000	50.00	5.33	34.214	0.000	0.0	0.0	0.0	0.77	6.0	0.0		
23.001	50.00	5.60	34.014	0.016	0.0	0.0	0.0	1.00	17.8	2.9		
24.000	50.00	5.18	34.364	0.009	0.0	0.0	0.0	0.91	7.1	1.7		
24.001	50.00	5.28	34.231	0.009	0.0	0.0	0.0	1.30	10.2	1.7		
©1982-2020 Innovyze												

Paul Basham Associates											Page 7	
Lancaster Court Fareham Hampshire, PO15 5TU					189.5005 ANGMERING PHASE 2 NE 10% AEP +40% CC							
Date 08/10/2025 File 251007_NE PHASE 2.MDX					Designed by LEC Checked by COH							
Innovyze					Network 2020.1.3							
<u>STORM SEWER DESIGN by the Modified Rational Method</u>												
<u>Network Design Table for Surface Network 5</u>												
PN	Length (m)	Fall (m)	Slope (1:X)	I.Area (ha)	T.E. (mins)	Base Flow (l/s)	k (mm)	n	HYD SECT	DIA (mm)	Section Type	Auto Design
23.002	8.320	0.049	170.0	0.019	0.00	0.0	0.600		o	225	Pipe/Conduit	
25.000	4.022	0.999	4.0	0.000	5.00	0.0	0.600		o	100	Pipe/Conduit	
19.004	37.339	0.115	325.0	0.046	0.00	0.0	0.600		o	450	Pipe/Conduit	
26.000	4.944	0.062	80.0	0.002	5.00	0.0	0.600		o	100	Pipe/Conduit	
26.001	14.912	0.239	62.4	0.007	0.00	0.0	0.600		o	100	Pipe/Conduit	
27.000	10.657	1.250	8.5	0.000	5.00	0.0	0.600		o	100	Pipe/Conduit	
26.002	8.262	0.210	39.3	0.004	0.00	0.0	0.600		o	100	Pipe/Conduit	
26.003	4.041	0.371	10.9	0.000	0.00	0.0	0.600		o	150	Pipe/Conduit	
28.000	19.545	1.257	15.5	0.014	5.00	0.0	0.600		o	150	Pipe/Conduit	
26.004	28.756	3.766	7.6	0.047	0.00	0.0	0.600		o	150	Pipe/Conduit	
29.000	9.547	0.143	66.6	0.002	5.00	0.0	0.600		o	100	Pipe/Conduit	
29.001	8.863	0.665	13.3	0.003	0.00	0.0	0.600		o	100	Pipe/Conduit	
29.002	30.254	2.832	10.7	0.060	0.00	0.0	0.600		o	150	Pipe/Conduit	
<u>Network Results Table</u>												
PN	Rain (mm/hr)	T.C. (mins)	US/IL (m)	E I.Area (ha)	E Base Flow (l/s)	Foul (l/s)	Add Flow (l/s)	Vel (m/s)	Cap (l/s)	Flow (l/s)		
23.002	50.00	5.74	33.772	0.045		0.0	0.0	0.0	1.00	39.8	8.0	
25.000	50.00	5.02	34.836	0.000		0.0	0.0	0.0	3.88	30.5	0.0	
19.004	50.00	6.30	33.498	0.142		0.0	0.0	0.0	1.12	178.5	25.7	
26.000	50.00	5.10	38.331	0.002		0.0	0.0	0.0	0.86	6.8	0.4	
26.001	50.00	5.35	38.269	0.010		0.0	0.0	0.0	0.98	7.7	1.8	
27.000	50.00	5.07	39.280	0.000		0.0	0.0	0.0	2.66	20.9	0.0	
26.002	50.00	5.46	38.030	0.014		0.0	0.0	0.0	1.23	9.7	2.5	
26.003	50.00	5.48	37.820	0.014		0.0	0.0	0.0	3.07	54.2	2.5	
28.000	50.00	5.13	38.706	0.014		0.0	0.0	0.0	2.57	45.4	2.5	
26.004	50.00	5.61	37.449	0.075		0.0	0.0	0.0	3.67	64.8	13.5	
29.000	50.00	5.17	37.373	0.002		0.0	0.0	0.0	0.94	7.4	0.4	
29.001	50.00	5.24	37.230	0.005		0.0	0.0	0.0	2.13	16.7	0.9	
29.002	50.00	5.40	36.515	0.065		0.0	0.0	0.0	3.10	54.8	11.7	
©1982-2020 Innovyze												

Paul Basham Associates

Page 8

Lancaster Court
Fareham
Hampshire, PO15 5TU

Date 08/10/2025
File 251007_NE PHASE 2.MDX

Innovyze

189.5005 ANGMERING
PHASE 2 NE
10% AEP +40% CC

Designed by LEC
Checked by COH

Network 2020.1.3

Micro Drainage

STORM SEWER DESIGN by the Modified Rational Method

Network Design Table for Surface Network 5

PN	Length (m)	Fall (m)	Slope (1:X)	I.Area (ha)	T.E. (mins)	Base Flow (l/s)	k (mm)	n	HYD SECT	DIA (mm)	Section Type	Auto Design
19.005	48.996	0.124	394.5	0.120	0.00	0.0	0.600		o	450	Pipe/Conduit	
30.000	6.326	0.079	80.0	0.000	5.00	0.0	0.600		o	100	Pipe/Conduit	
30.001	6.482	0.081	80.0	0.000	0.00	0.0	0.600		o	100	Pipe/Conduit	
30.002	5.090	0.064	80.0	0.000	0.00	0.0	0.600		o	100	Pipe/Conduit	
30.003	6.237	0.116	53.6	0.000	0.00	0.0	0.600		o	100	Pipe/Conduit	
31.000	10.385	0.130	80.0	0.000	5.00	0.0	0.600		o	100	Pipe/Conduit	
31.001	8.261	0.103	80.0	0.000	0.00	0.0	0.600		o	100	Pipe/Conduit	
30.004	9.306	2.451	3.8	0.000	0.00	0.0	0.600		o	150	Pipe/Conduit	
32.000	10.022	0.127	78.9	0.000	5.00	0.0	0.600		o	100	Pipe/Conduit	
32.001	8.061	0.663	12.2	0.004	0.00	0.0	0.600		o	100	Pipe/Conduit	
33.000	10.433	0.165	63.3	0.000	5.00	0.0	0.600		o	100	Pipe/Conduit	
32.002	12.826	1.748	7.3	0.000	0.00	0.0	0.600		o	150	Pipe/Conduit	
19.006	9.869	0.024	409.4	0.018	0.00	0.0	0.600		o	450	Pipe/Conduit	

Network Results Table

PN	Rain (mm/hr)	T.C. (mins)	US/IL (m)	E I.Area (ha)	E Base Flow (l/s)	Foul (l/s)	Add Flow (l/s)	Vel (m/s)	Cap (l/s)	Flow (l/s)
19.005	50.00	7.10	33.383	0.402	0.0	0.0	0.0	1.02	161.8	72.5
30.000	50.00	5.12	36.400	0.000	0.0	0.0	0.0	0.86	6.8	0.0
30.001	50.00	5.25	36.321	0.000	0.0	0.0	0.0	0.86	6.8	0.0
30.002	50.00	5.35	36.240	0.000	0.0	0.0	0.0	0.86	6.8	0.0
30.003	50.00	5.45	36.176	0.000	0.0	0.0	0.0	1.05	8.3	0.0
31.000	50.00	5.20	36.293	0.000	0.0	0.0	0.0	0.86	6.8	0.0
31.001	50.00	5.36	36.163	0.000	0.0	0.0	0.0	0.86	6.8	0.0
30.004	50.00	5.47	36.010	0.000	0.0	0.0	0.0	5.21	92.1	0.0
32.000	50.00	5.19	36.147	0.000	0.0	0.0	0.0	0.87	6.8	0.0
32.001	50.00	5.25	36.020	0.004	0.0	0.0	0.0	2.23	17.5	0.8
33.000	50.00	5.18	35.522	0.000	0.0	0.0	0.0	0.97	7.6	0.0
32.002	50.00	5.31	35.307	0.004	0.0	0.0	0.0	3.74	66.2	0.8
19.006	50.00	7.26	33.259	0.424	0.0	0.0	0.0	1.00	158.8	76.5

©1982-2020 Innovyze

Paul Basham Associates

Lancaster Court
Fareham
Hampshire, PO15 5TU

Date 08/10/2025
File 251007_NE PHASE 2.MDX

Innovyze

189.5005 ANGMERING
PHASE 2 NE
10% AEP +40% CC

Designed by LEC
Checked by COH

Network 2020.1.3

Page 9



STORM SEWER DESIGN by the Modified Rational Method

Network Design Table for Surface Network 5

PN	Length (m)	Fall (m)	Slope (1:X)	I.Area (ha)	T.E. (mins)	Base Flow (l/s)	k (mm)	n	HYD SECT	DIA (mm)	Section Type	Auto Design
34.000	13.202	0.165	80.2	0.014	5.00	0.0	0.600		o	100	Pipe/Conduit	
34.001	6.725	0.084	79.8	0.004	0.00	0.0	0.600		o	225	Pipe/Conduit	
35.000	11.923	0.228	52.2	0.006	5.00	0.0	0.600		o	100	Pipe/Conduit	
34.002	29.417	0.986	29.8	0.030	0.00	0.0	0.600		o	225	Pipe/Conduit	
36.000	11.941	0.613	19.5	0.000	5.00	0.0	0.600		o	100	Pipe/Conduit	
34.003	4.873	0.160	30.5	0.000	0.00	0.0	0.600		o	225	Pipe/Conduit	
34.004	19.071	0.319	59.7	0.012	0.00	0.0	0.600		o	300	Pipe/Conduit	
37.000	13.924	0.174	80.0	0.000	5.00	0.0	0.600		o	100	Pipe/Conduit	
37.001	21.975	0.376	58.4	0.007	0.00	0.0	0.600		o	100	Pipe/Conduit	
38.000	12.670	0.170	74.5	0.000	5.00	0.0	0.600		o	100	Pipe/Conduit	
37.002	20.755	0.624	33.3	0.012	0.00	0.0	0.600		o	150	Pipe/Conduit	
34.005	18.535	0.976	19.0	0.000	0.00	0.0	0.600		o	225	Pipe/Conduit	

Network Results Table

PN	Rain (mm/hr)	T.C. (mins)	US/IL (m)	E I.Area (ha)	E Base Flow (l/s)	Foul (l/s)	Add Flow (l/s)	Vel (m/s)	Cap (l/s)	Flow (l/s)
34.000	50.00	5.26	39.610	0.014	0.0	0.0	0.0	0.86	6.8	2.6
34.001	50.00	5.33	39.320	0.019	0.0	0.0	0.0	1.46	58.2	3.4
35.000	50.00	5.19	39.589	0.006	0.0	0.0	0.0	1.07	8.4	1.0
34.002	50.00	5.54	39.236	0.054	0.0	0.0	0.0	2.40	95.6	9.8
36.000	50.00	5.11	38.988	0.000	0.0	0.0	0.0	1.76	13.8	0.0
34.003	50.00	5.57	38.250	0.054	0.0	0.0	0.0	2.38	94.6	9.8
34.004	50.00	5.73	38.090	0.067	0.0	0.0	0.0	2.04	144.0	12.0
37.000	50.00	5.27	39.070	0.000	0.0	0.0	0.0	0.86	6.8	0.0
37.001	50.00	5.63	38.896	0.007	0.0	0.0	0.0	1.01	7.9	1.2
38.000	50.00	5.24	38.690	0.000	0.0	0.0	0.0	0.89	7.0	0.0
37.002	50.00	5.83	38.470	0.019	0.0	0.0	0.0	1.75	31.0	3.4
34.005	50.00	5.93	37.771	0.086	0.0	0.0	0.0	3.02	119.9	15.5

©1982-2020 Innovyze

Paul Basham Associates

Page 10

Lancaster Court
Fareham
Hampshire, PO15 5TU

Date 08/10/2025
File 251007_NE PHASE 2.MDX

189.5005 ANGMERING
PHASE 2 NE
10% AEP +40% CC

Designed by LEC
Checked by COH

Micro Drainage

InnovyzeNetwork 2020.1.3

STORM SEWER DESIGN by the Modified Rational Method

Network Design Table for Surface Network 5

PN	Length (m)	Fall (m)	Slope (1:X)	I.Area (ha)	T.E. (mins)	Base Flow (l/s)	k (mm)	n	HYD SECT	DIA (mm)	Section Type	Auto Design
39.000	9.338	0.660	14.1	0.000	5.00	0.0	0.600		o	150	Pipe/Conduit	
40.000	7.148	0.895	8.0	0.000	5.00	0.0	0.600		o	225	Pipe/Conduit	
34.006	30.842	1.217	25.3	0.047	0.00	0.0	0.600		o	300	Pipe/Conduit	
41.000	5.343	0.162	32.9	0.000	5.00	0.0	0.600		o	100	Pipe/Conduit	
41.001	12.219	0.159	76.8	0.002	0.00	0.0	0.600		o	100	Pipe/Conduit	
41.002	9.993	1.445	6.9	0.000	0.00	0.0	0.600		o	150	Pipe/Conduit	
42.000	2.570	0.327	7.9	0.000	5.00	0.0	0.600		o	100	Pipe/Conduit	
34.007	11.227	1.952	5.8	0.023	0.00	0.0	0.600		o	300	Pipe/Conduit	
19.007	11.333	0.028	405.0	0.007	0.00	0.0	0.600		o	450	Pipe/Conduit	
43.000	7.066	0.111	63.5	0.000	5.00	0.0	0.600		o	100	Pipe/Conduit	
43.001	2.649	0.040	66.2	0.000	0.00	0.0	0.600		o	100	Pipe/Conduit	
43.002	12.205	0.153	80.0	0.000	0.00	0.0	0.600		o	100	Pipe/Conduit	
43.003	3.775	0.047	79.6	0.000	0.00	0.0	0.600		o	100	Pipe/Conduit	

Network Results Table

PN	Rain (mm/hr)	T.C. (mins)	US/IL (m)	Σ I.Area (ha)	Σ Base Flow (l/s)	Foul (l/s)	Add Flow (l/s)	Vel (m/s)	Cap (l/s)	Flow (l/s)
39.000	50.00	5.06	37.530	0.000	0.0	0.0	0.0	2.69	47.6	0.0
40.000	50.00	5.03	37.690	0.000	0.0	0.0	0.0	4.66	185.3	0.0
34.006	50.00	6.10	36.720	0.133	0.0	0.0	0.0	3.14	221.6	23.9
41.000	50.00	5.07	37.420	0.000	0.0	0.0	0.0	1.35	10.6	0.0
41.001	50.00	5.30	37.258	0.002	0.0	0.0	0.0	0.88	6.9	0.4
41.002	50.00	5.34	37.098	0.002	0.0	0.0	0.0	3.86	68.2	0.4
42.000	50.00	5.02	36.030	0.000	0.0	0.0	0.0	2.77	21.8	0.0
34.007	50.00	6.12	35.503	0.158	0.0	0.0	0.0	6.60	466.4	28.5
19.007	50.00	7.45	33.235	0.589	0.0	0.0	0.0	1.00	159.7	106.3
43.000	50.00	5.12	35.591	0.000	0.0	0.0	0.0	0.97	7.6	0.0
43.001	50.00	5.17	35.480	0.000	0.0	0.0	0.0	0.95	7.4	0.0
43.002	50.00	5.40	35.440	0.000	0.0	0.0	0.0	0.86	6.8	0.0
43.003	50.00	5.48	35.287	0.000	0.0	0.0	0.0	0.86	6.8	0.0

©1982-2020 Innovyze

Paul Basham Associates											Page 11	
Lancaster Court Fareham Hampshire, PO15 5TU						189.5005 ANGMERING PHASE 2 NE 10% AEP +40% CC						
Date 08/10/2025 File 251007_NE PHASE 2.MDX						Designed by LEC Checked by COH						
Innovyze						Network 2020.1.3						
STORM SEWER DESIGN by the Modified Rational Method												
Network Design Table for Surface Network 5												
PN	Length (m)	Fall (m)	Slope (1:X)	I.Area (ha)	T.E. (mins)	Base Flow (l/s)	k (mm)	n	HYD SECT	DIA (mm)	Section Type	Auto Design
44.000	12.883	0.610	21.1	0.000	5.00	0.0	0.600		o	100	Pipe/Conduit	
45.000	6.491	0.290	22.4	0.000	5.00	0.0	0.600		o	100	Pipe/Conduit	
43.004	7.011	1.524	4.6	0.000	0.00	0.0	0.600		o	150	Pipe/Conduit	
19.008	41.812	0.253	165.5	0.112	0.00	0.0	0.600		o	450	Pipe/Conduit	
46.000	6.245	0.070	89.6	0.000	5.00	0.0	0.600		o	100	Pipe/Conduit	
46.001	6.497	1.206	5.4	0.000	0.00	0.0	0.600		o	100	Pipe/Conduit	
47.000	6.277	0.104	60.4	0.000	5.00	0.0	0.600		o	100	Pipe/Conduit	
47.001	5.007	0.263	19.1	0.000	0.00	0.0	0.600		o	100	Pipe/Conduit	
46.002	41.205	0.581	71.0	0.033	0.00	0.0	0.600		o	225	Pipe/Conduit	
48.000	12.268	1.380	8.9	0.000	5.00	0.0	0.600		o	100	Pipe/Conduit	
48.001	17.204	0.430	40.0	0.013	0.00	0.0	0.600		o	150	Pipe/Conduit	
49.000	7.110	0.084	84.3	0.000	5.00	0.0	0.600		o	100	Pipe/Conduit	
Network Results Table												
PN	Rain (mm/hr)	T.C. (mins)	US/IL (m)	E I.Area (ha)	E Base Flow (l/s)	Foul (l/s)	Add Flow (l/s)	Vel (m/s)	Cap (l/s)	Flow (l/s)		
44.000	50.00	5.13	35.850	0.000	0.0	0.0	0.0	1.69	13.3	0.0		
45.000	50.00	5.07	35.530	0.000	0.0	0.0	0.0	1.64	12.9	0.0		
43.004	50.00	5.50	35.190	0.000	0.0	0.0	0.0	4.73	83.6	0.0		
19.008	50.00	7.89	33.207	0.700	0.0	0.0	0.0	1.58	250.9	126.5		
46.000	50.00	5.13	35.161	0.000	0.0	0.0	0.0	0.81	6.4	0.0		
46.001	50.00	5.16	35.092	0.000	0.0	0.0	0.0	3.35	26.3	0.0		
47.000	50.00	5.11	34.252	0.000	0.0	0.0	0.0	0.99	7.8	0.0		
47.001	50.00	5.15	34.148	0.000	0.0	0.0	0.0	1.78	14.0	0.0		
46.002	50.00	5.60	33.760	0.033	0.0	0.0	0.0	1.55	61.8	5.9		
48.000	50.00	5.08	35.740	0.000	0.0	0.0	0.0	2.61	20.5	0.0		
48.001	50.00	5.26	34.360	0.013	0.0	0.0	0.0	1.60	28.2	2.3		
49.000	50.00	5.14	34.584	0.000	0.0	0.0	0.0	0.84	6.6	0.0		
©1982-2020 Innovyze												

Paul Basham Associates

Lancaster Court
Fareham
Hampshire, PO15 5TU

Date 08/10/2025
File 251007_NE PHASE 2.MDX

Innovyze

189.5005 ANGMERING
PHASE 2 NE
10% AEP +40% CC

Designed by LEC
Checked by COH

Network 2020.1.3

Page 12



STORM SEWER DESIGN by the Modified Rational Method

Network Design Table for Surface Network 5

PN	Length (m)	Fall (m)	Slope (1:X)	I.Area (ha)	T.E. (mins)	Base Flow (l/s)	k (mm)	n	HYD SECT	DIA (mm)	Section Type	Auto Design
49.001	17.207	0.570	30.2	0.011	0.00	0.0	0.600		o	100	Pipe/Conduit	
48.002	5.542	0.550	10.1	0.000	0.00	0.0	0.600		o	150	Pipe/Conduit	
50.000	12.613	0.158	80.0	0.000	5.00	0.0	0.600		o	100	Pipe/Conduit	
50.001	3.146	0.037	84.8	0.000	0.00	0.0	0.600		o	100	Pipe/Conduit	
48.003	9.869	0.126	78.6	0.007	0.00	0.0	0.600		o	225	Pipe/Conduit	
19.009	32.727	2.720	12.0	0.020	0.00	0.0	0.600		o	450	Pipe/Conduit	
51.000	7.540	0.780	9.7	0.014	5.00	0.0	0.600		o	100	Pipe/Conduit	
51.001	15.003	0.543	27.6	0.004	0.00	0.0	0.600		o	100	Pipe/Conduit	
51.002	7.891	0.929	8.5	0.000	0.00	0.0	0.600		o	100	Pipe/Conduit	
52.000	14.212	0.178	79.9	0.007	5.00	0.0	0.600		o	100	Pipe/Conduit	
51.003	13.122	0.164	80.1	0.000	0.00	0.0	0.600		o	150	Pipe/Conduit	
53.000	11.274	0.194	58.2	0.014	5.00	0.0	0.600		o	100	Pipe/Conduit	

Network Results Table

PN	Rain (mm/hr)	T.C. (mins)	US/IL (m)	E I.Area (ha)	E Base Flow (l/s)	Foul (l/s)	Add Flow (l/s)	Vel (m/s)	Cap (l/s)	Flow (l/s)	
49.001	50.00	5.34	34.500	0.011		0.0	0.0	0.0	1.41	11.1	2.0
48.002	50.00	5.37	33.930	0.024		0.0	0.0	0.0	3.19	56.4	4.3
50.000	50.00	5.24	33.625	0.000		0.0	0.0	0.0	0.86	6.8	0.0
50.001	50.00	5.31	33.467	0.000		0.0	0.0	0.0	0.84	6.6	0.0
48.003	50.00	5.49	33.380	0.031		0.0	0.0	0.0	1.48	58.7	5.5
19.009	50.00	7.99	32.954	0.784		0.0	0.0	0.0	5.89	936.0	141.5
51.000	50.00	5.05	34.012	0.014		0.0	0.0	0.0	2.50	19.6	2.5
51.001	50.00	5.22	33.232	0.018		0.0	0.0	0.0	1.47	11.6	3.3
51.002	50.00	5.27	32.689	0.018		0.0	0.0	0.0	2.67	21.0	3.3
52.000	50.00	5.27	31.938	0.007		0.0	0.0	0.0	0.86	6.8	1.2
51.003	50.00	5.47	31.710	0.025		0.0	0.0	0.0	1.12	19.9	4.5
53.000	50.00	5.19	32.700	0.014		0.0	0.0	0.0	1.01	7.9	2.5

©1982-2020 Innovyze

Paul Basham Associates

Lancaster Court
Fareham
Hampshire, PO15 5TU

Date 08/10/2025
File 251007_NE PHASE 2.MDX

Innovyze

189.5005 ANGMERING
PHASE 2 NE
10% AEP +40% CC

Designed by LEC
Checked by COH

Network 2020.1.3

Page 13



STORM SEWER DESIGN by the Modified Rational Method

Network Design Table for Surface Network 5

PN	Length (m)	Fall (m)	Slope (1:X)	I.Area (ha)	T.E. (mins)	Base Flow (l/s)	k (mm)	n	HYD SECT	DIA (mm)	Section Type	Auto Design
54.000	5.399	0.290	18.6	0.000	5.00	0.0	0.600		o	100	Pipe/Conduit	
54.001	5.141	0.277	18.6	0.007	0.00	0.0	0.600		o	100	Pipe/Conduit	
53.001	9.150	1.922	4.8	0.000	0.00	0.0	0.600		o	150	Pipe/Conduit	
19.010	12.398	0.031	400.0	0.030	0.00	0.0	0.600		o	600	Pipe/Conduit	
55.000	13.192	0.169	78.0	0.000	5.00	0.0	0.600		o	100	Pipe/Conduit	
56.000	11.786	0.430	27.4	0.014	5.00	0.0	0.600		o	100	Pipe/Conduit	
55.001	9.359	0.180	52.0	0.000	0.00	0.0	0.600		o	100	Pipe/Conduit	
57.000	13.984	0.128	109.0	0.000	5.00	0.0	0.600		o	100	Pipe/Conduit	
55.002	7.652	1.486	5.1	0.000	0.00	0.0	0.600		o	150	Pipe/Conduit	
19.011	16.107	0.040	400.0	0.015	0.00	0.0	0.600		o	600	Pipe/Conduit	
58.000	3.533	0.090	39.3	0.006	5.00	0.0	0.600		o	100	Pipe/Conduit	
58.001	10.371	1.156	9.0	0.000	0.00	0.0	0.600		o	100	Pipe/Conduit	
Network Results Table												
PN	Rain (mm/hr)	T.C. (mins)	US/IL (m)	E I.Area (ha)	Σ Base Flow (l/s)	Foul (l/s)	Add Flow (l/s)	Vel (m/s)	Cap (l/s)	Flow (l/s)		
54.000	50.00	5.05	33.073	0.000	0.0	0.0	0.0	1.80	14.1	0.0		
54.001	50.00	5.10	32.783	0.007	0.0	0.0	0.0	1.80	14.1	1.3		
53.001	50.00	5.22	32.456	0.021	0.0	0.0	0.0	4.65	82.2	3.8		
19.010	50.00	8.16	30.085	0.860	0.0	0.0	0.0	1.21	342.5	155.3		
55.000	50.00	5.25	32.389	0.000	0.0	0.0	0.0	0.87	6.8	0.0		
56.000	50.00	5.13	32.650	0.014	0.0	0.0	0.0	1.48	11.6	2.5		
55.001	50.00	5.40	32.220	0.014	0.0	0.0	0.0	1.07	8.4	2.5		
57.000	50.00	5.32	32.168	0.000	0.0	0.0	0.0	0.74	5.8	0.0		
55.002	50.00	5.43	31.990	0.014	0.0	0.0	0.0	4.47	79.0	2.5		
19.011	50.00	8.38	30.054	0.889	0.0	0.0	0.0	1.21	342.5	160.4		
58.000	50.00	5.05	32.350	0.006	0.0	0.0	0.0	1.23	9.7	1.1		
58.001	50.00	5.11	32.260	0.006	0.0	0.0	0.0	2.60	20.4	1.1		

©1982-2020 Innovyze

Paul Basham Associates											Page 14	
Lancaster Court Fareham Hampshire, PO15 5TU					189.5005 ANGMERING PHASE 2 NE 10% AEP +40% CC							
Date 08/10/2025 File 251007_NE PHASE 2.MDX					Designed by LEC Checked by COH							
Innovyze					Network 2020.1.3							
STORM SEWER DESIGN by the Modified Rational Method												
Network Design Table for Surface Network 5												
PN	Length (m)	Fall (m)	Slope (1:X)	I.Area (ha)	T.E. (mins)	Base Flow (l/s)	k (mm)	n	HYD SECT	DIA (mm)	Section Type	Auto Design
19.012	57.300	0.143	399.6	0.114	0.00	0.0	0.600		o	600	Pipe/Conduit	
59.000	11.988	0.670	17.9	0.005	5.00	0.0	0.600		o	100	Pipe/Conduit	
59.001	40.659	0.491	82.8	0.033	0.00	0.0	0.600		o	150	Pipe/Conduit	
60.000	12.302	0.772	15.9	0.000	5.00	0.0	0.600		o	100	Pipe/Conduit	
59.002	10.248	0.274	37.5	0.007	0.00	0.0	0.600		o	225	Pipe/Conduit	
61.000	7.054	0.088	80.0	0.000	5.00	0.0	0.600		o	100	Pipe/Conduit	
61.001	2.514	0.032	77.5	0.000	0.00	0.0	0.600		o	100	Pipe/Conduit	
61.002	12.680	0.350	36.2	0.004	0.00	0.0	0.600		o	100	Pipe/Conduit	
62.000	7.646	0.530	14.4	0.000	5.00	0.0	0.600		o	100	Pipe/Conduit	
61.003	14.385	0.500	28.8	0.000	0.00	0.0	0.600		o	150	Pipe/Conduit	
63.000	9.759	0.058	166.9	0.000	5.00	0.0	0.600		o	100	Pipe/Conduit	
64.000	5.141	0.046	110.8	0.000	5.00	0.0	0.600		o	100	Pipe/Conduit	
Network Results Table												
PN	Rain (mm/hr)	T.C. (mins)	US/IL (m)	E I.Area (ha)	E Base Flow (l/s)	Foul (l/s)	Add Flow (l/s)	Vel (m/s)	Cap (l/s)	Flow (l/s)		
19.012	50.00	9.17	30.013	1.009		0.0	0.0		0.0	1.21	342.7	182.2
59.000	50.00	5.11	31.730	0.005		0.0	0.0		0.0	1.83	14.4	1.0
59.001	50.00	5.72	31.010	0.038		0.0	0.0		0.0	1.11	19.5	6.9
60.000	50.00	5.11	31.542	0.000		0.0	0.0		0.0	1.94	15.3	0.0
59.002	50.00	5.80	30.519	0.045		0.0	0.0		0.0	2.14	85.3	8.2
61.000	50.00	5.14	31.291	0.000		0.0	0.0		0.0	0.86	6.8	0.0
61.001	50.00	5.18	31.202	0.000		0.0	0.0		0.0	0.87	6.9	0.0
61.002	50.00	5.35	31.170	0.004		0.0	0.0		0.0	1.29	10.1	0.8
62.000	50.00	5.06	31.350	0.000		0.0	0.0		0.0	2.04	16.1	0.0
61.003	50.00	5.48	30.820	0.004		0.0	0.0		0.0	1.88	33.3	0.8
63.000	50.00	5.27	31.495	0.000		0.0	0.0		0.0	0.59	4.7	0.0
64.000	50.00	5.12	31.483	0.000		0.0	0.0		0.0	0.73	5.7	0.0
©1982-2020 Innovyze												

Paul Basham Associates

Lancaster Court
Fareham
Hampshire, PO15 5TU

Date 08/10/2025
File 251007_NE PHASE 2.MDX

Innovyze

189.5005 ANGMERING
PHASE 2 NE
10% AEP +40% CC

Designed by LEC
Checked by COH

Network 2020.1.3

Page 15



STORM SEWER DESIGN by the Modified Rational Method

Network Design Table for Surface Network 5

PN	Length (m)	Fall (m)	Slope (1:X)	I.Area (ha)	T.E. (mins)	Base Flow (l/s)	k (mm)	n	HYD SECT	DIA (mm)	Section Type	Auto Design
63.001	9.586	1.066	9.0	0.000	0.00	0.0	0.600		o	100	Pipe/Conduit	
19.013	21.227	0.074	285.0	0.040	0.00	0.0	0.600		o	600	Pipe/Conduit	
65.000	11.876	0.198	59.9	0.000	5.00	0.0	0.600		o	100	Pipe/Conduit	
65.001	17.682	0.901	19.6	0.000	0.00	0.0	0.600		o	100	Pipe/Conduit	
66.000	13.080	1.271	10.3	0.000	5.00	0.0	0.600		o	100	Pipe/Conduit	
65.002	11.173	0.384	29.1	0.031	0.00	0.0	0.600		o	150	Pipe/Conduit	
65.003	21.742	0.677	32.1	0.011	0.00	0.0	0.600		o	150	Pipe/Conduit	
67.000	10.718	0.328	32.7	0.012	5.00	0.0	0.600		o	100	Pipe/Conduit	
67.001	6.231	0.789	7.9	0.000	0.00	0.0	0.600		o	100	Pipe/Conduit	
65.004	7.177	0.303	23.7	0.000	0.00	0.0	0.600		o	225	Pipe/Conduit	
65.005	10.324	0.467	22.1	0.000	0.00	0.0	0.600		o	225	Pipe/Conduit	
68.000	6.744	0.490	13.8	0.000	5.00	0.0	0.600		o	100	Pipe/Conduit	

Network Results Table

PN	Rain (mm/hr)	T.C. (mins)	US/IL (m)	E I.Area (ha)	E Base Flow (l/s)	Foul (l/s)	Add Flow (l/s)	Vel (m/s)	Cap (l/s)	Flow (l/s)
63.001	50.00	5.34	31.436	0.000	0.0	0.0	0.0	2.59	20.4	0.0
19.013	50.00	9.41	29.870	1.099	0.0	0.0	0.0	1.44	406.4	198.5
65.000	50.00	5.20	39.202	0.000	0.0	0.0	0.0	1.00	7.8	0.0
65.001	50.00	5.37	39.003	0.000	0.0	0.0	0.0	1.75	13.8	0.0
66.000	50.00	5.09	39.374	0.000	0.0	0.0	0.0	2.42	19.0	0.0
65.002	50.00	5.47	38.052	0.031	0.0	0.0	0.0	1.87	33.1	5.6
65.003	50.00	5.67	37.668	0.042	0.0	0.0	0.0	1.78	31.5	7.6
67.000	50.00	5.13	38.158	0.012	0.0	0.0	0.0	1.35	10.6	2.2
67.001	50.00	5.17	37.830	0.012	0.0	0.0	0.0	2.77	21.7	2.2
65.004	50.00	5.71	36.917	0.054	0.0	0.0	0.0	2.70	107.3	9.8
65.005	50.00	5.78	36.614	0.054	0.0	0.0	0.0	2.80	111.2	9.8
68.000	50.00	5.05	36.761	0.000	0.0	0.0	0.0	2.09	16.4	0.0

©1982-2020 Innovyze

Paul Basham Associates											Page 16	
Lancaster Court Fareham Hampshire, PO15 5TU					189.5005 ANGMERING PHASE 2 NE 10% AEP +40% CC							
Date 08/10/2025 File 251007_NE PHASE 2.MDX					Designed by LEC Checked by COH							
Innovyze					Network 2020.1.3							
<u>STORM SEWER DESIGN by the Modified Rational Method</u>												
<u>Network Design Table for Surface Network 5</u>												
PN	Length (m)	Fall (m)	Slope (1:X)	I.Area (ha)	T.E. (mins)	Base Flow (l/s)	k (mm)	n	HYD SECT	DIA (mm)	Section Type	Auto Design
65.006	41.157	2.492	16.5	0.087	0.00	0.0	0.600		o	300	Pipe/Conduit	
69.000	7.897	0.099	80.0	0.000	5.00	0.0	0.600		o	100	Pipe/Conduit	
69.001	11.899	0.149	79.9	0.000	0.00	0.0	0.600		o	100	Pipe/Conduit	
69.002	8.141	0.366	22.2	0.000	0.00	0.0	0.600		o	100	Pipe/Conduit	
65.007	38.185	2.183	17.5	0.032	0.00	0.0	0.600		o	375	Pipe/Conduit	
70.000	10.436	0.130	80.0	0.000	5.00	0.0	0.600		o	100	Pipe/Conduit	
70.001	14.417	0.251	57.5	0.000	0.00	0.0	0.600		o	100	Pipe/Conduit	
70.002	5.569	0.380	14.6	0.000	0.00	0.0	0.600		o	100	Pipe/Conduit	
71.000	10.704	0.040	268.9	0.000	5.00	0.0	0.600		o	100	Pipe/Conduit	
70.003	6.038	0.730	8.3	0.000	0.00	0.0	0.600		o	150	Pipe/Conduit	
72.000	7.727	0.062	124.7	0.000	5.00	0.0	0.600		o	100	Pipe/Conduit	
70.004	6.469	0.459	14.1	0.006	0.00	0.0	0.600		o	150	Pipe/Conduit	
65.008	24.322	1.375	17.7	0.036	0.00	0.0	0.600		o	375	Pipe/Conduit	
<u>Network Results Table</u>												
PN	Rain (mm/hr)	T.C. (mins)	US/IL (m)	E I.Area (ha)	E Base Flow (l/s)	Foul (l/s)	Add Flow (l/s)	Vel (m/s)	Cap (l/s)	Flow (l/s)		
65.006	50.00	5.95	36.071	0.141		0.0	0.0	0.0	3.89	274.8	25.5	
69.000	50.00	5.15	34.468	0.000		0.0	0.0	0.0	0.86	6.8	0.0	
69.001	50.00	5.38	34.369	0.000		0.0	0.0	0.0	0.86	6.8	0.0	
69.002	50.00	5.47	34.220	0.000		0.0	0.0	0.0	1.64	12.9	0.0	
65.007	50.00	6.10	33.579	0.173		0.0	0.0	0.0	4.35	480.5	31.3	
70.000	50.00	5.20	33.621	0.000		0.0	0.0	0.0	0.86	6.8	0.0	
70.001	50.00	5.44	33.491	0.000		0.0	0.0	0.0	1.02	8.0	0.0	
70.002	50.00	5.48	33.240	0.000		0.0	0.0	0.0	2.03	15.9	0.0	
71.000	50.00	5.38	32.900	0.000		0.0	0.0	0.0	0.46	3.6	0.0	
70.003	50.00	5.51	32.810	0.000		0.0	0.0	0.0	3.52	62.3	0.0	
72.000	50.00	5.19	32.192	0.000		0.0	0.0	0.0	0.69	5.4	0.0	
70.004	50.00	5.55	32.080	0.006		0.0	0.0	0.0	2.70	47.7	1.0	
65.008	50.00	6.19	31.396	0.215		0.0	0.0	0.0	4.33	477.7	38.9	
©1982-2020 Innovyze												

Paul Basham Associates

Lancaster Court
Fareham
Hampshire, PO15 5TU

Date 08/10/2025
File 251007_NE PHASE 2.MDX

189.5005 ANGMERING
PHASE 2 NE
10% AEP +40% CC

Designed by LEC
Checked by COH

Page 17



Innovyze

Network 2020.1.3

STORM SEWER DESIGN by the Modified Rational Method

Network Design Table for Surface Network 5

PN	Length (m)	Fall (m)	Slope (1:X)	I.Area (ha)	T.E. (mins)	Base Flow (l/s)	k (mm)	n	HYD SECT	DIA (mm)	Section Type	Auto Design
73.000	5.145	0.064	80.0	0.000	5.00	0.0	0.600		o	100	Pipe/Conduit	
73.001	7.866	0.524	15.0	0.010	0.00	0.0	0.600		o	100	Pipe/Conduit	
19.014	16.174	0.040	400.0	0.000	0.00	0.0	0.600		o	600	Pipe/Conduit	
19.015	10.654	0.027	400.0	0.024	0.00	0.0	0.600		o	600	Pipe/Conduit	
19.016	30.660	0.359	85.4	0.022	0.00	0.0		0.045	3 \=/	100	1:3 Swale	
19.017	32.076	0.570	56.3	0.036	0.00	0.0		0.045	3 \=/	100	1:3 Swale	
19.018	19.419	0.600	32.4	0.015	0.00	0.0		0.045	3 \=/	100	1:3 Swale	
74.000	13.172	0.047	277.8	0.000	5.00	0.0	0.600		o	100	Pipe/Conduit	
74.001	10.648	0.127	83.9	0.000	0.00	0.0	0.600		o	100	Pipe/Conduit	
74.002	14.890	0.401	37.1	0.000	0.00	0.0	0.600		o	100	Pipe/Conduit	
75.000	3.527	0.212	16.6	0.000	5.00	0.0	0.600		o	100	Pipe/Conduit	
75.001	13.544	0.390	34.7	0.002	0.00	0.0	0.600		o	100	Pipe/Conduit	
74.003	16.017	0.218	73.5	0.000	0.00	0.0	0.600		o	150	Pipe/Conduit	
76.000	13.512	0.894	15.1	0.000	5.00	0.0	0.600		o	100	Pipe/Conduit	
76.001	12.204	0.704	17.3	0.000	0.00	0.0	0.600		o	100	Pipe/Conduit	

Network Results Table

PN	Rain (mm/hr)	T.C. (mins)	US/IL (m)	Σ I.Area (ha)	Σ Base Flow (l/s)	Foul (l/s)	Add Flow (l/s)	Vel (m/s)	Cap (l/s)	Flow (l/s)
73.000	50.00	5.10	30.884	0.000	0.0	0.0	0.0	0.86	6.8	0.0
73.001	50.00	5.17	30.820	0.010	0.0	0.0	0.0	2.00	15.7	1.8
19.014	50.00	9.63	29.796	1.324	0.0	0.0	0.0	1.21	342.5	239.1
19.015	50.00	9.78	29.755	1.348	0.0	0.0	0.0	1.21	342.5	243.4
19.016	50.00	10.13	29.729	1.370	0.0	0.0	0.0	1.46	4407.6	247.4
19.017	50.00	10.43	29.370	1.406	0.0	0.0	0.0	1.80	5429.9	253.9
19.018	50.00	10.56	28.800	1.422	0.0	0.0	0.0	2.38	7121.8	256.7
74.000	50.00	5.48	29.476	0.000	0.0	0.0	0.0	0.46	3.6	0.0
74.001	50.00	5.69	29.428	0.000	0.0	0.0	0.0	0.84	6.6	0.0
74.002	50.00	5.89	29.301	0.000	0.0	0.0	0.0	1.27	10.0	0.0
75.000	50.00	5.03	29.502	0.000	0.0	0.0	0.0	1.90	14.9	0.0
75.001	50.00	5.20	29.290	0.002	0.0	0.0	0.0	1.31	10.3	0.4
74.003	50.00	6.11	28.850	0.002	0.0	0.0	0.0	1.17	20.8	0.4
76.000	50.00	5.11	30.279	0.000	0.0	0.0	0.0	2.00	15.7	0.0
76.001	50.00	5.22	29.386	0.000	0.0	0.0	0.0	1.86	14.6	0.0

©1982-2020 Innovyze

Paul Basham Associates

Lancaster Court
Fareham
Hampshire, PO15 5TU

Date 08/10/2025
File 251007_NE PHASE 2.MDX

Innovyze

189.5005 ANGMERING
PHASE 2 NE
10% AEP +40% CC

Designed by LEC
Checked by COH

Network 2020.1.3

Page 18



STORM SEWER DESIGN by the Modified Rational Method

Network Design Table for Surface Network 5

PN	Length (m)	Fall (m)	Slope (1:X)	I.Area (ha)	T.E. (mins)	Base Flow (l/s)	k (mm)	n	HYD SECT	DIA (mm)	Section Type	Auto Design
77.000	11.061	0.710	15.6	0.006	5.00	0.0	0.600		o	100	Pipe/Conduit	
74.004	17.048	0.282	60.5	0.045	0.00	0.0	0.600		o	300	Pipe/Conduit	
78.000	3.036	0.210	14.5	0.000	5.00	0.0	0.600		o	100	Pipe/Conduit	
1.024	5.796	0.775	7.5	0.000	0.00	0.0	0.600		o	675	Pipe/Conduit	
1.025	58.041	0.600	96.7	0.000	0.00	0.0	0.600		o	675	Pipe/Conduit	
1.026	36.148	1.000	36.1	0.000	0.00	0.0	0.600		o	675	Pipe/Conduit	
1.027	37.630	1.609	23.4	0.000	0.00	0.0	0.600		o	675	Pipe/Conduit	
1.028	8.860	0.041	218.2	0.000	0.00	0.0	0.600		o	675	Pipe/Conduit	
1.029	18.180	1.075	16.9	0.000	0.00	0.0	0.600		o	675	Pipe/Conduit	

Network Results Table

PN	Rain (mm/hr)	T.C. (mins)	US/IL (m)	Σ I.Area (ha)	Σ Base Flow (l/s)	Foul (l/s)	Add Flow (l/s)	Vel (m/s)	Cap (l/s)	Flow (l/s)
77.000	50.00	5.09	29.392	0.006	0.0	0.0	0.0	1.97	15.4	1.0
74.004	50.00	6.25	28.482	0.053	0.0	0.0	0.0	2.03	143.2	9.5
78.000	50.00	5.02	28.410	0.000	0.0	0.0	0.0	2.04	16.0	0.0
1.024	50.00	10.57	28.200	2.082	0.0	0.0	0.0	9.62	3442.2	376.0
1.025	50.00	10.94	27.425	2.082	0.0	0.0	0.0	2.67	953.7	376.0
1.026	50.00	11.07	26.825	2.082	0.0	0.0	0.0	4.37	1563.1	376.0
1.027	50.00	11.19	25.825	2.082	0.0	0.0	0.0	5.43	1944.7	376.0
1.028	50.00	11.27	24.216	2.082	0.0	0.0	0.0	1.77	633.4	376.0
1.029	50.00	11.32	24.175	2.082	0.0	0.0	0.0	6.39	2287.5	376.0

Free Flowing Outfall Details for Surface Network 5

Outfall Pipe Number	Outfall Name	C. Level (m)	I. Level (m)	Min I. Level (m)	D,L (mm)	W (mm)
1.029	S3066	25.459	23.100	0.000	0	0

©1982-2020 Innovyze

Paul Basham Associates

Lancaster Court
Fareham
Hampshire, PO15 5TU

Date 08/10/2025
File 251007_NE PHASE 2.MDX

Innovyze

189.5005 ANGMERING
PHASE 2 NE
10% AEP +40% CC

Designed by LEC
Checked by COH

Network 2020.1.3

Page 20



Summary of Critical Results by Maximum Level (Rank 1) for Surface Network 5

Simulation Criteria

Areal Reduction Factor 1.000

Hot Start (mins) 0

Hot Start Level (mm) 0

Manhole Headloss Coeff (Global) 0.500

Foul Sewage per hectare (l/s) 0.000

Additional Flow - % of Total Flow 0.000

MADD Factor * 10m³/ha Storage 2.000

Inlet Coefficient 0.800

Flow per Person per Day (l/per/day) 0.000

Number of Input Hydrographs 0

Number of Online Controls 0

Number of Offline Controls 0

Number of Storage Structures 0

Number of Time/Area Diagrams 0

Number of Real Time Controls 0

Synthetic Rainfall Details

Rainfall Model FEH

FEH Rainfall Version 2013

Site Location GB 507546 105033 TQ 07546 05033

Data Type Point

Cv (Summer) 0.850

Cv (Winter) 0.900

Margin for Flood Risk Warning (mm) 200.0

Analysis Timestep 2.5 Second Increment (Extended)

DTS Status ON

DVD Status OFF

Inertia Status OFF

Profile(s) Summer and Winter

Duration(s) (mins) 15, 30, 60, 120, 240, 360, 480, 960, 1440

Return Period(s) (years) 10

Climate Change (%) 40

	US/MH		Return	Climate	First (X)	First (Y)	First (Z)	Overflow	Water
PN	Name	Storm	Period	Change	Surcharge	Flood	Overflow	Act.	Level
									(m)
1.000	PS1666	15 Summer	10	+40%					40.054
1.001	PS1665	15 Summer	10	+40%	10/15 Summer				40.044
1.002	PS1664	15 Summer	10	+40%	10/15 Summer				40.046
1.003	PS1663	15 Summer	10	+40%					39.768
1.004	PS1661	15 Summer	10	+40%					39.617
1.005	PS2904	15 Summer	10	+40%					39.541
1.006	PS2905	15 Summer	10	+40%					39.402
1.007	PS2906	15 Summer	10	+40%					39.168
1.008	PS2907	15 Summer	10	+40%					38.866
1.009	PS2908	15 Summer	10	+40%					38.310
1.010	PS2909	15 Summer	10	+40%					38.008
1.011	PS2910	15 Summer	10	+40%					37.715
2.000	PS1754	15 Summer	10	+40%					38.134
2.001	PS1753	15 Summer	10	+40%					37.990
3.000	PS1760	15 Summer	10	+40%					38.090
3.001	PS1759	15 Summer	10	+40%					37.580
2.002	PS1752	15 Summer	10	+40%					37.320

©1982-2020 Innovyze

Paul Basham Associates		Page 21
Lancaster Court Fareham Hampshire, PO15 5TU	189.5005 ANGMERING PHASE 2 NE 10% AEP +40% CC	
Date 08/10/2025 File 251007_NE PHASE 2.MDX	Designed by LEC Checked by COH	
Innovyze	Network 2020.1.3	

Summary of Critical Results by Maximum Level (Rank 1) for Surface Network 5

PN	US/MH Name	Surcharged		Flooded		Half Drain Time (mins)	Pipe Flow (l/s)	Status	Level Exceeded
		Depth (m)	Volume (m³)	Flow / Cap.	Overflow (l/s)				
1.000	PS1666	-0.100	0.000	0.00			0.0	OK	
1.001	PS1665	0.005	0.000	0.10			0.6	SURCHARGED	
1.002	PS1664	0.075	0.000	1.20			7.2	SURCHARGED	
1.003	PS1663	-0.042	0.000	0.86			14.3	OK	
1.004	PS1661	-0.042	0.000	0.82			14.2	OK	
1.005	PS2904	-0.978	0.000	0.01			23.4	OK	
1.006	PS2905	-0.871	0.000	0.01			36.5	OK	
1.007	PS2906	-0.885	0.000	0.01			37.0	OK	
1.008	PS2907	-0.860	0.000	0.01			47.4	OK	
1.009	PS2908	-0.832	0.000	0.02			83.6	OK	
1.010	PS2909	-0.794	0.000	0.02			89.2	OK	
1.011	PS2910	-0.841	0.000	0.01			93.3	OK	
2.000	PS1754	-0.100	0.000	0.00			0.0	OK	
2.001	PS1753	-0.100	0.000	0.00			0.0	OK	
3.000	PS1760	-0.100	0.000	0.00			0.0	OK	
3.001	PS1759	-0.100	0.000	0.00			0.0	OK	
2.002	PS1752	-0.150	0.000	0.00			0.0	OK	

Paul Basham Associates

Lancaster Court
Fareham
Hampshire, PO15 5TU

Date 08/10/2025
File 251007_NE PHASE 2.MDX

189.5005 ANGMERING
PHASE 2 NE
10% AEP +40% CC

Designed by LEC
Checked by COH

Innovyze

Network 2020.1.3

Page 22



Summary of Critical Results by Maximum Level (Rank 1) for Surface Network 5

PN	US/MH Name	Storm	Return Period	Climate Change	First (X) Surcharge	First (Y) Flood	First (Z) Overflow	Overflow Act.	Water Level (m)
4.000	PS1770	15 Summer	10	+40%					36.744
5.000	PS1779	15 Summer	10	+40%					36.845
4.001	PS1768	15 Summer	10	+40%					36.644
2.003	PS1750	15 Summer	10	+40%					36.469
1.012	PS2927	15 Summer	10	+40%					36.447
6.000	PS3062	15 Summer	10	+40%					36.300
6.001	PS1780	15 Summer	10	+40%					35.788
7.000	PS1778	15 Summer	10	+40%					36.456
6.002	PS1777	15 Summer	10	+40%					35.603
6.003	PS1776	15 Summer	10	+40%					35.506
8.000	PS1787	15 Summer	10	+40%	10/15 Summer				35.662
6.004	PS1774	15 Summer	10	+40%	10/15 Summer				35.476
6.005	PS3076	15 Summer	10	+40%	10/15 Summer				35.084
1.013	PS2911	15 Summer	10	+40%					35.117
1.014	PS2922	15 Summer	10	+40%					34.553
1.015	PS2913	15 Summer	10	+40%					32.838
9.000	PS1802	15 Summer	10	+40%					33.866
9.001	PS1797	15 Summer	10	+40%					33.370
10.000	PS1808	15 Summer	10	+40%					33.350
9.002	PS1796	15 Summer	10	+40%					33.070
11.000	PS1813	15 Summer	10	+40%					33.320
11.001	PS1812	15 Summer	10	+40%					33.151
9.003	PS1795	15 Summer	10	+40%					32.641
1.016	PS2929	15 Summer	10	+40%					32.614
12.000	PS1826	15 Summer	10	+40%					32.500
12.001	PS1825	15 Summer	10	+40%	10/15 Summer				32.411
12.002	PS1824	15 Summer	10	+40%					32.002
13.000	PS2854	15 Summer	10	+40%					32.017
13.001	PS2855	15 Summer	10	+40%					31.583
12.003	PS1818	15 Summer	10	+40%					31.279
1.017	PS2940	15 Summer	10	+40%					31.267
1.018	PS2914	15 Summer	10	+40%					31.127
1.019	PS2915	15 Summer	10	+40%					30.381
1.020	PS2916	15 Summer	10	+40%					30.075
14.000	PS2170	15 Summer	10	+40%					32.184
14.001	PS2169	15 Summer	10	+40%					32.157
15.000	PS2167	15 Summer	10	+40%					31.716
14.002	PS2166	15 Summer	10	+40%					31.045
14.003	PS32	15 Summer	10	+40%					30.225
16.000	PS1845	15 Summer	10	+40%					31.441
16.001	PS1851	15 Summer	10	+40%					30.779
17.000	PS1843	15 Summer	10	+40%					30.740
16.002	PS1842	15 Summer	10	+40%					30.367
16.003	PS1840	15 Summer	10	+40%					30.103
16.004	PS1839	15 Summer	10	+40%					29.654
18.000	PS1866	15 Summer	10	+40%					29.746
18.001	PS1865	15 Summer	10	+40%					29.562
18.002	PS1862	15 Summer	10	+40%					29.381
14.004	PS2941	15 Summer	10	+40%					29.347

©1982-2020

Innovyze

Paul Basham Associates

Lancaster Court
Fareham
Hampshire, PO15 5TU

Date 08/10/2025
File 251007_NE PHASE 2.MDX

Innovyze

189.5005 ANGMERING
PHASE 2 NE
10% AEP +40% CC

Designed by LEC
Checked by COH

Network 2020.1.3

Page 23



Summary of Critical Results by Maximum Level (Rank 1) for Surface Network 5

PN	US/MH Name	Surcharged Depth (m)	Flooded Volume (m³)	Flow / Cap.	Overflow (l/s)	Half Drain Time (mins)	Pipe Flow (l/s)	Status	Level Exceeded
4.000	PS1770	-0.073	0.000	0.16			1.0	OK	
5.000	PS1779	-0.100	0.000	0.00			0.0	OK	
4.001	PS1768	-0.033	0.000	0.79			4.5	OK	
2.003	PS1750	-0.067	0.000	0.58			18.5	OK	
1.012	PS2927	-0.779	0.000	0.02			119.1	OK	
6.000	PS3062	-0.100	0.000	0.00			0.0	OK	
6.001	PS1780	-0.022	0.000	0.97			5.2	OK	
7.000	PS1778	-0.061	0.000	0.32			4.1	OK	
6.002	PS1777	-0.077	0.000	0.47			9.3	OK	
6.003	PS1776	-0.004	0.000	0.62			9.1	OK	
8.000	PS1787	0.385	0.000	1.11			7.0	SURCHARGED	
6.004	PS1774	0.293	0.000	0.93			14.7	SURCHARGED	
6.005	PS3076	0.050	0.000	3.73			14.7	FLOOD RISK*	
1.013	PS2911	-0.715	0.000	0.02			140.5	OK	
1.014	PS2922	-0.714	0.000	0.02			147.2	OK	
1.015	PS2913	-0.784	0.000	0.02			145.8	OK	
9.000	PS1802	-0.100	0.000	0.00			0.0	OK	
9.001	PS1797	-0.150	0.000	0.00			0.0	OK	
10.000	PS1808	-0.100	0.000	0.00			0.0	OK	
9.002	PS1796	-0.150	0.000	0.00			0.0	OK	
11.000	PS1813	-0.100	0.000	0.00			0.0	OK	
11.001	PS1812	-0.079	0.000	0.10			1.1	OK	
9.003	PS1795	-0.116	0.000	0.38			16.8	OK	
1.016	PS2929	-0.735	0.000	0.02			167.5	OK	
12.000	PS1826	-0.100	0.000	0.00			0.0	OK	
12.001	PS1825	0.091	0.000	1.18			7.5	SURCHARGED	
12.002	PS1824	-0.103	0.000	0.22			7.5	OK	
13.000	PS2854	-0.100	0.000	0.00			0.0	OK	
13.001	PS2855	-0.067	0.000	0.24			2.1	OK	
12.003	PS1818	-0.126	0.000	0.18			9.4	OK	
1.017	PS2940	-0.767	0.000	0.03			175.0	OK	
1.018	PS2914	-0.383	0.000	0.09			185.5	OK	
1.019	PS2915	-0.750	0.000	0.03			187.6	OK	
1.020	PS2916	-1.366	0.000	0.01			188.4	OK	
14.000	PS2170	-0.039	0.000	0.67			1.6	OK	
14.001	PS2169	-0.063	0.000	0.30			5.9	OK	
15.000	PS2167	-0.100	0.000	0.00			0.0	OK	
14.002	PS2166	-0.065	0.000	0.26			5.9	OK	
14.003	PS32	-0.230	0.000	0.12			21.8	OK	
16.000	PS1845	-0.100	0.000	0.00			0.0	OK	
16.001	PS1851	-0.100	0.000	0.00			0.0	OK	
17.000	PS1843	-0.100	0.000	0.00			0.0	OK	
16.002	PS1842	-0.123	0.000	0.08			2.0	OK	
16.003	PS1840	-0.127	0.000	0.06			2.0	OK	
16.004	PS1839	-0.126	0.000	0.06			2.0	OK	
18.000	PS1866	-0.100	0.000	0.00			0.0	OK	
18.001	PS1865	-0.100	0.000	0.00			0.0	OK	
18.002	PS1862	-0.100	0.000	0.00			0.0	OK	

©1982-2020 Innovyze

Lancaster Court
Fareham
Hampshire, PO15 5TU

189.5005 ANGMERING
PHASE 2 NE
10% AEP +40% CC



Date	08/10/2025
------	------------

Designed by LEC

File 251007_NE PHASE 2.MDX

Checked by COH

Innovyze

Network 2020.1.3

Summary of Critical Results by Maximum Level (Rank 1) for Surface Network 5

PN	US/MH Name	Surcharged	Flooded			Half Drain	Pipe	Status	Level Exceeded
		Depth (m)	Volume (m³)	Flow / Cap.	Overflow (l/s)	Time (mins)	Flow (l/s)		
14.004	PS2941	-0.086	0.000	0.65			59.2	OK	

Paul Basham Associates

Page 25

Lancaster Court
Fareham
Hampshire, PO15 5TU

Date 08/10/2025
File 251007_NE PHASE 2.MDX

189.5005 ANGMERING
PHASE 2 NE
10% AEP +40% CC

Designed by LEC
Checked by COH

Innovyze

Network 2020.1.3

Micro
Drainage

Summary of Critical Results by Maximum Level (Rank 1) for Surface Network 5

PN	US/MH Name	Storm	Return Period	Climate Change	First (X) Surcharge	First (Y) Flood	First (Z) Overflow	Overflow Act.	Water Level (m)
1.021	PS2716	15 Summer	10	+40%					29.306
1.022	PS2917	15 Summer	10	+40%					29.104
1.023	PS2918	15 Summer	10	+40%					28.968
19.000	PS2064	15 Summer	10	+40%					34.260
19.001	PS2063	15 Summer	10	+40%					34.164
19.002	PS2062	15 Summer	10	+40%	10/15 Summer				34.198
20.000	PS2072	15 Summer	10	+40%					34.698
20.001	PS2071	15 Summer	10	+40%					34.572
21.000	PS2069	15 Summer	10	+40%					35.063
20.002	PS2068	15 Summer	10	+40%					34.418
22.000	PS2060	15 Summer	10	+40%					34.863
19.003	S35	15 Summer	10	+40%	10/15 Summer				34.199
23.000	PS2090	15 Summer	10	+40%					34.214
23.001	S2723	15 Summer	10	+40%	10/15 Summer				34.211
24.000	PS2084	15 Summer	10	+40%					34.423
24.001	PS2083	15 Summer	10	+40%					34.278
23.002	S36	15 Summer	10	+40%	10/15 Summer				34.185
25.000	PS2056	15 Summer	10	+40%					34.836
19.004	S37	15 Summer	10	+40%	10/15 Summer				34.166
26.000	PS2257	15 Summer	10	+40%					38.359
26.001	PS2256	15 Summer	10	+40%					38.327
27.000	PS1687	15 Summer	10	+40%					39.280
26.002	PS2255	15 Summer	10	+40%					38.095
26.003	PS2252	15 Summer	10	+40%					37.862
28.000	PS2887	15 Summer	10	+40%					38.744
26.004	S39	15 Summer	10	+40%					37.531
29.000	PS1566	15 Summer	10	+40%					37.399
29.001	PS1565	15 Summer	10	+40%					37.256
29.002	S41	15 Summer	10	+40%					36.600
19.005	S2709	15 Summer	10	+40%	10/15 Summer				34.139
30.000	PS1602	15 Summer	10	+40%					36.400
30.001	PS1601	15 Summer	10	+40%					36.321
30.002	PS3053	15 Summer	10	+40%					36.240
30.003	PS2819	15 Summer	10	+40%					36.176
31.000	PS2986	15 Summer	10	+40%					36.293
31.001	PS2987	15 Summer	10	+40%					36.163
30.004	PS1599	15 Summer	10	+40%					36.010
32.000	PS2026	15 Summer	10	+40%					36.147
32.001	PS2025	15 Summer	10	+40%					36.044
33.000	PS3050	15 Summer	10	+40%					35.522
32.002	PS2029	15 Summer	10	+40%					35.326
19.006	S43	15 Summer	10	+40%	10/15 Summer				33.999
34.000	PS1686	15 Summer	10	+40%					39.696
34.001	PS1685	15 Summer	10	+40%					39.389
35.000	PS1702	15 Summer	10	+40%					39.628
34.002	PS1701	15 Summer	10	+40%					39.318
36.000	PS1712	15 Summer	10	+40%					38.988
34.003	PS1700	15 Summer	10	+40%					38.357
34.004	PS1699	15 Summer	10	+40%					38.193

©1982-2020 Innovyze

Paul Basham Associates

Page 26

Lancaster Court
Fareham
Hampshire, PO15 5TU

Date 08/10/2025
File 251007_NE PHASE 2.MDX

189.5005 ANGMERING
PHASE 2 NE
10% AEP +40% CC

Designed by LEC
Checked by COH

Innovyze

Network 2020.1.3

Micro
Drainage

Summary of Critical Results by Maximum Level (Rank 1) for Surface Network 5

PN	US/MH Name	Depth (m)	Volume (m³)	Flow / Cap.	Overflow (l/s)	Half Drain Time (mins)	Pipe Flow (l/s)	Status	Level Exceeded
1.021	PS2716	-0.690	0.000	0.05			229.9	OK	
1.022	PS2917	-0.683	0.000	0.06			232.5	OK	
1.023	PS2918	-0.681	0.000	0.05			239.2	OK	
19.000	PS2064	-0.100	0.000	0.00			0.0	OK	
19.001	PS2063	-0.087	0.000	0.00			0.0	OK	
19.002	PS2062	0.004	0.000	0.05			0.8	SURCHARGED	
20.000	PS2072	-0.061	0.000	0.32			2.1	OK	
20.001	PS2071	-0.062	0.000	0.31			2.1	OK	
21.000	PS2069	-0.078	0.000	0.11			2.0	OK	
20.002	PS2068	-0.118	0.000	0.10			4.1	OK	
22.000	PS2060	-0.100	0.000	0.00			0.0	OK	
19.003	S35	0.165	0.000	0.61			23.9	SURCHARGED	
23.000	PS2090	-0.100	0.000	0.00			0.0	OK	
23.001	S2723	0.047	0.000	0.50			8.3	SURCHARGED	
24.000	PS2084	-0.042	0.000	0.63			4.2	OK	
24.001	PS2083	-0.053	0.000	0.44			4.2	OK	
23.002	S36	0.188	0.000	0.74			23.1	SURCHARGED	
25.000	PS2056	-0.100	0.000	0.00			0.0	OK	
19.004	S37	0.217	0.000	0.38			60.3	SURCHARGED	
26.000	PS2257	-0.072	0.000	0.17			1.0	OK	
26.001	PS2256	-0.042	0.000	0.64			4.7	OK	
27.000	PS1687	-0.100	0.000	0.00			0.0	OK	
26.002	PS2255	-0.035	0.000	0.75			6.7	OK	
26.003	PS2252	-0.108	0.000	0.18			6.7	OK	
28.000	PS2887	-0.112	0.000	0.14			6.1	OK	
26.004	S39	-0.068	0.000	0.58			36.0	OK	
29.000	PS1566	-0.075	0.000	0.15			1.0	OK	
29.001	PS1565	-0.074	0.000	0.15			2.4	OK	
29.002	S41	-0.065	0.000	0.61			32.1	OK	
19.005	S2709	0.306	0.000	1.04			152.3	SURCHARGED	
30.000	PS1602	-0.100	0.000	0.00			0.0	OK	
30.001	PS1601	-0.100	0.000	0.00			0.0	OK	
30.002	PS3053	-0.100	0.000	0.00			0.0	OK	
30.003	PS2819	-0.100	0.000	0.00			0.0	OK	
31.000	PS2986	-0.100	0.000	0.00			0.0	OK	
31.001	PS2987	-0.100	0.000	0.00			0.0	OK	
30.004	PS1599	-0.150	0.000	0.00			0.0	OK	
32.000	PS2026	-0.100	0.000	0.00			0.0	OK	
32.001	PS2025	-0.076	0.000	0.13			2.1	OK	
33.000	PS3050	-0.100	0.000	0.00			0.0	OK	
32.002	PS2029	-0.132	0.000	0.04			2.1	OK	
19.006	S43	0.289	0.000	1.69			159.6	SURCHARGED	
34.000	PS1686	-0.013	0.000	0.99			6.3	OK	
34.001	PS1685	-0.156	0.000	0.21			8.4	OK	
35.000	PS1702	-0.061	0.000	0.32			2.6	OK	
34.002	PS1701	-0.143	0.000	0.29			25.7	OK	
36.000	PS1712	-0.100	0.000	0.00			0.0	OK	
34.003	PS1700	-0.118	0.000	0.45			25.6	OK	

©1982-2020 Innovyze

Paul Basham Associates		Page 27
Lancaster Court	189.5005 ANGMERING	
Fareham	PHASE 2 NE	
Hampshire, PO15 5TU	10% AEP +40% CC	
Date 08/10/2025	Designed by LEC	
File 251007_NE PHASE 2.MDX	Checked by COH	
Innovyze	Network 2020.1.3	

Summary of Critical Results by Maximum Level (Rank 1) for Surface Network 5

PN	US/MH Name	Surcharged	Flooded	Flow / Cap.	Overflow (l/s)	Half Drain	Pipe	Status	Level Exceeded
		Depth (m)	Volume (m³)			Time (mins)	Flow (l/s)		
34.004	PS1699	-0.197	0.000	0.25			31.6	OK	

©1982-2020 Innovyze

Paul Basham Associates

Page 28

Lancaster Court
Fareham
Hampshire, PO15 5TU

189.5005 ANGMERING
PHASE 2 NE
10% AEP +40% CC

Date 08/10/2025
File 251007_NE PHASE 2.MDX

Designed by LEC
Checked by COH

Innovyze

Network 2020.1.3

Summary of Critical Results by Maximum Level (Rank 1) for Surface Network 5

PN	US/MH Name	Storm	Return Period	Climate Change	First (X) Surcharge	First (Y) Flood	First (Z) Overflow	Overflow Act.	Water Level (m)
37.000	PS1747	15 Summer	10	+40%					39.070
37.001	PS1725	15 Summer	10	+40%					38.943
38.000	PS1732	15 Summer	10	+40%					38.690
37.002	PS1727	15 Summer	10	+40%					38.529
34.005	S2722	15 Summer	10	+40%					37.867
39.000	PS1730	15 Summer	10	+40%					37.530
40.000	PS1717	15 Summer	10	+40%					37.690
34.006	S44	15 Summer	10	+40%					36.836
41.000	PS1611	15 Summer	10	+40%					37.420
41.001	PS1610	15 Summer	10	+40%					37.285
41.002	PS1609	15 Summer	10	+40%					37.112
42.000	PS1607	15 Summer	10	+40%					36.030
34.007	S45	15 Summer	10	+40%					35.598
19.007	S2714	15 Summer	10	+40%	10/15 Summer				33.946
43.000	PS1640	15 Summer	10	+40%					35.591
43.001	PS1639	15 Summer	10	+40%					35.480
43.002	PS1637	15 Summer	10	+40%					35.440
43.003	PS2828	15 Summer	10	+40%					35.287
44.000	PS1658	15 Summer	10	+40%					35.850
45.000	PS2824	15 Summer	10	+40%					35.530
43.004	PS2825	15 Summer	10	+40%					35.190
19.008	S2710	15 Summer	10	+40%	10/15 Summer				33.776
46.000	PS1773	15 Summer	10	+40%					35.161
46.001	PS1792	15 Summer	10	+40%					35.092
47.000	PS1798	15 Summer	10	+40%					34.252
47.001	PS1799	15 Summer	10	+40%					34.148
46.002	PS2715	15 Summer	10	+40%					33.840
48.000	PS2012	15 Summer	10	+40%					35.740
48.001	PS2011	15 Summer	10	+40%					34.409
49.000	PS2017	15 Summer	10	+40%					34.584
49.001	PS2016	15 Summer	10	+40%					34.552
48.002	PS2010	15 Summer	10	+40%					33.981
50.000	PS3058	15 Summer	10	+40%					33.625
50.001	PS3057	15 Summer	10	+40%					33.467
48.003	PS2007	15 Summer	10	+40%					33.466
19.009	S50	15 Summer	10	+40%					33.147
51.000	PS2003	15 Summer	10	+40%					34.053
51.001	PS2002	15 Summer	10	+40%					33.297
51.002	PS2001	15 Summer	10	+40%					32.735
52.000	PS1998	15 Summer	10	+40%					31.985
51.003	PS1997	15 Summer	10	+40%					31.796
53.000	PS2191	15 Summer	10	+40%					32.769
54.000	PS2197	15 Summer	10	+40%					33.073
54.001	PS3059	15 Summer	10	+40%					32.820
53.001	PS2190	15 Summer	10	+40%					32.493
19.010	S51	15 Winter	10	+40%	10/15 Summer				31.098
55.000	PS2185	15 Summer	10	+40%					32.389
56.000	PS2875	15 Summer	10	+40%					32.703
55.001	PS2876	15 Summer	10	+40%					32.287

©1982-2020 Innovyze

Paul Basham Associates							Page 29		
Lancaster Court Fareham Hampshire, PO15 5TU				189.5005 ANGMERING PHASE 2 NE 10% AEP +40% CC					
Date 08/10/2025 File 251007_NE PHASE 2.MDX				Designed by LEC Checked by COH					
Innovyze				Network 2020.1.3					
Summary of Critical Results by Maximum Level (Rank 1) for Surface Network 5									

Paul Basham Associates		Page 30
Lancaster Court Fareham Hampshire, PO15 5TU	189.5005 ANGMERING PHASE 2 NE 10% AEP +40% CC	
Date 08/10/2025 File 251007_NE PHASE 2.MDX	Designed by LEC Checked by COH	
Innovyze	Network 2020.1.3	

Summary of Critical Results by Maximum Level (Rank 1) for Surface Network 5

PN	US/MH Name	Surcharged	Flooded	Flow / Cap.	Overflow (l/s)	Half Drain	Pipe	Status	Level
		Depth (m)	Volume (m³)			Time (mins)	Flow (l/s)		Exceeded
55.001	PS2876	-0.033	0.000	0.76			5.9	OK	

©1982-2020 Innovyze

Paul Basham Associates

Lancaster Court
Fareham
Hampshire, PO15 5TU

Date 08/10/2025
File 251007_NE PHASE 2.MDX

189.5005 ANGMERING
PHASE 2 NE
10% AEP +40% CC

Designed by LEC
Checked by COH

Innovyze

Network 2020.1.3

Page 31



Summary of Critical Results by Maximum Level (Rank 1) for Surface Network 5

PN	US/MH Name	Storm	Return Period	Climate Change	First (X) Surcharge	First (Y) Flood	First (Z) Overflow	Overflow Act.	Water Level (m)
57.000	PS2179	15 Summer	10	+40%					32.168
55.002	PS2178	15 Summer	10	+40%					32.020
19.011	S2718	15 Winter	10	+40%	10/15 Summer				31.042
58.000	PS2885	15 Summer	10	+40%					32.391
58.001	PS1994	15 Summer	10	+40%					32.285
19.012	S53	15 Winter	10	+40%	10/15 Summer				30.975
59.000	PS1975	15 Summer	10	+40%					31.758
59.001	PS1974	15 Summer	10	+40%					31.129
60.000	PS1969	15 Summer	10	+40%					31.542
59.002	PS1968	15 Winter	10	+40%	10/15 Summer				30.800
61.000	PS2864	15 Summer	10	+40%					31.291
61.001	PS2865	15 Summer	10	+40%					31.202
61.002	PS1963	15 Summer	10	+40%					31.202
62.000	PS3032	15 Summer	10	+40%					31.350
61.003	PS1939	15 Summer	10	+40%					30.846
63.000	PS1935	15 Summer	10	+40%					31.495
64.000	PS1933	15 Summer	10	+40%					31.483
63.001	PS1932	15 Summer	10	+40%					31.436
19.013	S55	15 Winter	10	+40%	10/15 Summer				30.782
65.000	PS1550	15 Summer	10	+40%					39.202
65.001	PS1549	15 Summer	10	+40%					39.003
66.000	PS1553	15 Summer	10	+40%					39.374
65.002	S57	15 Summer	10	+40%					38.129
65.003	S58	15 Summer	10	+40%					37.762
67.000	PS1541	15 Summer	10	+40%					38.210
67.001	PS1540	15 Summer	10	+40%					37.866
65.004	S2713	15 Summer	10	+40%					37.007
65.005	S2719	15 Summer	10	+40%					36.695
68.000	PS2148	15 Summer	10	+40%					36.761
65.006	S60	15 Summer	10	+40%					36.177
69.000	PS2836	15 Summer	10	+40%					34.468
69.001	PS2129	15 Summer	10	+40%					34.369
69.002	PS2128	15 Summer	10	+40%					34.220
65.007	S62	15 Summer	10	+40%					33.691
70.000	PS2114	15 Summer	10	+40%					33.621
70.001	PS2838	15 Summer	10	+40%					33.491
70.002	PS2884	15 Summer	10	+40%					33.240
71.000	PS2105	15 Summer	10	+40%					32.900
70.003	PS2103	15 Summer	10	+40%					32.810
72.000	PS2100	15 Summer	10	+40%					32.192
70.004	PS2099	15 Summer	10	+40%					32.106
65.008	S63	15 Summer	10	+40%					31.525
73.000	PS1928	15 Summer	10	+40%					30.884
73.001	PS1930	15 Summer	10	+40%					30.860
19.014	S56	15 Winter	10	+40%	10/15 Summer				30.652
19.015	S2711	15 Winter	10	+40%	10/15 Summer				30.475
19.016	PS2921	15 Winter	10	+40%					30.130
19.017	PS2920	15 Winter	10	+40%					29.738
19.018	PS2919	15 Winter	10	+40%					29.129

©1982-2020

Innovyze

Paul Basham Associates					Page 32				
Lancaster Court Fareham Hampshire, PO15 5TU			189.5005 ANGMERING PHASE 2 NE 10% AEP +40% CC						
Date 08/10/2025 File 251007_NE PHASE 2.MDX			Designed by LEC Checked by COH						
Innovyze			Network 2020.1.3						
Summary of Critical Results by Maximum Level (Rank 1) for Surface Network 5									
PN	US/MH Name	Depth (m)	Volume (m³)	Flow / Cap.	Overflow (l/s)	Half Drain Time (mins)	Pipe Flow (l/s)	Status	Level Exceeded
57.000	PS2179	-0.100	0.000	0.00			0.0	OK	
55.002	PS2178	-0.120	0.000	0.09			6.0	OK	
19.011	S2718	0.389	0.000	1.45			319.5	SURCHARGED	
58.000	PS2885	-0.059	0.000	0.34			2.8	OK	
58.001	PS1994	-0.075	0.000	0.14			2.8	OK	
19.012	S53	0.361	0.000	1.12			340.2	SURCHARGED	
59.000	PS1975	-0.072	0.000	0.18			2.4	OK	
59.001	PS1974	-0.031	0.000	0.96			18.3	OK	
60.000	PS1969	-0.100	0.000	0.00			0.0	OK	
59.002	PS1968	0.057	0.000	0.29			20.6	SURCHARGED	
61.000	PS2864	-0.100	0.000	0.00			0.0	OK	
61.001	PS2865	-0.100	0.000	0.00			0.0	OK	
61.002	PS1963	-0.068	0.000	0.22			2.1	OK	
62.000	PS3032	-0.100	0.000	0.00			0.0	OK	
61.003	PS1939	-0.124	0.000	0.07			2.1	OK	
63.000	PS1935	-0.100	0.000	0.00			0.0	OK	
64.000	PS1933	-0.100	0.000	0.00			0.0	OK	
63.001	PS1932	-0.100	0.000	0.00			0.0	OK	
19.013	S55	0.312	0.000	1.16			359.9	SURCHARGED	
65.000	PS1550	-0.100	0.000	0.00			0.0	OK	
65.001	PS1549	-0.100	0.000	0.00			0.0	OK	
66.000	PS1553	-0.100	0.000	0.00			0.0	OK	
65.002	S57	-0.073	0.000	0.52			15.5	OK	
65.003	S58	-0.056	0.000	0.70			21.0	OK	
67.000	PS1541	-0.047	0.000	0.54			5.4	FLOOD RISK	
67.001	PS1540	-0.064	0.000	0.27			5.3	OK	
65.004	S2713	-0.134	0.000	0.34			26.3	OK	
65.005	S2719	-0.144	0.000	0.28			26.1	OK	
68.000	PS2148	-0.100	0.000	0.00			0.0	OK	
65.006	S60	-0.194	0.000	0.27			68.7	OK	
69.000	PS2836	-0.100	0.000	0.00			0.0	OK	
69.001	PS2129	-0.100	0.000	0.00			0.0	OK	
69.002	PS2128	-0.100	0.000	0.00			0.0	OK	
65.007	S62	-0.263	0.000	0.19			84.1	OK	
70.000	PS2114	-0.100	0.000	0.00			0.0	OK	
70.001	PS2838	-0.100	0.000	0.00			0.0	OK	
70.002	PS2884	-0.100	0.000	0.00			0.0	OK	
71.000	PS2105	-0.100	0.000	0.00			0.0	OK	
70.003	PS2103	-0.150	0.000	0.00			0.0	OK	
72.000	PS2100	-0.100	0.000	0.00			0.0	OK	
70.004	PS2099	-0.124	0.000	0.07			2.8	OK	
65.008	S63	-0.246	0.000	0.25			104.3	OK	
73.000	PS1928	-0.100	0.000	0.00			0.0	OK	
73.001	PS1930	-0.060	0.000	0.34			4.9	OK	
19.014	S56	0.256	0.000	1.89			418.4	SURCHARGED	
19.015	S2711	0.120	0.000	2.22			422.2	SURCHARGED	
19.016	PS2921	-0.600	0.000	0.09			422.8	OK	
19.017	PS2920	-0.639	0.000	0.07			430.0	OK	
©1982-2020 Innovyze									

Paul Basham Associates		Page 33
Lancaster Court	189.5005 ANGMERING	
Fareham	PHASE 2 NE	
Hampshire, PO15 5TU	10% AEP +40% CC	
Date 08/10/2025	Designed by LEC	
File 251007_NE PHASE 2.MDX	Checked by COH	
Innovyze	Network 2020.1.3	

Summary of Critical Results by Maximum Level (Rank 1) for Surface Network 5

PN	US/MH Name	Surcharged	Flooded	Flow / Cap.	Overflow (l/s)	Half Drain	Pipe	Status	Level
		Depth (m)	Volume (m³)			Time (mins)	Flow (l/s)		Exceeded
19.018	PS2919	-0.654	0.000	0.06			430.8	OK	

©1982-2020 Innovyze

