

The Civil Engineering Practice										Page 1																																																																																																																																																																																																																
11 Tungsten Building George Street Fishersgate BN41 1RA					Manor Nursery Angmering West Sussex																																																																																																																																																																																																																					
Date 28/06/2019					Designed by S Burgess																																																																																																																																																																																																																					
File Planning Network File.MDX					Checked by SRD																																																																																																																																																																																																																					
Innovyze					Network 2017.1.2																																																																																																																																																																																																																					
<u>STORM SEWER DESIGN by the Modified Rational Method</u> <u>Design Criteria for NETWORK 6.SWS</u> Pipe Sizes NETWORK 9 Manhole Sizes NETWORK 9 FSR Rainfall Model - England and Wales <table><tr><td>Return Period (years)</td><td>2</td><td>PIMP (%)</td><td>100</td></tr><tr><td>M5-60 (mm)</td><td>19.600</td><td>Add Flow / Climate Change (%)</td><td>0</td></tr><tr><td>Ratio R</td><td>0.350</td><td>Minimum Backdrop Height (m)</td><td>0.500</td></tr><tr><td>Maximum Rainfall (mm/hr)</td><td>50</td><td>Maximum Backdrop Height (m)</td><td>1.000</td></tr><tr><td>Maximum Time of Concentration (mins)</td><td>30</td><td>Min Design Depth for Optimisation (m)</td><td>1.200</td></tr><tr><td>Foul Sewage (l/s/ha)</td><td>0.000</td><td>Min Vel for Auto Design only (m/s)</td><td>0.75</td></tr><tr><td>Volumetric Runoff Coeff.</td><td>0.750</td><td>Min Slope for Optimisation (1:X)</td><td>500</td></tr></table> Designed with Level Soffits												Return Period (years)	2	PIMP (%)	100	M5-60 (mm)	19.600	Add Flow / Climate Change (%)	0	Ratio R	0.350	Minimum Backdrop Height (m)	0.500	Maximum Rainfall (mm/hr)	50	Maximum Backdrop Height (m)	1.000	Maximum Time of Concentration (mins)	30	Min Design Depth for Optimisation (m)	1.200	Foul Sewage (l/s/ha)	0.000	Min Vel for Auto Design only (m/s)	0.75	Volumetric Runoff Coeff.	0.750	Min Slope for Optimisation (1:X)	500																																																																																																																																																																																			
Return Period (years)	2	PIMP (%)	100																																																																																																																																																																																																																							
M5-60 (mm)	19.600	Add Flow / Climate Change (%)	0																																																																																																																																																																																																																							
Ratio R	0.350	Minimum Backdrop Height (m)	0.500																																																																																																																																																																																																																							
Maximum Rainfall (mm/hr)	50	Maximum Backdrop Height (m)	1.000																																																																																																																																																																																																																							
Maximum Time of Concentration (mins)	30	Min Design Depth for Optimisation (m)	1.200																																																																																																																																																																																																																							
Foul Sewage (l/s/ha)	0.000	Min Vel for Auto Design only (m/s)	0.75																																																																																																																																																																																																																							
Volumetric Runoff Coeff.	0.750	Min Slope for Optimisation (1:X)	500																																																																																																																																																																																																																							
<u>Network Design Table for NETWORK 6.SWS</u> <table><tr><th>PN</th><th>Length (m)</th><th>Fall (m)</th><th>Slope (1:X)</th><th>I.Area (ha)</th><th>T.E. (mins)</th><th>Base Flow (l/s)</th><th>k (mm)</th><th>HYD SECT</th><th>DIA (mm)</th><th>Section Type</th><th>Auto Design</th></tr><tr><td>1.000</td><td>13.024</td><td>0.127</td><td>103.0</td><td>0.000</td><td>5.00</td><td>0.0</td><td>0.600</td><td>o</td><td>100</td><td>Pipe/Conduit</td><td></td></tr><tr><td>1.001</td><td>10.052</td><td>0.098</td><td>103.0</td><td>0.004</td><td>0.00</td><td>0.0</td><td>0.600</td><td>o</td><td>100</td><td>Pipe/Conduit</td><td></td></tr><tr><td>2.000</td><td>14.867</td><td>0.224</td><td>66.3</td><td>0.004</td><td>5.00</td><td>0.0</td><td>0.600</td><td>o</td><td>100</td><td>Pipe/Conduit</td><td></td></tr><tr><td>1.002</td><td>1.369</td><td>0.013</td><td>103.0</td><td>0.000</td><td>0.00</td><td>0.0</td><td>0.600</td><td>o</td><td>100</td><td>Pipe/Conduit</td><td></td></tr><tr><td>3.000</td><td>15.130</td><td>0.237</td><td>63.7</td><td>0.003</td><td>5.00</td><td>0.0</td><td>0.600</td><td>o</td><td>100</td><td>Pipe/Conduit</td><td></td></tr><tr><td>1.003</td><td>5.348</td><td>0.052</td><td>103.0</td><td>0.003</td><td>0.00</td><td>0.0</td><td>0.600</td><td>o</td><td>100</td><td>Pipe/Conduit</td><td></td></tr><tr><td>1.004</td><td>5.497</td><td>0.053</td><td>102.9</td><td>0.001</td><td>0.00</td><td>0.0</td><td>0.600</td><td>o</td><td>100</td><td>Pipe/Conduit</td><td></td></tr><tr><td>4.000</td><td>7.128</td><td>0.343</td><td>20.8</td><td>0.003</td><td>5.00</td><td>0.0</td><td>0.600</td><td>o</td><td>100</td><td>Pipe/Conduit</td><td></td></tr></table> <u>Network Results Table</u> <table><tr><th>PN</th><th>Rain (mm/hr)</th><th>T.C. (mins)</th><th>US/IL (m)</th><th>Σ I.Area (ha)</th><th>Σ Base Flow (l/s)</th><th>Foul (l/s)</th><th>Add Flow (l/s)</th><th>Vel (m/s)</th><th>Cap (l/s)</th><th>Flow (l/s)</th></tr><tr><td>1.000</td><td>50.00</td><td>5.29</td><td>15.650</td><td>0.000</td><td>0.0</td><td>0.0</td><td>0.0</td><td>0.76</td><td>5.9</td><td>0.0</td></tr><tr><td>1.001</td><td>50.00</td><td>5.51</td><td>15.524</td><td>0.004</td><td>0.0</td><td>0.0</td><td>0.0</td><td>0.76</td><td>5.9</td><td>0.5</td></tr><tr><td>2.000</td><td>50.00</td><td>5.26</td><td>15.650</td><td>0.004</td><td>0.0</td><td>0.0</td><td>0.0</td><td>0.95</td><td>7.4</td><td>0.5</td></tr><tr><td>1.002</td><td>50.00</td><td>5.54</td><td>15.426</td><td>0.008</td><td>0.0</td><td>0.0</td><td>0.0</td><td>0.76</td><td>5.9</td><td>1.1</td></tr><tr><td>3.000</td><td>50.00</td><td>5.26</td><td>15.650</td><td>0.003</td><td>0.0</td><td>0.0</td><td>0.0</td><td>0.97</td><td>7.6</td><td>0.4</td></tr><tr><td>1.003</td><td>50.00</td><td>5.66</td><td>15.413</td><td>0.014</td><td>0.0</td><td>0.0</td><td>0.0</td><td>0.76</td><td>5.9</td><td>1.9</td></tr><tr><td>1.004</td><td>50.00</td><td>5.78</td><td>15.361</td><td>0.015</td><td>0.0</td><td>0.0</td><td>0.0</td><td>0.76</td><td>6.0</td><td>2.0</td></tr><tr><td>4.000</td><td>50.00</td><td>5.07</td><td>15.650</td><td>0.003</td><td>0.0</td><td>0.0</td><td>0.0</td><td>1.70</td><td>13.4</td><td>0.4</td></tr></table> ©1982-2017 XP Solutions												PN	Length (m)	Fall (m)	Slope (1:X)	I.Area (ha)	T.E. (mins)	Base Flow (l/s)	k (mm)	HYD SECT	DIA (mm)	Section Type	Auto Design	1.000	13.024	0.127	103.0	0.000	5.00	0.0	0.600	o	100	Pipe/Conduit		1.001	10.052	0.098	103.0	0.004	0.00	0.0	0.600	o	100	Pipe/Conduit		2.000	14.867	0.224	66.3	0.004	5.00	0.0	0.600	o	100	Pipe/Conduit		1.002	1.369	0.013	103.0	0.000	0.00	0.0	0.600	o	100	Pipe/Conduit		3.000	15.130	0.237	63.7	0.003	5.00	0.0	0.600	o	100	Pipe/Conduit		1.003	5.348	0.052	103.0	0.003	0.00	0.0	0.600	o	100	Pipe/Conduit		1.004	5.497	0.053	102.9	0.001	0.00	0.0	0.600	o	100	Pipe/Conduit		4.000	7.128	0.343	20.8	0.003	5.00	0.0	0.600	o	100	Pipe/Conduit		PN	Rain (mm/hr)	T.C. (mins)	US/IL (m)	Σ I.Area (ha)	Σ Base Flow (l/s)	Foul (l/s)	Add Flow (l/s)	Vel (m/s)	Cap (l/s)	Flow (l/s)	1.000	50.00	5.29	15.650	0.000	0.0	0.0	0.0	0.76	5.9	0.0	1.001	50.00	5.51	15.524	0.004	0.0	0.0	0.0	0.76	5.9	0.5	2.000	50.00	5.26	15.650	0.004	0.0	0.0	0.0	0.95	7.4	0.5	1.002	50.00	5.54	15.426	0.008	0.0	0.0	0.0	0.76	5.9	1.1	3.000	50.00	5.26	15.650	0.003	0.0	0.0	0.0	0.97	7.6	0.4	1.003	50.00	5.66	15.413	0.014	0.0	0.0	0.0	0.76	5.9	1.9	1.004	50.00	5.78	15.361	0.015	0.0	0.0	0.0	0.76	6.0	2.0	4.000	50.00	5.07	15.650	0.003	0.0	0.0	0.0	1.70	13.4	0.4
PN	Length (m)	Fall (m)	Slope (1:X)	I.Area (ha)	T.E. (mins)	Base Flow (l/s)	k (mm)	HYD SECT	DIA (mm)	Section Type	Auto Design																																																																																																																																																																																																															
1.000	13.024	0.127	103.0	0.000	5.00	0.0	0.600	o	100	Pipe/Conduit																																																																																																																																																																																																																
1.001	10.052	0.098	103.0	0.004	0.00	0.0	0.600	o	100	Pipe/Conduit																																																																																																																																																																																																																
2.000	14.867	0.224	66.3	0.004	5.00	0.0	0.600	o	100	Pipe/Conduit																																																																																																																																																																																																																
1.002	1.369	0.013	103.0	0.000	0.00	0.0	0.600	o	100	Pipe/Conduit																																																																																																																																																																																																																
3.000	15.130	0.237	63.7	0.003	5.00	0.0	0.600	o	100	Pipe/Conduit																																																																																																																																																																																																																
1.003	5.348	0.052	103.0	0.003	0.00	0.0	0.600	o	100	Pipe/Conduit																																																																																																																																																																																																																
1.004	5.497	0.053	102.9	0.001	0.00	0.0	0.600	o	100	Pipe/Conduit																																																																																																																																																																																																																
4.000	7.128	0.343	20.8	0.003	5.00	0.0	0.600	o	100	Pipe/Conduit																																																																																																																																																																																																																
PN	Rain (mm/hr)	T.C. (mins)	US/IL (m)	Σ I.Area (ha)	Σ Base Flow (l/s)	Foul (l/s)	Add Flow (l/s)	Vel (m/s)	Cap (l/s)	Flow (l/s)																																																																																																																																																																																																																
1.000	50.00	5.29	15.650	0.000	0.0	0.0	0.0	0.76	5.9	0.0																																																																																																																																																																																																																
1.001	50.00	5.51	15.524	0.004	0.0	0.0	0.0	0.76	5.9	0.5																																																																																																																																																																																																																
2.000	50.00	5.26	15.650	0.004	0.0	0.0	0.0	0.95	7.4	0.5																																																																																																																																																																																																																
1.002	50.00	5.54	15.426	0.008	0.0	0.0	0.0	0.76	5.9	1.1																																																																																																																																																																																																																
3.000	50.00	5.26	15.650	0.003	0.0	0.0	0.0	0.97	7.6	0.4																																																																																																																																																																																																																
1.003	50.00	5.66	15.413	0.014	0.0	0.0	0.0	0.76	5.9	1.9																																																																																																																																																																																																																
1.004	50.00	5.78	15.361	0.015	0.0	0.0	0.0	0.76	6.0	2.0																																																																																																																																																																																																																
4.000	50.00	5.07	15.650	0.003	0.0	0.0	0.0	1.70	13.4	0.4																																																																																																																																																																																																																

The Civil Engineering Practice										Page 2																																																																						
11 Tungsten Building George Street Fishersgate BN41 1RA					Manor Nursery Angmering West Sussex																																																																											
Date 28/06/2019					Designed by S Burgess																																																																											
File Planning Network File.MDX					Checked by SRD																																																																											
Innovyze					Network 2017.1.2																																																																											
<u>Network Design Table for NETWORK 6.SWS</u> <table><tr><th>PN</th><th>Length (m)</th><th>Fall (m)</th><th>Slope (1:X)</th><th>I.Area (ha)</th><th>T.E. (mins)</th><th>Base Flow (l/s)</th><th>k (mm)</th><th>HYD SECT</th><th>DIA (mm)</th><th>Section Type</th><th>Auto Design</th></tr><tr><td>5.000</td><td>7.444</td><td>0.343</td><td>21.7</td><td>0.001</td><td>5.00</td><td>0.0</td><td>0.600</td><td>o</td><td>100</td><td>Pipe/Conduit</td><td></td></tr><tr><td>1.005</td><td>9.975</td><td>0.097</td><td>102.9</td><td>0.000</td><td>0.00</td><td>0.0</td><td>0.600</td><td>o</td><td>100</td><td>Pipe/Conduit</td><td></td></tr></table> <u>Network Results Table</u> <table><tr><th>PN</th><th>Rain (mm/hr)</th><th>T.C. (mins)</th><th>US/IL (m)</th><th>Σ I.Area (ha)</th><th>Σ Base Flow (l/s)</th><th>Foul (l/s)</th><th>Add Flow (l/s)</th><th>Vel (m/s)</th><th>Cap (l/s)</th><th>Flow (l/s)</th></tr><tr><td>5.000</td><td>50.00</td><td>5.07</td><td>15.650</td><td>0.001</td><td>0.0</td><td>0.0</td><td>0.0</td><td>1.66</td><td>13.1</td><td>0.1</td></tr><tr><td>1.005</td><td>50.00</td><td>6.00</td><td>15.307</td><td>0.019</td><td>0.0</td><td>0.0</td><td>0.0</td><td>0.76</td><td>6.0</td><td>2.6</td></tr></table>												PN	Length (m)	Fall (m)	Slope (1:X)	I.Area (ha)	T.E. (mins)	Base Flow (l/s)	k (mm)	HYD SECT	DIA (mm)	Section Type	Auto Design	5.000	7.444	0.343	21.7	0.001	5.00	0.0	0.600	o	100	Pipe/Conduit		1.005	9.975	0.097	102.9	0.000	0.00	0.0	0.600	o	100	Pipe/Conduit		PN	Rain (mm/hr)	T.C. (mins)	US/IL (m)	Σ I.Area (ha)	Σ Base Flow (l/s)	Foul (l/s)	Add Flow (l/s)	Vel (m/s)	Cap (l/s)	Flow (l/s)	5.000	50.00	5.07	15.650	0.001	0.0	0.0	0.0	1.66	13.1	0.1	1.005	50.00	6.00	15.307	0.019	0.0	0.0	0.0	0.76	6.0	2.6
PN	Length (m)	Fall (m)	Slope (1:X)	I.Area (ha)	T.E. (mins)	Base Flow (l/s)	k (mm)	HYD SECT	DIA (mm)	Section Type	Auto Design																																																																					
5.000	7.444	0.343	21.7	0.001	5.00	0.0	0.600	o	100	Pipe/Conduit																																																																						
1.005	9.975	0.097	102.9	0.000	0.00	0.0	0.600	o	100	Pipe/Conduit																																																																						
PN	Rain (mm/hr)	T.C. (mins)	US/IL (m)	Σ I.Area (ha)	Σ Base Flow (l/s)	Foul (l/s)	Add Flow (l/s)	Vel (m/s)	Cap (l/s)	Flow (l/s)																																																																						
5.000	50.00	5.07	15.650	0.001	0.0	0.0	0.0	1.66	13.1	0.1																																																																						
1.005	50.00	6.00	15.307	0.019	0.0	0.0	0.0	0.76	6.0	2.6																																																																						
©1982-2017 XP Solutions																																																																																

The Civil Engineering Practice								Page 3																																																																																																																																																																																																						
11 Tungsten Building George Street Fishersgate BN41 1RA				Manor Nursery Angmering West Sussex																																																																																																																																																																																																										
Date 28/06/2019 File Planning Network File.MDX				Designed by S Burgess Checked by SRD																																																																																																																																																																																																										
Innovyze				Network 2017.1.2																																																																																																																																																																																																										
<u>PIPELINE SCHEDULES for NETWORK 6.SWS</u> <u>Upstream Manhole</u> <table><tr><th>PN</th><th>Hyd Sect</th><th>Diam (mm)</th><th>MH Name</th><th>C.Level (m)</th><th>I.Level (m)</th><th>D.Depth (m)</th><th>MH Connection</th><th>MH DIAM., L*W (mm)</th></tr><tr><td>1.000</td><td>o</td><td>100</td><td>1</td><td>16.250</td><td>15.650</td><td>0.500</td><td>Open Manhole</td><td>1200</td></tr><tr><td>1.001</td><td>o</td><td>100</td><td>2</td><td>16.250</td><td>15.524</td><td>0.627</td><td>Open Manhole</td><td>1200</td></tr><tr><td>2.000</td><td>o</td><td>100</td><td>8</td><td>16.250</td><td>15.650</td><td>0.500</td><td>Open Manhole</td><td>1200</td></tr><tr><td>1.002</td><td>o</td><td>100</td><td>3</td><td>16.250</td><td>15.426</td><td>0.724</td><td>Open Manhole</td><td>1200</td></tr><tr><td>3.000</td><td>o</td><td>100</td><td>9</td><td>16.250</td><td>15.650</td><td>0.500</td><td>Open Manhole</td><td>1200</td></tr><tr><td>1.003</td><td>o</td><td>100</td><td>4</td><td>16.250</td><td>15.413</td><td>0.737</td><td>Open Manhole</td><td>1200</td></tr><tr><td>1.004</td><td>o</td><td>100</td><td>5</td><td>16.250</td><td>15.361</td><td>0.789</td><td>Open Manhole</td><td>1200</td></tr><tr><td>4.000</td><td>o</td><td>100</td><td>10</td><td>16.250</td><td>15.650</td><td>0.500</td><td>Open Manhole</td><td>1200</td></tr><tr><td>5.000</td><td>o</td><td>100</td><td>11</td><td>16.250</td><td>15.650</td><td>0.500</td><td>Open Manhole</td><td>1200</td></tr><tr><td>1.005</td><td>o</td><td>100</td><td>6</td><td>16.250</td><td>15.307</td><td>0.843</td><td>Open Manhole</td><td>1200</td></tr></table> <u>Downstream Manhole</u> <table><tr><th>PN</th><th>Length (m)</th><th>Slope (1:X)</th><th>MH Name</th><th>C.Level (m)</th><th>I.Level (m)</th><th>D.Depth (m)</th><th>MH Connection</th><th>MH DIAM., L*W (mm)</th></tr><tr><td>1.000</td><td>13.024</td><td>103.0</td><td>2</td><td>16.250</td><td>15.524</td><td>0.627</td><td>Open Manhole</td><td>1200</td></tr><tr><td>1.001</td><td>10.052</td><td>103.0</td><td>3</td><td>16.250</td><td>15.426</td><td>0.724</td><td>Open Manhole</td><td>1200</td></tr><tr><td>2.000</td><td>14.867</td><td>66.3</td><td>3</td><td>16.250</td><td>15.426</td><td>0.724</td><td>Open Manhole</td><td>1200</td></tr><tr><td>1.002</td><td>1.369</td><td>103.0</td><td>4</td><td>16.250</td><td>15.413</td><td>0.737</td><td>Open Manhole</td><td>1200</td></tr><tr><td>3.000</td><td>15.130</td><td>63.7</td><td>4</td><td>16.250</td><td>15.413</td><td>0.737</td><td>Open Manhole</td><td>1200</td></tr><tr><td>1.003</td><td>5.348</td><td>103.0</td><td>5</td><td>16.250</td><td>15.361</td><td>0.789</td><td>Open Manhole</td><td>1200</td></tr><tr><td>1.004</td><td>5.497</td><td>102.9</td><td>6</td><td>16.250</td><td>15.307</td><td>0.843</td><td>Open Manhole</td><td>1200</td></tr><tr><td>4.000</td><td>7.128</td><td>20.8</td><td>6</td><td>16.250</td><td>15.307</td><td>0.843</td><td>Open Manhole</td><td>1200</td></tr><tr><td>5.000</td><td>7.444</td><td>21.7</td><td>6</td><td>16.250</td><td>15.307</td><td>0.843</td><td>Open Manhole</td><td>1200</td></tr><tr><td>1.005</td><td>9.975</td><td>102.9</td><td>7</td><td>16.300</td><td>15.210</td><td>0.990</td><td>Open Manhole</td><td>0</td></tr></table>									PN	Hyd Sect	Diam (mm)	MH Name	C.Level (m)	I.Level (m)	D.Depth (m)	MH Connection	MH DIAM., L*W (mm)	1.000	o	100	1	16.250	15.650	0.500	Open Manhole	1200	1.001	o	100	2	16.250	15.524	0.627	Open Manhole	1200	2.000	o	100	8	16.250	15.650	0.500	Open Manhole	1200	1.002	o	100	3	16.250	15.426	0.724	Open Manhole	1200	3.000	o	100	9	16.250	15.650	0.500	Open Manhole	1200	1.003	o	100	4	16.250	15.413	0.737	Open Manhole	1200	1.004	o	100	5	16.250	15.361	0.789	Open Manhole	1200	4.000	o	100	10	16.250	15.650	0.500	Open Manhole	1200	5.000	o	100	11	16.250	15.650	0.500	Open Manhole	1200	1.005	o	100	6	16.250	15.307	0.843	Open Manhole	1200	PN	Length (m)	Slope (1:X)	MH Name	C.Level (m)	I.Level (m)	D.Depth (m)	MH Connection	MH DIAM., L*W (mm)	1.000	13.024	103.0	2	16.250	15.524	0.627	Open Manhole	1200	1.001	10.052	103.0	3	16.250	15.426	0.724	Open Manhole	1200	2.000	14.867	66.3	3	16.250	15.426	0.724	Open Manhole	1200	1.002	1.369	103.0	4	16.250	15.413	0.737	Open Manhole	1200	3.000	15.130	63.7	4	16.250	15.413	0.737	Open Manhole	1200	1.003	5.348	103.0	5	16.250	15.361	0.789	Open Manhole	1200	1.004	5.497	102.9	6	16.250	15.307	0.843	Open Manhole	1200	4.000	7.128	20.8	6	16.250	15.307	0.843	Open Manhole	1200	5.000	7.444	21.7	6	16.250	15.307	0.843	Open Manhole	1200	1.005	9.975	102.9	7	16.300	15.210	0.990	Open Manhole	0
PN	Hyd Sect	Diam (mm)	MH Name	C.Level (m)	I.Level (m)	D.Depth (m)	MH Connection	MH DIAM., L*W (mm)																																																																																																																																																																																																						
1.000	o	100	1	16.250	15.650	0.500	Open Manhole	1200																																																																																																																																																																																																						
1.001	o	100	2	16.250	15.524	0.627	Open Manhole	1200																																																																																																																																																																																																						
2.000	o	100	8	16.250	15.650	0.500	Open Manhole	1200																																																																																																																																																																																																						
1.002	o	100	3	16.250	15.426	0.724	Open Manhole	1200																																																																																																																																																																																																						
3.000	o	100	9	16.250	15.650	0.500	Open Manhole	1200																																																																																																																																																																																																						
1.003	o	100	4	16.250	15.413	0.737	Open Manhole	1200																																																																																																																																																																																																						
1.004	o	100	5	16.250	15.361	0.789	Open Manhole	1200																																																																																																																																																																																																						
4.000	o	100	10	16.250	15.650	0.500	Open Manhole	1200																																																																																																																																																																																																						
5.000	o	100	11	16.250	15.650	0.500	Open Manhole	1200																																																																																																																																																																																																						
1.005	o	100	6	16.250	15.307	0.843	Open Manhole	1200																																																																																																																																																																																																						
PN	Length (m)	Slope (1:X)	MH Name	C.Level (m)	I.Level (m)	D.Depth (m)	MH Connection	MH DIAM., L*W (mm)																																																																																																																																																																																																						
1.000	13.024	103.0	2	16.250	15.524	0.627	Open Manhole	1200																																																																																																																																																																																																						
1.001	10.052	103.0	3	16.250	15.426	0.724	Open Manhole	1200																																																																																																																																																																																																						
2.000	14.867	66.3	3	16.250	15.426	0.724	Open Manhole	1200																																																																																																																																																																																																						
1.002	1.369	103.0	4	16.250	15.413	0.737	Open Manhole	1200																																																																																																																																																																																																						
3.000	15.130	63.7	4	16.250	15.413	0.737	Open Manhole	1200																																																																																																																																																																																																						
1.003	5.348	103.0	5	16.250	15.361	0.789	Open Manhole	1200																																																																																																																																																																																																						
1.004	5.497	102.9	6	16.250	15.307	0.843	Open Manhole	1200																																																																																																																																																																																																						
4.000	7.128	20.8	6	16.250	15.307	0.843	Open Manhole	1200																																																																																																																																																																																																						
5.000	7.444	21.7	6	16.250	15.307	0.843	Open Manhole	1200																																																																																																																																																																																																						
1.005	9.975	102.9	7	16.300	15.210	0.990	Open Manhole	0																																																																																																																																																																																																						
©1982-2017 XP Solutions																																																																																																																																																																																																														

The Civil Engineering Practice							Page 4																																																																																																																																			
11 Tungsten Building George Street Fishersgate BN41 1RA				Manor Nursery Angmering West Sussex																																																																																																																																						
Date 28/06/2019 File Planning Network File.MDX				Designed by S Burgess Checked by SRD																																																																																																																																						
Innovyze				Network 2017.1.2																																																																																																																																						
<u>Summary of Critical Results by Maximum Level (Rank 1) for NETWORK 6.SWS</u>																																																																																																																																										
<u>Simulation Criteria</u>																																																																																																																																										
Areal Reduction Factor 1.000			Additional Flow - % of Total Flow 0.000																																																																																																																																							
Hot Start (mins) 0			MADD Factor * 10m³/ha Storage 2.000																																																																																																																																							
Hot Start Level (mm) 0			Inlet Coefficient 0.800																																																																																																																																							
Manhole Headloss Coeff (Global) 0.500			Flow per Person per Day (l/per/day) 0.000																																																																																																																																							
Foul Sewage per hectare (l/s) 0.000																																																																																																																																										
Number of Input Hydrographs 0			Number of Storage Structures 0																																																																																																																																							
Number of Online Controls 0			Number of Time/Area Diagrams 0																																																																																																																																							
Number of Offline Controls 0			Number of Real Time Controls 0																																																																																																																																							
<u>Synthetic Rainfall Details</u>																																																																																																																																										
Rainfall Model			FSR		Ratio R 0.350																																																																																																																																					
Region England and Wales			Cv (Summer) 0.750																																																																																																																																							
M5-60 (mm)			19.500		Cv (Winter) 0.840																																																																																																																																					
Margin for Flood Risk Warning (mm) 300.0			DVD Status OFF																																																																																																																																							
Analysis Timestep			Fine Inertia Status OFF																																																																																																																																							
DTS Status			ON																																																																																																																																							
Profile(s)			Summer and Winter																																																																																																																																							
Duration(s) (mins)			15, 30, 60, 120, 240, 360, 480, 960, 1440																																																																																																																																							
Return Period(s) (years)			100																																																																																																																																							
Climate Change (%)			40																																																																																																																																							
<table><tr><td></td><td>US/MH</td><td></td><td>Return</td><td>Climate</td><td>First (X)</td><td>First (Y)</td><td>First (Z)</td><td>Overflow</td><td>Water</td></tr><tr><td>PN</td><td>Name</td><td>Storm</td><td>Period</td><td>Change</td><td>Surcharge</td><td>Flood</td><td>Overflow</td><td>Act.</td><td>Level</td></tr><tr><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td>(m)</td></tr><tr><td>1.000</td><td>1</td><td>60 Winter</td><td>100</td><td>+40%</td><td></td><td></td><td></td><td></td><td>15.650</td></tr><tr><td>1.001</td><td>2</td><td>15 Winter</td><td>100</td><td>+40%</td><td>100/15 Winter</td><td></td><td></td><td></td><td>15.633</td></tr><tr><td>2.000</td><td>8</td><td>15 Winter</td><td>100</td><td>+40%</td><td></td><td></td><td></td><td></td><td>15.689</td></tr><tr><td>1.002</td><td>3</td><td>15 Winter</td><td>100</td><td>+40%</td><td>100/15 Summer</td><td></td><td></td><td></td><td>15.622</td></tr><tr><td>3.000</td><td>9</td><td>15 Winter</td><td>100</td><td>+40%</td><td></td><td></td><td></td><td></td><td>15.683</td></tr><tr><td>1.003</td><td>4</td><td>15 Winter</td><td>100</td><td>+40%</td><td>100/15 Summer</td><td></td><td></td><td></td><td>15.614</td></tr><tr><td>1.004</td><td>5</td><td>15 Winter</td><td>100</td><td>+40%</td><td>100/15 Summer</td><td></td><td></td><td></td><td>15.556</td></tr><tr><td>4.000</td><td>10</td><td>15 Winter</td><td>100</td><td>+40%</td><td></td><td></td><td></td><td></td><td>15.675</td></tr><tr><td>5.000</td><td>11</td><td>15 Winter</td><td>100</td><td>+40%</td><td></td><td></td><td></td><td></td><td>15.664</td></tr><tr><td>1.005</td><td>6</td><td>15 Winter</td><td>100</td><td>+40%</td><td>100/15 Summer</td><td></td><td></td><td></td><td>15.489</td></tr></table>										US/MH		Return	Climate	First (X)	First (Y)	First (Z)	Overflow	Water	PN	Name	Storm	Period	Change	Surcharge	Flood	Overflow	Act.	Level										(m)	1.000	1	60 Winter	100	+40%					15.650	1.001	2	15 Winter	100	+40%	100/15 Winter				15.633	2.000	8	15 Winter	100	+40%					15.689	1.002	3	15 Winter	100	+40%	100/15 Summer				15.622	3.000	9	15 Winter	100	+40%					15.683	1.003	4	15 Winter	100	+40%	100/15 Summer				15.614	1.004	5	15 Winter	100	+40%	100/15 Summer				15.556	4.000	10	15 Winter	100	+40%					15.675	5.000	11	15 Winter	100	+40%					15.664	1.005	6	15 Winter	100	+40%	100/15 Summer				15.489
	US/MH		Return	Climate	First (X)	First (Y)	First (Z)	Overflow	Water																																																																																																																																	
PN	Name	Storm	Period	Change	Surcharge	Flood	Overflow	Act.	Level																																																																																																																																	
									(m)																																																																																																																																	
1.000	1	60 Winter	100	+40%					15.650																																																																																																																																	
1.001	2	15 Winter	100	+40%	100/15 Winter				15.633																																																																																																																																	
2.000	8	15 Winter	100	+40%					15.689																																																																																																																																	
1.002	3	15 Winter	100	+40%	100/15 Summer				15.622																																																																																																																																	
3.000	9	15 Winter	100	+40%					15.683																																																																																																																																	
1.003	4	15 Winter	100	+40%	100/15 Summer				15.614																																																																																																																																	
1.004	5	15 Winter	100	+40%	100/15 Summer				15.556																																																																																																																																	
4.000	10	15 Winter	100	+40%					15.675																																																																																																																																	
5.000	11	15 Winter	100	+40%					15.664																																																																																																																																	
1.005	6	15 Winter	100	+40%	100/15 Summer				15.489																																																																																																																																	
<table><tr><td></td><td>US/MH</td><td></td><td>Depth</td><td>Volume</td><td>Flow / Overflow</td><td>Pipe</td><td></td><td>Level</td></tr><tr><td>PN</td><td>Name</td><td></td><td>(m)</td><td>(m³)</td><td>Cap. (l/s)</td><td>Flow (l/s)</td><td>Status</td><td>Exceeded</td></tr><tr><td>1.000</td><td>1</td><td></td><td>-0.100</td><td>0.000</td><td>0.00</td><td>0.0</td><td>OK</td><td></td></tr><tr><td>1.001</td><td>2</td><td></td><td>0.010</td><td>0.000</td><td>0.42</td><td>2.3</td><td>SURCHARGED</td><td></td></tr><tr><td>2.000</td><td>8</td><td></td><td>-0.061</td><td>0.000</td><td>0.32</td><td>2.3</td><td>OK</td><td></td></tr><tr><td>1.002</td><td>3</td><td></td><td>0.096</td><td>0.000</td><td>0.82</td><td>3.2</td><td>SURCHARGED</td><td></td></tr><tr><td>3.000</td><td>9</td><td></td><td>-0.067</td><td>0.000</td><td>0.23</td><td>1.7</td><td>OK</td><td></td></tr><tr><td>1.003</td><td>4</td><td></td><td>0.102</td><td>0.000</td><td>1.06</td><td>5.5</td><td>SURCHARGED</td><td></td></tr></table>										US/MH		Depth	Volume	Flow / Overflow	Pipe		Level	PN	Name		(m)	(m³)	Cap. (l/s)	Flow (l/s)	Status	Exceeded	1.000	1		-0.100	0.000	0.00	0.0	OK		1.001	2		0.010	0.000	0.42	2.3	SURCHARGED		2.000	8		-0.061	0.000	0.32	2.3	OK		1.002	3		0.096	0.000	0.82	3.2	SURCHARGED		3.000	9		-0.067	0.000	0.23	1.7	OK		1.003	4		0.102	0.000	1.06	5.5	SURCHARGED																																																											
	US/MH		Depth	Volume	Flow / Overflow	Pipe		Level																																																																																																																																		
PN	Name		(m)	(m³)	Cap. (l/s)	Flow (l/s)	Status	Exceeded																																																																																																																																		
1.000	1		-0.100	0.000	0.00	0.0	OK																																																																																																																																			
1.001	2		0.010	0.000	0.42	2.3	SURCHARGED																																																																																																																																			
2.000	8		-0.061	0.000	0.32	2.3	OK																																																																																																																																			
1.002	3		0.096	0.000	0.82	3.2	SURCHARGED																																																																																																																																			
3.000	9		-0.067	0.000	0.23	1.7	OK																																																																																																																																			
1.003	4		0.102	0.000	1.06	5.5	SURCHARGED																																																																																																																																			
©1982-2017 XP Solutions																																																																																																																																										

The Civil Engineering Practice						Page 5	
11 Tungsten Building George Street Fishersgate BN41 1RA				Manor Nursery Angmering West Sussex			
Date 28/06/2019				Designed by S Burgess			
File Planning Network File.MDX				Checked by SRD			
Innovyze				Network 2017.1.2			
<u>Summary of Critical Results by Maximum Level (Rank 1) for NETWORK 6.SWS</u>							
		Surcharged Flooded			Pipe		
	US/MH	Depth	Volume	Flow / Overflow	Flow		Level
PN	Name	(m)	(m³)	Cap.	(l/s)	(l/s)	Status Exceeded
1.004	5	0.096	0.000	1.12		5.9	SURCHARGED
4.000	10	-0.075	0.000	0.14		1.7	OK
5.000	11	-0.086	0.000	0.05		0.6	OK
1.005	6	0.082	0.000	1.37		7.6	SURCHARGED
©1982-2017 XP Solutions							