

The Civil Engineering Practice					Page 1																																																																																																																																																																																																																			
11 Tungsten Building George Street Fishersgate BN41 1RA			Manor Nursery Angmering West Sussex																																																																																																																																																																																																																					
Date 23/09/2020 File Soakaway 4 Factor Safet...			Designed by S Burgess Checked by SRD																																																																																																																																																																																																																					
Innovyze			Source Control 2020.1																																																																																																																																																																																																																					
Summary of Results for 100 year Return Period (+40%) Half Drain Time : 345 minutes. <table><thead><tr><th>Storm Event</th><th>Max Level (m)</th><th>Max Depth (m)</th><th>Max Infiltration (l/s)</th><th>Max Volume (m³)</th><th>Status</th></tr></thead><tbody><tr><td>15 min Summer</td><td>14.837</td><td>0.937</td><td>0.4</td><td>6.9</td><td>0 K</td></tr><tr><td>30 min Summer</td><td>15.193</td><td>1.293</td><td>0.4</td><td>9.1</td><td>0 K</td></tr><tr><td>60 min Summer</td><td>15.547</td><td>1.647</td><td>0.4</td><td>11.3</td><td>0 K</td></tr><tr><td>120 min Summer</td><td>15.846</td><td>1.946</td><td>0.4</td><td>13.2</td><td>0 K</td></tr><tr><td>180 min Summer</td><td>15.955</td><td>2.055</td><td>0.4</td><td>13.9</td><td>0 K</td></tr><tr><td>240 min Summer</td><td>15.981</td><td>2.081</td><td>0.4</td><td>14.1</td><td>0 K</td></tr><tr><td>360 min Summer</td><td>15.970</td><td>2.070</td><td>0.4</td><td>14.0</td><td>0 K</td></tr><tr><td>480 min Summer</td><td>15.936</td><td>2.036</td><td>0.4</td><td>13.8</td><td>0 K</td></tr><tr><td>600 min Summer</td><td>15.890</td><td>1.990</td><td>0.4</td><td>13.5</td><td>0 K</td></tr><tr><td>720 min Summer</td><td>15.837</td><td>1.937</td><td>0.4</td><td>13.2</td><td>0 K</td></tr><tr><td>960 min Summer</td><td>15.719</td><td>1.819</td><td>0.4</td><td>12.4</td><td>0 K</td></tr><tr><td>1440 min Summer</td><td>15.475</td><td>1.575</td><td>0.4</td><td>10.9</td><td>0 K</td></tr><tr><td>2160 min Summer</td><td>15.136</td><td>1.236</td><td>0.4</td><td>8.8</td><td>0 K</td></tr><tr><td>2880 min Summer</td><td>14.847</td><td>0.947</td><td>0.4</td><td>6.9</td><td>0 K</td></tr><tr><td>4320 min Summer</td><td>14.439</td><td>0.539</td><td>0.4</td><td>4.4</td><td>0 K</td></tr><tr><td>5760 min Summer</td><td>14.244</td><td>0.344</td><td>0.4</td><td>3.1</td><td>0 K</td></tr><tr><td>7200 min Summer</td><td>14.196</td><td>0.296</td><td>0.3</td><td>2.7</td><td>0 K</td></tr><tr><td>8640 min Summer</td><td>14.161</td><td>0.261</td><td>0.3</td><td>2.4</td><td>0 K</td></tr><tr><td>10080 min Summer</td><td>14.134</td><td>0.234</td><td>0.3</td><td>2.1</td><td>0 K</td></tr><tr><td>15 min Winter</td><td>14.973</td><td>1.073</td><td>0.4</td><td>7.7</td><td>0 K</td></tr></tbody></table> <table><thead><tr><th>Storm Event</th><th>Rain (mm/hr)</th><th>Flooded Volume (m³)</th><th>Time-Peak (mins)</th></tr></thead><tbody><tr><td>15 min Summer</td><td>128.238</td><td>0.0</td><td>21</td></tr><tr><td>30 min Summer</td><td>86.178</td><td>0.0</td><td>35</td></tr><tr><td>60 min Summer</td><td>55.250</td><td>0.0</td><td>64</td></tr><tr><td>120 min Summer</td><td>34.177</td><td>0.0</td><td>122</td></tr><tr><td>180 min Summer</td><td>25.410</td><td>0.0</td><td>182</td></tr><tr><td>240 min Summer</td><td>20.436</td><td>0.0</td><td>240</td></tr><tr><td>360 min Summer</td><td>15.037</td><td>0.0</td><td>304</td></tr><tr><td>480 min Summer</td><td>12.081</td><td>0.0</td><td>366</td></tr><tr><td>600 min Summer</td><td>10.185</td><td>0.0</td><td>430</td></tr><tr><td>720 min Summer</td><td>8.854</td><td>0.0</td><td>498</td></tr><tr><td>960 min Summer</td><td>7.093</td><td>0.0</td><td>636</td></tr><tr><td>1440 min Summer</td><td>5.178</td><td>0.0</td><td>908</td></tr><tr><td>2160 min Summer</td><td>3.772</td><td>0.0</td><td>1296</td></tr><tr><td>2880 min Summer</td><td>3.009</td><td>0.0</td><td>1648</td></tr><tr><td>4320 min Summer</td><td>2.184</td><td>0.0</td><td>2336</td></tr><tr><td>5760 min Summer</td><td>1.738</td><td>0.0</td><td>2992</td></tr><tr><td>7200 min Summer</td><td>1.455</td><td>0.0</td><td>3680</td></tr><tr><td>8640 min Summer</td><td>1.260</td><td>0.0</td><td>4408</td></tr><tr><td>10080 min Summer</td><td>1.115</td><td>0.0</td><td>5144</td></tr><tr><td>15 min Winter</td><td>128.238</td><td>0.0</td><td>21</td></tr></tbody></table>							Storm Event	Max Level (m)	Max Depth (m)	Max Infiltration (l/s)	Max Volume (m³)	Status	15 min Summer	14.837	0.937	0.4	6.9	0 K	30 min Summer	15.193	1.293	0.4	9.1	0 K	60 min Summer	15.547	1.647	0.4	11.3	0 K	120 min Summer	15.846	1.946	0.4	13.2	0 K	180 min Summer	15.955	2.055	0.4	13.9	0 K	240 min Summer	15.981	2.081	0.4	14.1	0 K	360 min Summer	15.970	2.070	0.4	14.0	0 K	480 min Summer	15.936	2.036	0.4	13.8	0 K	600 min Summer	15.890	1.990	0.4	13.5	0 K	720 min Summer	15.837	1.937	0.4	13.2	0 K	960 min Summer	15.719	1.819	0.4	12.4	0 K	1440 min Summer	15.475	1.575	0.4	10.9	0 K	2160 min Summer	15.136	1.236	0.4	8.8	0 K	2880 min Summer	14.847	0.947	0.4	6.9	0 K	4320 min Summer	14.439	0.539	0.4	4.4	0 K	5760 min Summer	14.244	0.344	0.4	3.1	0 K	7200 min Summer	14.196	0.296	0.3	2.7	0 K	8640 min Summer	14.161	0.261	0.3	2.4	0 K	10080 min Summer	14.134	0.234	0.3	2.1	0 K	15 min Winter	14.973	1.073	0.4	7.7	0 K	Storm Event	Rain (mm/hr)	Flooded Volume (m³)	Time-Peak (mins)	15 min Summer	128.238	0.0	21	30 min Summer	86.178	0.0	35	60 min Summer	55.250	0.0	64	120 min Summer	34.177	0.0	122	180 min Summer	25.410	0.0	182	240 min Summer	20.436	0.0	240	360 min Summer	15.037	0.0	304	480 min Summer	12.081	0.0	366	600 min Summer	10.185	0.0	430	720 min Summer	8.854	0.0	498	960 min Summer	7.093	0.0	636	1440 min Summer	5.178	0.0	908	2160 min Summer	3.772	0.0	1296	2880 min Summer	3.009	0.0	1648	4320 min Summer	2.184	0.0	2336	5760 min Summer	1.738	0.0	2992	7200 min Summer	1.455	0.0	3680	8640 min Summer	1.260	0.0	4408	10080 min Summer	1.115	0.0	5144	15 min Winter	128.238	0.0	21
Storm Event	Max Level (m)	Max Depth (m)	Max Infiltration (l/s)	Max Volume (m³)	Status																																																																																																																																																																																																																			
15 min Summer	14.837	0.937	0.4	6.9	0 K																																																																																																																																																																																																																			
30 min Summer	15.193	1.293	0.4	9.1	0 K																																																																																																																																																																																																																			
60 min Summer	15.547	1.647	0.4	11.3	0 K																																																																																																																																																																																																																			
120 min Summer	15.846	1.946	0.4	13.2	0 K																																																																																																																																																																																																																			
180 min Summer	15.955	2.055	0.4	13.9	0 K																																																																																																																																																																																																																			
240 min Summer	15.981	2.081	0.4	14.1	0 K																																																																																																																																																																																																																			
360 min Summer	15.970	2.070	0.4	14.0	0 K																																																																																																																																																																																																																			
480 min Summer	15.936	2.036	0.4	13.8	0 K																																																																																																																																																																																																																			
600 min Summer	15.890	1.990	0.4	13.5	0 K																																																																																																																																																																																																																			
720 min Summer	15.837	1.937	0.4	13.2	0 K																																																																																																																																																																																																																			
960 min Summer	15.719	1.819	0.4	12.4	0 K																																																																																																																																																																																																																			
1440 min Summer	15.475	1.575	0.4	10.9	0 K																																																																																																																																																																																																																			
2160 min Summer	15.136	1.236	0.4	8.8	0 K																																																																																																																																																																																																																			
2880 min Summer	14.847	0.947	0.4	6.9	0 K																																																																																																																																																																																																																			
4320 min Summer	14.439	0.539	0.4	4.4	0 K																																																																																																																																																																																																																			
5760 min Summer	14.244	0.344	0.4	3.1	0 K																																																																																																																																																																																																																			
7200 min Summer	14.196	0.296	0.3	2.7	0 K																																																																																																																																																																																																																			
8640 min Summer	14.161	0.261	0.3	2.4	0 K																																																																																																																																																																																																																			
10080 min Summer	14.134	0.234	0.3	2.1	0 K																																																																																																																																																																																																																			
15 min Winter	14.973	1.073	0.4	7.7	0 K																																																																																																																																																																																																																			
Storm Event	Rain (mm/hr)	Flooded Volume (m³)	Time-Peak (mins)																																																																																																																																																																																																																					
15 min Summer	128.238	0.0	21																																																																																																																																																																																																																					
30 min Summer	86.178	0.0	35																																																																																																																																																																																																																					
60 min Summer	55.250	0.0	64																																																																																																																																																																																																																					
120 min Summer	34.177	0.0	122																																																																																																																																																																																																																					
180 min Summer	25.410	0.0	182																																																																																																																																																																																																																					
240 min Summer	20.436	0.0	240																																																																																																																																																																																																																					
360 min Summer	15.037	0.0	304																																																																																																																																																																																																																					
480 min Summer	12.081	0.0	366																																																																																																																																																																																																																					
600 min Summer	10.185	0.0	430																																																																																																																																																																																																																					
720 min Summer	8.854	0.0	498																																																																																																																																																																																																																					
960 min Summer	7.093	0.0	636																																																																																																																																																																																																																					
1440 min Summer	5.178	0.0	908																																																																																																																																																																																																																					
2160 min Summer	3.772	0.0	1296																																																																																																																																																																																																																					
2880 min Summer	3.009	0.0	1648																																																																																																																																																																																																																					
4320 min Summer	2.184	0.0	2336																																																																																																																																																																																																																					
5760 min Summer	1.738	0.0	2992																																																																																																																																																																																																																					
7200 min Summer	1.455	0.0	3680																																																																																																																																																																																																																					
8640 min Summer	1.260	0.0	4408																																																																																																																																																																																																																					
10080 min Summer	1.115	0.0	5144																																																																																																																																																																																																																					
15 min Winter	128.238	0.0	21																																																																																																																																																																																																																					
©1982-2020 Innovyze																																																																																																																																																																																																																								

The Civil Engineering Practice					Page 2
11 Tungsten Building George Street Fishersgate BN41 1RA		Manor Nursery Angmering West Sussex			
Date 23/09/2020 File Soakaway 4 Factor Safet...		Designed by S Burgess Checked by SRD			
Innovyze		Source Control 2020.1			
Summary of Results for 100 year Return Period (+40%)					
Storm Event	Max Level (m)	Max Depth (m)	Max Infiltration (l/s)	Max Volume (m³)	Status
30 min Winter	15.377	1.477	0.4	10.3	0 K
60 min Winter	15.781	1.881	0.4	12.8	0 K
120 min Winter	16.135	2.235	0.4	15.0	Flood Risk
180 min Winter	16.277	2.377	0.4	15.9	Flood Risk
240 min Winter	16.325	2.425	0.4	16.2	Flood Risk
360 min Winter	16.325	2.425	0.4	16.2	Flood Risk
480 min Winter	16.265	2.365	0.4	15.8	Flood Risk
600 min Winter	16.203	2.303	0.4	15.5	Flood Risk
720 min Winter	16.126	2.226	0.4	15.0	Flood Risk
960 min Winter	15.950	2.050	0.4	13.9	0 K
1440 min Winter	15.575	1.675	0.4	11.5	0 K
2160 min Winter	15.053	1.153	0.4	8.2	0 K
2880 min Winter	14.632	0.732	0.4	5.6	0 K
4320 min Winter	14.231	0.331	0.4	3.0	0 K
5760 min Winter	14.167	0.267	0.3	2.4	0 K
7200 min Winter	14.125	0.225	0.3	2.1	0 K
8640 min Winter	14.096	0.196	0.2	1.8	0 K
10080 min Winter	14.074	0.174	0.2	1.6	0 K
Storm Event	Rain (mm/hr)	Flooded Volume (m³)	Time-Peak (mins)		
30 min Winter	86.178	0.0	35		
60 min Winter	55.250	0.0	64		
120 min Winter	34.177	0.0	120		
180 min Winter	25.410	0.0	178		
240 min Winter	20.436	0.0	234		
360 min Winter	15.037	0.0	342		
480 min Winter	12.081	0.0	392		
600 min Winter	10.185	0.0	464		
720 min Winter	8.854	0.0	542		
960 min Winter	7.093	0.0	694		
1440 min Winter	5.178	0.0	982		
2160 min Winter	3.772	0.0	1368		
2880 min Winter	3.009	0.0	1728		
4320 min Winter	2.184	0.0	2288		
5760 min Winter	1.738	0.0	3000		
7200 min Winter	1.455	0.0	3744		
8640 min Winter	1.260	0.0	4416		
10080 min Winter	1.115	0.0	5144		
©1982-2020 Innovyze					

The Civil Engineering Practice		Page 3																																				
11 Tungsten Building George Street Fishersgate BN41 1RA	Manor Nursery Angmering West Sussex																																					
Date 23/09/2020	Designed by S Burgess																																					
File Soakaway 4 Factor Safet...	Checked by SRD																																					
Innovyze		Source Control 2020.1																																				
<u>Rainfall Details</u> <table> <tr> <td>Rainfall Model</td> <td>FSR</td> <td>Winter Storms</td> <td>Yes</td> </tr> <tr> <td>Return Period (years)</td> <td>100</td> <td>Cv (Summer)</td> <td>0.750</td> </tr> <tr> <td>Region</td> <td>England and Wales</td> <td>Cv (Winter)</td> <td>0.840</td> </tr> <tr> <td>M5-60 (mm)</td> <td>19.500</td> <td>Shortest Storm (mins)</td> <td>15</td> </tr> <tr> <td>Ratio R</td> <td>0.350</td> <td>Longest Storm (mins)</td> <td>10080</td> </tr> <tr> <td>Summer Storms</td> <td>Yes</td> <td>Climate Change %</td> <td>+40</td> </tr> </table> <u>Time Area Diagram</u> Total Area (ha) 0.030 <table> <thead> <tr> <th>Time (mins)</th> <th>Area</th> <th>Time (mins)</th> <th>Area</th> </tr> <tr> <th>From: To:</th> <th>(ha)</th> <th>From: To:</th> <th>(ha)</th> </tr> </thead> <tbody> <tr> <td>0 4</td> <td>0.022</td> <td>4 8</td> <td>0.008</td> </tr> </tbody> </table>			Rainfall Model	FSR	Winter Storms	Yes	Return Period (years)	100	Cv (Summer)	0.750	Region	England and Wales	Cv (Winter)	0.840	M5-60 (mm)	19.500	Shortest Storm (mins)	15	Ratio R	0.350	Longest Storm (mins)	10080	Summer Storms	Yes	Climate Change %	+40	Time (mins)	Area	Time (mins)	Area	From: To:	(ha)	From: To:	(ha)	0 4	0.022	4 8	0.008
Rainfall Model	FSR	Winter Storms	Yes																																			
Return Period (years)	100	Cv (Summer)	0.750																																			
Region	England and Wales	Cv (Winter)	0.840																																			
M5-60 (mm)	19.500	Shortest Storm (mins)	15																																			
Ratio R	0.350	Longest Storm (mins)	10080																																			
Summer Storms	Yes	Climate Change %	+40																																			
Time (mins)	Area	Time (mins)	Area																																			
From: To:	(ha)	From: To:	(ha)																																			
0 4	0.022	4 8	0.008																																			
©1982-2020 Innovyze																																						

The Civil Engineering Practice		Page 4																				
11 Tungsten Building George Street Fishersgate BN41 1RA	Manor Nursery Angmering West Sussex																					
Date 23/09/2020	Designed by S Burgess																					
File Soakaway 4 Factor Safet...	Checked by SRD																					
Innovyze		Source Control 2020.1																				
<u>Model Details</u> Storage is Online Cover Level (m) 16.400 <u>Lined Soakaway Structure</u> <table> <tr> <td>Infiltration Coefficient Base (m/hr)</td> <td>0.00000</td> <td>Ring Diameter (m)</td> <td>2.00</td> </tr> <tr> <td>Infiltration Coefficient Side (m/hr)</td> <td>0.72360</td> <td>Pit Multiplier</td> <td>1.4</td> </tr> <tr> <td>Safety Factor</td> <td>4.0</td> <td>Number Required</td> <td>2</td> </tr> <tr> <td>Porosity</td> <td>0.30</td> <td>Cap Volume Depth (m)</td> <td>2.500</td> </tr> <tr> <td>Invert Level (m)</td> <td>13.900</td> <td>Cap Infiltration Depth (m)</td> <td>0.350</td> </tr> </table>			Infiltration Coefficient Base (m/hr)	0.00000	Ring Diameter (m)	2.00	Infiltration Coefficient Side (m/hr)	0.72360	Pit Multiplier	1.4	Safety Factor	4.0	Number Required	2	Porosity	0.30	Cap Volume Depth (m)	2.500	Invert Level (m)	13.900	Cap Infiltration Depth (m)	0.350
Infiltration Coefficient Base (m/hr)	0.00000	Ring Diameter (m)	2.00																			
Infiltration Coefficient Side (m/hr)	0.72360	Pit Multiplier	1.4																			
Safety Factor	4.0	Number Required	2																			
Porosity	0.30	Cap Volume Depth (m)	2.500																			
Invert Level (m)	13.900	Cap Infiltration Depth (m)	0.350																			
©1982-2020 Innovyze																						