

ASHDOWN SITE INVESTIGATION

L · I · M · I · T · E · D

E-mail: contact@ashdownsi.co.uk
Web: www.ashdownsi.co.uk
Tel: 01273 483119

Site Name: Manor Nursery, Angmering, West Sussex

Job Number: R18-13430

Start Date: 05/12/2018

End Date: 05/12/2018

Borehole Number: **WS101**

Sheet 1 of 1

Samples and In Situ Testing					Legend	Depth	Stratum Description
Standpipe	Sample/ Test Type	Depth From (m)	Depth To (m)	Test Result			
	D	1.00				0.00	MADE GROUND: Sandy subangular to subrounded fine to coarse gravel.
						0.20	Brown silty CLAY. (River Terrace Deposits)
						1.10	Brown gravelly silty CLAY. Gravel is subangular to subrounded fine to medium flint. (River Terrace Deposits)
	D	2.00				1.90	Brown very silty subangular to subrounded fine to coarse GRAVEL of chalk and flint. (River Terrace Deposits)
	D	3.00				3.10	Off white very silty subangular to subrounded fine to medium GRAVEL of chalk and flint. (River Terrace Deposits)
	D	4.00				4.10	Orange very silty subangular to subrounded fine to medium GRAVEL of chalk and flint. (River Terrace Deposits)
	D	5.00				5.00	End of borehole at 5.00m

Remarks Groundwater: Borehole dry on completion. Stability: Borehole stable on completion. Notes: Standpipe installed to 5.00m depth; 5.00m to 2.00m slotted pipe with gravel surround; 2.00m to ground level plain pipe with bentonite seal; completed with end cap and security cover concreted flush with ground surface.	Excavation Method: WLS
	Borehole Diameter: Various
	Made By: KK

Site Name: Manor Nursery, Angmering, West Sussex




Job Number: R18-13430

Start Date: 05/12/2018

End Date: 05/12/2018

Borehole Number: **WS102**

Sheet 1 of 1

Standpipe		Samples and In Situ Testing				Legend	Depth	Stratum Description
Sample/ Test Type	Depth From (m)	Depth To (m)	Test Result					
D	1.00					0.00	MADE GROUND: Sandy subangular to subrounded fine to coarse gravel.	
						0.20	Light brown silty CLAY. (River Terrace Deposits)	
D	2.00					1.50	Brown gravelly silty CLAY. Gravel is subangular to subrounded fine to medium flint. (River Terrace Deposits)	
						2.10	Light brown silty subangular to subrounded fine to medium GRAVEL of flint and chalk. (River Terrace Deposits)	
D	3.00					3.30	Off white silty subangular to subrounded fine to coarse GRAVEL of flint and chalk. (River Terrace Deposits)	
						4.10	Brown sandy subangular to subrounded fine to coarse GRAVEL of flint. Sand is fine to coarse. (River Terrace Deposits)	
D	5.00					4.70	Orange sandy subangular to subrounded fine to coarse GRAVEL of flint. (River Terrace Deposits)	
						5.00	End of borehole at 5.00m	

Remarks

Groundwater: Borehole dry on completion.

Stability: Borehole stable on completion.

Notes: Standpipe installed to 5.00m depth; 5.00m to 2.00m slotted pipe with gravel surround; 2.00m to ground level plain pipe with bentonite seal; completed with end cap and security cover concreted flush with ground surface.

Excavation Method: WLS

Borehole Diameter:	Various
---------------------------	---------

Made By: KK

